

FINAL

# NAPL Recovery Construction Completion Report, Quanta Resources Corporation Superfund Site, Edgewater, New Jersey

*Prepared for*  
Honeywell International Inc.

January 2017



CH2M HILL Engineers, Inc.  
18 Tremont Street Suite 700  
Boston, MA 02108

# Contents

Section	Page
<b>Acronyms and Abbreviations .....</b>	<b>v</b>
<b>1      Introduction .....</b>	<b>1-1</b>
1.1     Site Background and History.....	1-1
1.2     Objectives and Design Summary .....	1-1
<b>2      Project Execution.....</b>	<b>2-1</b>
2.1     Permit Equivalency .....	2-1
2.2     Construction Activities.....	2-1
2.2.1    Mobilization and Site Preparation .....	2-1
2.2.2    Safety Considerations .....	2-2
2.2.3    Recovery and Monitoring Well Installation .....	2-2
2.2.4    Recovery and Monitoring Well Development .....	2-3
2.2.5    Deviations from Design.....	2-3
2.3     Gauging and Bail Down Testing .....	2-5
2.3.1    Initial Gauging .....	2-5
2.3.2    Initial Bail-down Testing .....	2-7
2.3.3    Deviations from Gauging and Bailedown Design.....	2-8
2.4     Sample Collection and Analysis .....	2-9
2.5     Waste Management .....	2-11
<b>3      Data Evaluation .....</b>	<b>3-1</b>
<b>4      Recommendations.....</b>	<b>4-1</b>
4.1     Operating Recommendations.....	4-1
4.2     Deep NAPL Monitoring Wells .....	4-1
4.2.1    TW-01 Rehabilitation .....	4-2
4.2.2    NZ-4 Sentry Well Construction .....	4-2
4.3     O&M and Reporting Schedule .....	4-2
<b>5      References.....</b>	<b>5-1</b>

## Appendices

- A      Boring Logs and Well Construction Details
- B      Transducer Data and Transmissivity Calculations
- C      NAPL Physical Parameters Lab Report
- D      Waste Characterization and Disposal

## Attachment

- A      Equipment Specifications and Manuals

## Tables

- 2-1     Well Construction Summary
- 2-2     Monitoring and Recovery Well Gauging Data
- 2-3     Recovered NAPL Volumes During Initial Bailedown Test

CONTENTS

- 2-4 NAPL and Groundwater Physical Properties at Recovery Wells
- 3-1 Baseline Transmissivity Values
- 4-1 Recommended Operating Conditions
- 4-2 Operations Schedule

**Figure**

- 2-1 NZ-3 Deep NAPL Recovery and Monitoring Well Layout
- 2-2 NZ-4 Deep NAPL Recovery and Monitoring Well Layout
- 2-3 NZ-6 Deep NAPL Monitoring Well Location
- 2-4 NAPL Recovery Well and Vault Detail

# Acronyms and Abbreviations

amsl	above mean sea level
btoc	below top of casing
cP	centipoise
EPA	U.S. Environmental Protection Agency
ft bgs	feet below ground surface
g/mL	grams per milliliter
ISS	in situ solidification/stabilization
N.J.A.C.	New Jersey Administrative Code
NAPL	dense nonaqueous phase liquid
NJDEP	New Jersey Department of Environmental Protection
NZ	NAPL zone
O&M	operations and maintenance
OU	Operable Unit
PID	photoionization detectors
PPE	personal protective equipment
PVC	polyvinyl chloride
RD/RAWP	remedial design and remedial action work plan
ROD	Record of Decision

# Introduction

This construction completion report documents the dense nonaqueous phase liquid (NAPL) recovery system construction activities performed from July 20, 2015, through October 2015 at Operable Unit (OU) 1 of the Quanta Resources Corporation Superfund site, in Edgewater, New Jersey. The construction and startup was performed in accordance with the Remedial Design and Remedial Action Work Plan (RD/RAWP) (CH2M, 2015) that was approved by the U.S. Environmental Protection Agency (EPA) on April 8, 2015. Deviations from the RD/RAWP are detailed in Section 2.9 of this report.

Data collected as part of the initial startup testing have allowed for the determination of appropriate pumping schedules for NAPL recovery wells to be operated and for the establishment of baseline transmissivity values at the new recovery wells. Sentry wells have been installed and will be monitored as specified in the operations and maintenance (O&M) plan portion of the RD/RAWP.

This report summarizes the field construction activities, observations, field data, sample collection, laboratory analytical data, and data calculations. Recommendations for regular NAPL recovery operations and for the location of the additional sentry well are presented.

## 1.1 Site Background and History

The site is adjacent to the Hudson River, in Bergen County, in northeastern New Jersey. The area of OU1, as defined in the Record of Decision (ROD) (EPA, 2011), is approximately 24 acres and comprises a vacant lot referred to as “the Quanta property,” portions of River Road and Gorge Road, and properties and portions of properties surrounding the Quanta property. Surface water and sediment in the Hudson River are designated OU2 and are being investigated as part of an ongoing Remedial Investigation/Feasibility Study that is separate from this response action. Details on the site background are provided in the remedial investigation report (CH2M, 2008). Site background information including stratigraphy and definition of source areas including NAPL zones are provided in the final RDWP (CH2M, 2014a). A depiction of the NAPL zones is included in the RD/RAWP for NAPL recovery (CH2M, 2015, Figure 1-3).

The selected remedy described in the ROD “involves the solidification/stabilization of NAPL and arsenic source areas, capping and institutional controls, coupled with the installation of a groundwater containment remedy, a subaqueous reactive barrier in the Hudson River to mitigate contaminated groundwater releases” (p. 91). For deep NAPL, the ROD (p. 96) requires “[t]reatment of a portion of the Deep NAPL through ISS [in situ solidification/stabilization], passive NAPL collection for other areas of the Deep NAPL, and long-term monitoring.” The complete remedy meets the intent of the ROD and will effectively achieve the remedial action objectives for media at the site.

A draft Basis of Design report (CH2M, 2014b) was submitted to EPA on May 30, 2014, and a meeting was held on July 22, 2014, to discuss its contents. Parties at the meeting agreed to look at the potential to accelerate the NAPL recovery portion of the remediation to initiate recovery efforts as soon as possible. Therefore, the RD/RAWP for the NAPL recovery portion of the remedy was prepared separately from and in advance of the RD and RAWP for the remaining portions of the remedy. The RD/RAWP for NAPL recovery was approved by EPA in April 2015, and construction began in July 2015. Remedial design and construction of remaining portions of the remedy other than NAPL recovery will be presented under separate cover.

## 1.2 Objectives and Design Summary

The purpose of the work discussed below was to create a NAPL recovery system consisting of vertical recovery wells with sumps for in-well NAPL accumulation. The overall objective is to remove the NAPL from the sumps at a recovery-well-specific frequency that maximizes NAPL recovery. Downgradient monitoring

wells will act as test points to assure that the NAPL footprint remains stable and is not migrating, which will be assumed by the absence of recoverable NAPL within these wells.

The bulk of the NAPL, associated with several NAPL zones (NZs), will be addressed through ISS. The areas targeted for ISS are the shallow NZs: NZ-1, NZ-2, NZ-5, and a portion of NZ-3 referred to as the Stacked Area. The selected remedy for the remaining areas of deeper NAPL (portions of NZ-3, NZ-4, and NZ-6) is “passive NAPL collection... and long-term monitoring” (ROD, p. 96):

- “For remaining areas of NZ-3 and NZ-4, free-phase NAPL collection from recovery wells or recovery trenches will be performed, to the extent practicable” (ROD p. 96) and
- “No free-phase NAPL collection is anticipated for NZ-6, because no free-phase liquids have been observed that could be collected. If monitoring of NZ-6 identifies free-phase NAPL in the future, EPA will reevaluate the need for adding this deep NAPL remedy component in NZ-6” (ROD p. 97).

As stated in the final RDWP (CH2M, 2014a), the objective of deep NAPL recovery is to remove, where practicable, NAPL having the potential for future migration. Deep NAPL recovery is neither intended to nor expected to materially improve groundwater quality, due to the site-specific and contaminant-specific factors detailed in the Technical Impracticability Evaluation report (CH2M, 2010a).

The passive NAPL recovery system consists of vertical recovery wells in NZ-3 and NZ-4 with sumps for in-well NAPL accumulation. The basis of design, design details, and O&M plan for the NAPL recovery component of the overall remedy at the site are detailed in the RD/RAWP (CH2M, 2015). In general, the NAPL will be removed using the dedicated pump, at a frequency based on startup testing results and specified in Section 4.1. The results from periodic bail-down tests during O&M will be used to calculate NAPL transmissivity for each recovery well. Using the transmissivity value at each well, gauging data, and other site observations, the progress of each location toward its recovery endpoint will be evaluated on a quarterly basis. Data from deep NAPL recovery operations and monitoring will be evaluated on a regular basis to assess the effectiveness of the recovery system, and documented in annual reports along with any recommendations.

# Project Execution

The NAPL recovery construction was performed in accordance with the RD/Rawp (CH2M, 2015), with the exception of the minor deviations listed in Section 2.9. The work included the installation of four recovery wells and two monitoring wells identified in Section 2.4. These wells were then gauged and, based on gauging results (wells containing NAPL thicknesses which are more than 0.5 feet above the top of the well sump), a subset were selected for NAPL bail-down testing. Bail-down testing was performed to obtain data on the transmissivity of the NAPL to assess the best possible pumping frequency for the NAPL.

CH2M provided oversight for the field operations throughout the course of the field construction activities, which included recovery well installation and development. Details of daily construction activities were documented in a field logbook, and photographs of the various activities were taken throughout the project. The following summarizes field activities from mobilization through demobilization.

## 2.1 Permit Equivalency

No Coastal Zone Permit equivalency was required for this portion of work. Locations of the recovery and monitoring wells are outside of the jurisdiction of the Coastal Permit Program Rules and the Coastal Zone Management Rules, codified under New Jersey Administrative Code (N.J.A.C.) 7:7 and N.J.A.C. 7:7E, respectively. Construction activities occurred over 500 feet landward of the mean high-water line. Hazardous waste (that is, NAPL collected during NAPL recovery) and hazardous substances (as defined in Spill Compensation and Control Act, New Jersey Statutes Annotated 58:10–23.11) will be stored outside the area of 1 percent chance of flood.

In accordance with the Freshwater Wetlands Protection Act Rules (N.J.A.C. 7:7A), a Letter of Interpretation was prepared and submitted to the New Jersey Department of Environmental Protection (NJDEP) on June 26, 2014, indicating that no freshwater wetlands are present onsite. A site visit from NJDEP to confirm those findings was performed on August 26, 2014, and on September 9, 2014, the letter was approved.

## 2.2 Construction Activities

### 2.2.1 Mobilization and Site Preparation

The following mobilization and site preparation activities were completed prior to construction:

- **Health and Safety Review.** Health and safety training documentation from all subcontractors was sent to CH2M and reviewed and accepted by the health and safety manager.
- **Access.** Access to the Quanta, 115 River Road, Block 93 South, and iPark properties, necessary for construction and operation of the NAPL recovery system, was obtained.
- **Preconstruction Meeting.** A preconstruction meeting was held on July 20, 2015, to discuss the project schedule and the work activities, conduct initial task coordination with site personnel, and introduce personnel working on the project. A roster of all field personnel, additional contacts, and regulatory contacts was prepared and distributed afterward. Attendees included:
  - **CH2M** – Taylor Salsburg
  - **Hager Richter** – Jose Cambero
  - **Cascade Drilling** – Jon Weeks and Ben Grim
  - **HDR (EPA Oversight Contractor)** - Jiss Philip

- **Site Setup.** Mobilization activities included transporting personnel, equipment, materials, supplies, instruments, and subcontracted services required to implement the necessary actions. CH2M mobilized with the drilling subcontractor, Cascade Drilling, to initiate site preparation on July 20, 2015. This included establishing site controls, such as caution tape, signage, perimeter privacy fencing, and construction barricades for construction safety and security. CH2M-designated space within the fenced area of the Quanta site was used as a staging area for the duration of the field work.
- **Utility Clearance.** Hager Richter was also present onsite on July 20, 2015, to perform a utility search and mark-out. A 5-foot-by 5-foot area around each proposed boring was scanned for the presence of subsurface utilities using a combination of ground penetrating radar, electromagnetic conductance, and magnetics.

## 2.2.2 Safety Considerations

CH2M and onsite contractors were responsible for complying with Occupational Safety and Health Administration regulations, Honeywell's Health and Safety Program, NJDEP permit equivalents, and CH2M's Health, Safety, and Environment Program. The following specific safety-related activities took place during the field work.


- The HASP was reviewed and signed by all onsite project members
- Health and safety certifications for each onsite person were compiled by the field team leader prior to mobilization
- AHAs were developed for each work task and reviewed with the field personnel before the work was started
- Daily safety meetings were held every morning with all field personnel prior to the commencement of that day's field activities; relevant safety topics were addressed and the health and safety plan was reviewed
- Photoionization detectors (PIPs) and dust detectors were used to monitor the breathing zone of staff collecting and processing any soil samples and in areas of intrusive work
- Level D personal protective equipment (PPE) was used during onsite field activities; steel-toed boots, safety goggles, and nitrile gloves were worn, and TyChem suits and hearing protection were used when necessary
- Fire extinguishers, spill kits, chilled water and Gatorade, and ice were maintained in the area of operations (due to extreme heat during the event)


## 2.2.3 Recovery and Monitoring Well Installation


Monitoring and recovery wells were installed between July 20 and July 30, 2015, by Cascade Drilling and CH2M after Cascade obtained the requisite well drilling permits from NJDEP. Form As and Form Bs are included in Appendix A. New monitoring and recovery wells are shown with prior existing recovery and monitoring wells on Figure 2-1, 2-2, and 2-3 for NZ-3, NZ-4, and NZ-6, respectively. Figure 2-4 presents a diagram of the typical recovery/monitoring well construction.

Prior to the installation of each new recovery and monitoring well, a soil boring was drilled. Continuous soil cores were collected using a 5-foot long minisonic sampler and logged in the field. Borings were advanced to the depths of the clay or peat layer (that is, the NAPL confining layer) at each location. The soil was screened with a PIP. Visual observation was used to verify the depth of the NAPL confining layer into which the monitoring or recovery well sump was set.

Boreholes were generally completed when they reached 6 feet below the surface of the NAPL confining layer. The interface was defined by two criteria, both of which needed to be satisfied: (1) the transition








© CH2M HILL 2012. ALL RIGHTS RESERVED.  
USE OF DOCUMENTS: CH2M HILL AND NOT ITS BELIEVED IN WHOLE OR IN PART FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CH2M HILL.

© CH2M HILL 2012. ALL RIGHTS RESERVED.



**FIGURE 2-4**  
**NAPL RECOVERY WELL AND**  
**VAULT DETAIL**  
**QUANTA RESOURCES CORPORATION**  
**SUPERFUND SITE**  
**Edgewater, New Jersey**

# RECOVERY WELL VAULT PLAN

## RECOVERY WELL VAULT ELEVATION

**CH2MHILL®**

from soils with some NAPL saturation to soil with no NAPL saturation, and (2) the transition from coarser-grain soils (native sand or gravelly fill) to lower permeability grey silty clay or peat layers. Boring logs are attached as Appendix A.

New monitoring and recovery wells were installed within their associated borings generally in accordance with the design presented in the RD/RAWP (CH2M, 2015). Minor design variations are indicated in Section 2.10. Each location was a 4-inch-diameter well screened across the entire interval where deep NAPL was present and the bottom of the screen interval was set in the top of the confining layer. Continuous slot (wire-wrap) 0.02-inch slot size screens were used at lengths ranging from 5 to 15 feet, and each well was constructed with a 2- or 5-foot sump at the base of the screen that was sealed in cement grout to allow for the storage of NAPL and efficient operation of the passive recovery system. The sump was grouted into place to direct NAPL flows into the well and not into the area around the sump.

Surface completion consisted of a steel construction-traffic-rated flush-mount vault/road box with a steel cover with recessed handle. Four bolts are used to fasten the vault box closed when not in use. The vault box is anchored in the ground by concrete. Well construction diagrams are attached as Appendix A.

## 2.2.4 Recovery and Monitoring Well Development

After well installation, at least 48 hours elapsed before development activities could begin at each well to allow the grout to set. Cascade Drilling conducted the well development on July 29, 2015 and July 30, 2015. A Waterra Pump was used to surge and purge the wells; two surge blocks were anchored onto the Waterra's rigid poly tubing, one at the base and the other approximately 4 feet above the base. These surge blocks disturb the formation while the Waterra simultaneously purges the well water/NAPL directly into 55-gallon drums. Surging and purging started at the base of the sump and worked upwards to the top of the screen. A minimum of three well volumes were purged from each well, and continued to be surged and purged until turbidity visually cleared. A total of 90 gallons to 128 gallons of NAPL and water was purged from each well and disposed offsite as discussed in Section 2.5.

## 2.2.5 Deviations from Design

The following list summarizes deviations from scope of work defined in the RD/RAWP:

- Well construction details and borehole depths were adjusted from the RD/RAWP estimates based on field conditions. Actual screen placements are noted in Table 2-1.
- Sumps were grouted into place to direct NAPL flows into the well and not into the area around the sump, rather than using a cementing basket. At MW-400, #00 sand was used to avoid the potential for grout to foul the shorter (5-foot) screen at this location.
- MW-402 is considered a recovery well as opposed to a monitoring well due to the observation of sufficient NAPL in the well to conduct a bail-down test. A new sentry well is planned, as noted in Section 4.
- RW3-2, RW3-3, and RW3-4 are considered deep NAPL monitoring wells since insufficient NAPL has been observed to conduct a bail-down test. In the event that sufficient NAPL enters these wells, a bail-down test will be conducted.
- This construction completion report is being submitted in advance of installation of a new sentry well at NZ-4 so that regular operations and evaluations at the recovery wells may commence. Well construction information for the new sentry well will be included in the quarterly data transmittal following its installation.

**Table 2-1. Well Construction Summary**  
*Quanta Resources Corporation Superfund Site*

Well ID	Type of Well	Status	Slot Size (inches)	Well Diameter (Inches)	Screen (ft bgs)		Sump Length (ft)	Total Depth (ft bgs)	Lithology in Screen Interval
					Top	Bottom			
RW3-2	Monitoring	New	0.02	4	13	23	5	28	Fine to medium sand
MW-126	Monitoring	Installed in 2008	—	—	—	—	—	—	—
RW3-3	Monitoring	New	0.02	4	12	22	5	27	Fine sand, varved clay at base
RW3-4	Monitoring	New	0.02	4	13	23	5	28	Fine silty sand and fine sand
MW-121B	Monitoring	Installed in 2006	0.02	4	12	22	2	24	Medium/gravelly sand; silty clay at 20 ft bgs
RW3-1 (MW-130B)	Recovery	Installed in 2008	0.02	2	15	25	2	27	Native sand and silty clay
RW3-5	Recovery	New	0.02	4	9	24	5	29	Fine to medium sand; clayey silt at 23 ft bgs
MW-400	Monitoring	New	0.02	4	29	34	2	36	Fine to medium sand; grey, clayey silt at 33.2 ft bgs
MW-401	Monitoring	Planned (installation following full-scale construction)	0.02	4	17	27	5	32	Native sand and silty clay expected
TW-01 <sup>a</sup>	Monitoring	Predesign	0.03	4	17	27	2	29	Unknown; refusal at 6 ft bgs
RW4-1 (MW-123)	Recovery	Installed in 2008	0.02	4	6	16	2	18	Fill and gravelly sand; clayey peat at 15 ft bgs
RW4-2 (MW-402)	Recovery	New	0.02	4	6	16	5	21	Fine to medium sand and gravel; peat at 15 ft bgs
MW-410A	Monitoring	Recommended installation spring 2016	—	—	—	—	—	—	—

<sup>a</sup>TW-01 is currently missing; a construction entrance was placed over this location during redevelopment of the iPark site. See Section 4.2.2 for additional information.

## 2.3 Gauging and Bail Down Testing

### 2.3.1 Initial Gauging

Starting one week after development, newly-installed NAPL recovery wells and monitoring wells were gauged approximately weekly for up to 8 weeks depending on well conditions, to determine which wells contained sufficient NAPL to allow for bail-down testing. Data were also reviewed to determine when static conditions were reached; in general, this was defined as three consecutive measurements where NAPL thickness (water/NAPL interface) varied by 10 percent or less. Measurements of NAPL thickness were taken using an oil–water interface probe to determine the depth to NAPL and the total depth of the recovery well, subtracting one from the other to determine the in-well NAPL thickness.

Recovery and monitoring wells were gauged up to seven times between August 5 and October 1, 2015. Gauging data are presented in Table 2-2.

**Table 2-2. Initial Monitoring and Recovery Well Gauging Data**

*Quanta Resources Corporation Superfund Site*

Well ID	Date	Measuring Point Elevation (ft amsl)	Total Depth (ft btoc)	Depth to Water (ft btoc)	Water Elevation (ft amsl)	Depth to NAPL (ft btoc)	NAPL Thickness (ft)
<b>NZ-3</b>							
MW-121B	8/5/2015	7.16	23.94	3.67	3.49	23.94	Trace
	8/12/2015	7.16	23.94	3.56	3.60	23.94	Trace
	10/1/2015	7.16	NM	3.64	3.52	23.94	Trace
MW-400	8/5/2015	6.742	35.10	3.29	3.45	—	—
	8/12/2015	6.742	35.10	3.28	3.46	—	—
	8/19/2015	6.742	35.10	3.39	3.35	—	—
	8/26/2015	6.742	35.10	3.48	3.26	—	—
	9/3/2015	6.742	35.15	3.40	3.34	35.15	Trace
	9/11/2015	6.742	35.10	NM	NM	—	—
	10/1/2015	6.742	35.10	3.34	3.40	—	—
RW3-1 (MW-130B)	8/5/2015	6.47	24.95	3.02	3.45	20.71	4.24
	9/2/2015	6.47	24.95*	3.10	3.37	20.49	4.46
	9/16/2015	6.47	NM	NM	NM	20.42	—
	10/1/2015	6.47	24.95	2.95	3.52	21.83	3.12
RW3-2	8/5/2015	5.298	27.12	1.52	3.78	26.64	0.48
	8/12/2015	5.298	27.12	1.44	3.86	26.50	0.62
	8/19/2015	5.298	27.12	1.23	4.07	26.15	0.97
	8/26/2015	5.298	27.12	1.65	3.65	27.12	Trace
	9/3/2015**	5.298	27.11	2.70	2.60	18.95	8.16

**Table 2-2. Initial Monitoring and Recovery Well Gauging Data**  
*Quanta Resources Corporation Superfund Site*

Well ID	Date	Measuring Point		Depth to Water (ft btoc)	Water Elevation (ft amsl)	Depth to NAPL (ft btoc)	NAPL Thickness (ft)
		Elevation (ft amsl)	Total Depth (ft btoc)				
	9/11/2015	5.298	27.12	NM	NM	27.12	Trace
	10/1/2015	5.298	NM	1.51	3.79	27.12	Trace
RW3-3	8/5/2015	5.607	25.85	1.86	3.75	—	—
	8/12/2015	5.607	25.85	1.79	3.82	—	—
	8/19/2015	5.607	25.85	1.83	3.78	—	—
	8/26/2015	5.607	25.85	1.98	3.63	—	—
	9/3/2015	5.607	25.75	2.06	3.55	—	—
	10/1/2015	5.607	NM	1.82	3.79	—	—
RW3-4	8/5/2015	6.900	23.10	3.33	3.57	—	—
	8/12/2015	6.900	23.10	3.25	3.65	—	—
	8/19/2015	6.900	23.10	3.30	3.60	—	—
	8/26/2015	6.900	23.10	3.42	3.48	—	—
	9/3/2015	6.900	22.00	3.47	3.43	—	—
	10/1/2015	6.900	NM	3.34	3.56	—	—
RW3-5	8/5/2015	6.435	25.86	2.95	3.49	20.74	5.12
	8/12/2015	6.435	25.86	2.87	3.57	20.30	5.56
	8/19/2015	6.435	25.86	2.86	3.58	20.10	5.76
	8/26/2015	6.435	25.86	3.05	3.39	20.15	5.71
	9/2/2015	6.435	26.70	3.12	3.32	19.98	6.72
	9/3/2015	6.435	26.70	3.07	3.37	25.15	1.55
	9/16/2015	6.435	NM	NM	NM	19.97	6.73
	10/1/2015	6.435	NM	2.93	3.51	19.95	6.75
<b>NZ-4</b>							
RW4-1 (MW-123)	8/5/2015	5.54	17.40	2.89	2.65	11.90	5.50
	9/2/2015	5.54	17.32	2.95	2.59	11.04	6.28
	9/2/2015	5.54	17.32	2.98	2.56	16.27	1.05
	9/3/2015	5.54	17.32	3.00	2.54	15.79	1.53
	9/16/2015	5.54	NM	NM	NM	11.82	5.50
	10/1/2015	5.54	NM	2.68	2.86	11.34	5.98
	8/5/2015	6.159	20.20	3.70	2.46	12.25	7.95

**Table 2-2. Initial Monitoring and Recovery Well Gauging Data**  
*Quanta Resources Corporation Superfund Site*

Well ID	Date	Measuring Point Elevation (ft amsl)	Total Depth (ft btoc)	Depth to Water (ft btoc)	Water Elevation (ft amsl)	Depth to NAPL (ft btoc)	NAPL Thickness (ft)
RW4-2 (MW-402)	8/12/2015	6.159	20.20	3.75	2.41	12.38	7.82
	8/19/2015	6.159	20.20	3.80	2.36	12.41	7.79
	8/26/2015	6.159	20.20	3.80	2.36	12.40	7.80
	9/2/2015	6.159	20.15	3.54	2.62	11.95	8.20
	9/3/2015	6.159	20.15	3.71	2.45	12.11	8.04
	9/16/2015	6.159	NM	NM	NM	12.10	8.05
	10/1/2015	6.159	NM	3.71	2.45	12.20	7.95
<b>NZ-6</b>							
MW-126	8/12/2015	13.87	19.95	9.40	4.47	—	—

—, NAPL not observed, amsl, above mean sea level; btoc, below top of casing; DNAPL, dense nonaqueous phase liquid; NM, not measured, trace, <0.01 ft thickness or blebs observed on the probe.

\*Total depth reading at RW3-1 of 24.30 ft btoc was not used for calculations; prior total depth of 24.95 ft btoc was used.

\*\*September 3, 2015 measurements at RW3-2 are believed to be erroneous.

### 2.3.2 Initial Bail-down Testing

Gauging results determined which wells contained a thickness of NAPL sufficient for bail-down testing<sup>1</sup>: RW3-1, RW3-5, RW4-1/MW-123, and RW4-2/MW-402. Bail-down test measurements were taken on September 2, 2015 at all four of these wells, and again on October 1, 2015 at RW3-1 and RW4-2/MW-402. Transmissivity calculations were performed in accordance with the RD/RAWP for NAPL recovery (CH2M, 2015), except where noted below.

Depth to water, total well depth, and depth to NAPL were measured with a Solinst, Model 122 oil–water interface probe. Following these measurements, dedicated equipment was prepared for installation into the selected wells. A QED stainless steel Pulse Pump bottom-loading pneumatic pump and two In-Situ Level Troll, Model 500 pressure transducers were used in each well (one at the base of the well within the NAPL column and a second within the water column above the NAPL–water interface) to collect data that would allow for the estimation of in-well NAPL thicknesses over time. Manufacturer’s manuals for this equipment is included as Attachment A to this report. Measurements were made so that the pump intake was 12 inches from the bottom of the sump, the deep transducer was placed 9 inches from the bottom of the sump (or approximately 3 inches below the pump intake), and the shallow transducer was 48 inches below the static water table. Both the transducers and the pump were affixed to the 1-inch polyvinyl chloride (PVC) pipe inside the well at their respective distances using zip ties to ensure a limited movement. A schematic showing the typical pressure transducer configuration used during bail-down testing is presented in Figure 2-4).

After it had been determined that the wells had reached static conditions the installation of equipment, and initial bail-down tests was conducted the week of August 31, 2015, at wells RW3-1, RW3-5, RW4-1/MW-123,

<sup>1</sup> NAPL thicknesses which are more than 0.5 feet above the top of the well sump are sufficient for baildown testing.

and RW4-2/MW-402,. Transducers were started, the volume of removable NAPL was calculated, and then NAPL pumping was performed until the top of the measured NAPL was lowered to the pump's intake. The thickness of NAPL was measured periodically after the pump was shut off, as NAPL flowed into the well from the formation and adjacent sand pack.

NAPL and groundwater surface elevations were measured via timed manual measurements with an oil–water interface probe, and also by the in-well pressure transducers that were used to take more-frequent measurements for longer durations than would not be practicable using solely a manual measurement approach. Appendix B summarizes raw results and provides field measurements and graphical representations of the transducer data for RW3-1, RW3-5, RW4-1/MW-123, and MW-402.

The following are the general procedures that were conducted for bail-down testing:

1. Start the transducer data logging
2. Measure the initial depth to groundwater, NAPL thickness, and the total well depth
3. Calculate the volume of removable NAPL in the well and sand pack
4. Record the time pumping starts and stops as indicated on the data logger
5. Remove NAPL using the dedicated QED Pulse Pump, pump the NAPL into 5-gallon buckets to allow accurate measurement of the volume removed, and record the total volume of NAPL removed
6. Immediately following NAPL removal and pump shut-off, measure the depth to NAPL using the interface probe; collect periodic manual measurements of NAPL thickness to verify transducer data
7. Download transducer data during a subsequent gauging/bail-down field event
8. Manage waste as discussed in Section 2.5

Table 2-3 presents the total volume of NAPL removed during the prior pre-design baildown tests and initial baildown test.

**Table 2-3. Recovered NAPL Volumes During Baildown Tests**

*Quanta Resources Corporation Superfund Site*

Recovery Well ID	Predesign Baildown Testing (Nov 2012-Jan 2013)	Predesign Baildown Testing (Mar-Apr 2014)	Initial Baildown Test (Sep-Oct 2015)
RW3-1	Average 1.6 gallons per test, 15.75 gallons total	Average 0.7 gallons per test, 6.16 gallons total	0.6 gallons
RW3-5	Not yet installed	Not yet installed	3.75 gallons
RW4-1	Average 4.0 gallons per test, 44.6 gallons total	Average 2.9 gallons per test, 25.9 gallons total	3.7 gallons
RW4-2	Not yet installed	Not yet installed	4.0 gallons

### 2.3.3 Deviations from Gauging and Baildown Design

The following changes or challenges were documented during the bail-down testing:

- **Gauging outside drop pipe.** Gauging water and NAPL depths through the PVC drop pipe that was installed within the 4-inch recovery wells was demonstrated to be inaccurate in the field. NAPL sticking to the sides of the drop pipe and a delay in equilibration between the drop pipe and the levels in the 4-inch casing were resulting in inaccurate readings. Therefore measurements were taken directly within

the 4-inch casing, and the drop pipe will no longer be used. A drop pipe will not be installed in any future recovery or monitoring wells that may be needed.

- **Insufficient NAPL at planned recovery wells.** At RW3-2, RW3-3, and RW3-4, insufficient NAPL was present to allow bail-down testing.
- **NAPL in a planned monitoring well.** At MW-402 (in NZ-4), NAPL flowed into the monitoring well in sufficient quantities to allow a bail-down test; therefore equipment was installed and a test attempted at this location.
- **MW-130B/RW3-1 manual depth measurements:** At this 2-inch-diameter well, the oil–water interface probe was unable to fit down the well when the pump and two transducers were in place, preventing depth-to-water and depth-to-NAPL readings during the bail-down testing event. On October 1, 2015, the installed equipment was zip-tied to metal rods in an attempt to consolidate equipment within the well and yield more room for measurements. After the consolidation of equipment, a test run was attempted; however, the probe was still unable to fit down the well to the depth of NAPL. As a result, manual measurements are not available for this bail-down test at this location. Historical measurements will need to be used to develop initial operating recommendations for RW3-1. Gauging will be attempted in accordance with the planned O&M schedule. Baildown testing will rely upon transducer data only rather than both transducer data and manual measurements, and these results will be used to determine recommendations for ongoing operations at this well.
- **MW-402 pump failure:** While conducting the September 2, 2015, bail-down test at MW-402, NAPL purging was stopped when NAPL was observed in the airline of the pump, potentially due to the high viscosity of the NAPL. A new pump was installed on October 1, 2015, and a second bail-down test was conducted. The results of the second baildown test are included in Appendix B.

## 2.4 Sample Collection and Analysis

Samples of both groundwater and NAPL were collected at newly installed recovery wells containing NAPL (RW3-5 and MW-402). Groundwater samples for viscosity and density testing were collected using a bailer prior to the installation of any bail-down test equipment and after recovery/monitoring well development and equilibration of water level and NAPL thickness.

Plastic sheeting was placed around the monitoring wells prior to gauging and sampling. Upon the opening of each well, a PID was used to assess the presence of VOCs in the monitoring well headspace and breathing zone. Depth to water and NAPL thickness were gauged and recorded. No excess water was removed from the wells while groundwater samples were collected, and no purging was required prior to sample collection.

A disposable bailer was used to collect a groundwater sample from above the NAPL–water interface from each of the wells. One wide-mouth 16-oz glass jar was used for each groundwater sample.

One sample of NAPL was collected from each of the newly installed recovery wells. These samples were collected at the time of the first bail-down test by directing the flow of NAPL into the laboratory-supplied wide-mouth 16-oz glass jar for each sample. Care was taken to ensure the sample did not contain any groundwater, only NAPL.

The water and NAPL samples were sent to CH2M’s Applied Sciences Laboratory for measurement of viscosity (ASTM D445) and specific-gravity and density (ASTM D1217) at three temperatures (50°, 70°, and 100°F).

At MW-402, the initial NAPL sample was an emulsion of NAPL and water. The ratio was approximately 50/50 NAPL to water. A centrifuge was used to separate the phases and isolate the NAPL. The separated MW-402 NAPL phase (MW-402-NAPL) was then analyzed for specific gravity, density, and viscosity.

Results are presented in Table 2-4, which includes prior results for MW-123 and MW-130B/RW3-1 for reference:

**Table 2-4. NAPL and Groundwater Physical Properties at Recovery Wells**  
*Quanta Resources Corporation Superfund Site*

Sample Name	Matrix	Temperature (°F)	Specific Gravity	Density (g/mL)	Viscosity <sup>a</sup> (cP)
RW3-5-GW	Water	50	1.00	1.00	1.14
		70	1.00	1.00	1.08
		100	1.00	0.99	0.87
MW-402-GW	Water	50	1.01	1.01	1.23
		70	1.00	1.00	1.13
		101	0.99	0.98	0.84
RW3-5-NAPL	NAPL	50	1.06	1.06	7.59
		70	1.05	1.05	5.00
		100	1.05	1.04	3.63
MW-402-NAPL	NAPL	50	1.11	1.11	267
		70	1.11	1.11	110
		100	1.11	1.10	25.3
MW-402-Emulsion	NAPL	50	1.01	1.01	35.3
		70	1.00	1.00	7.51
		100	0.99	0.99	2.38
<b>Previous Results (2013)</b>					
MW123	Water	50	0.99	0.99	1.06
		70.9	0.98	0.98	1.05
		100	0.97	0.96	0.89
MW130B	Water	50	1.03	1.03	1.13
		70.9	1.01	1.01	1.08
		100	1.00	0.99	0.95
MW123B-NP	NAPL	50	1.11	1.11	522
		70.9	1.11	1.11	244
		100	1.11	1.10	83.3
MW130B-NP	NAPL	50	1.06	1.06	15.4
		70.9	1.06	1.06	14.2
		100	1.06	1.05	12.2

**Table 2-4. NAPL and Groundwater Physical Properties at Recovery Wells**  
*Quanta Resources Corporation Superfund Site*

Sample Name	Matrix	Temperature (°F)	Specific Gravity	Density (g/mL)	Viscosity <sup>a</sup> (cP)
-------------	--------	------------------	------------------	----------------	-----------------------------

g/mL, grams per milliliter; cP, centipoise.

Density and specific gravity measured by ASTM D1217.

<sup>a</sup>Groundwater viscosity was measured by ASTM D445 with a glass viscometer. NAPL viscosity was measured with a Brookfield rotational viscometer.

The full analytical deliverables report can be found in Appendix C.

## 2.5 Waste Management

Waste generated was managed as described in the waste management plan (CH2M, 2013, Appendix C). A log of transportation and disposal of the wastes generated from the site is provided in Attachment A-6 including copies of waste disposal profiles, manifests and weight tickets.

Remediation waste was containerized in United Nations-approved 55-gallon, open-top steel drums suitable for transport in accordance with the U.S. Department of Transportation regulations. Drums were labeled with the type of media contained, location of its origin, and date that the waste was generated. Hazardous waste (that is, NAPL and NAPL-impacted waste) was staged outside the flood plain within a Conex box located at the north entrance to the Quanta property. Nonhazardous drums were staged on the Quanta property in a fenced area.

The following waste streams were generated during treatment activities:

- Nonhazardous drilling cuttings and drilling fluids/mud: excess soil (20 drums transported by EQ Northeast to Michigan Disposal Waste Treatment, in Belleville, Michigan) and drilling fluids (2 drums transported by EQ Northeast to EQ Detroit, in Detroit, Michigan).
- Development water and decontamination water containing NAPL were placed in 14 drums and a sample analyzed for offsite disposal. The drums of hazardous water were then transported by EQ Northeast to EQ Detroit, in Detroit, Michigan on October 19, 2015. Analytical results are included in Appendix D.
- General refuse and PPE: PPE with the visual observation of NAPL was placed in drums for offsite disposal. Waste not in contact with NAPL or contaminated media was bagged and put in an onsite waste bin for offsite nonhazardous waste disposal.

All wastes were transported and disposed of in accordance with all applicable federal, state, and local waste management regulations. Waste characterization results and disposal manifests are provided in Appendix D.

# Data Evaluation

Boring logs, well construction details, field gauging results, bail-down test manual measurements, and transducer data were reviewed and evaluated. The results in this section provide the baseline conditions against which subsequent measurements during regular operations will be compared, and allow development of recommendations for O&M activities.

Specific-gravity results were used in the transmissivity calculations for each new recovery well. Specific-gravity data were collected during the predesign investigation for MW-123/RW4-1 and RW3-1 and were used in the calculation of transmissivity at these existing recovery wells. Data from MW-123/RW4-1, MW-130B/RW3-1, and new recovery wells RW3-5 and MW-402/RW4-2 were evaluated to determine the transmissivity of NAPL at each of these locations using methods described in the ASTM standard and modified for DNAPL:

- Bouwer and Rice (1976)
- Cooper and Jacob (1946)
- Cooper et al. (1967)
- Theim Steady State equation

Appendix B includes for each evaluated recovery well a page with the model inputs, including the first several rows of data used in the calculations, figures used to evaluate the transducer data and determine various input parameters for the methods, and summary pages for each of the Bouwer and Rice (1976), Cooper and Jacob (1946), and Cooper et al. (1967) methods. The model input/summary pages present the transmissivity value resulting from each of the three methods, which are also summarized in Table 3-1. Transmissivity could not be calculated at RW3-1 during the startup period due to insufficient space for accurate manual gauging in the 2-inch monitoring well, and a malfunction in the transducer; prior results are reported.

**Table 3-1. Baseline Transmissivity Values**  
*Quanta Resources Corporation Superfund Site*

Recovery Well ID	Transmissivity (ft <sup>2</sup> /day)			
	Bouwer and Rice	Cooper and Jacob	Cooper et al.	Theim
RW3-1 <sup>a</sup>	0.06	0.09	0.06	N/A
RW3-5	0.33	1.3	0.6	1.2
RW4-1	0.08	0.12	0.07	0.15
RW4-2	14	22	10	28

<sup>a</sup>Values shown for RW3-1 (MW-130B) represent measurements from pre-design investigation testing in March 2014. Results for RW4-2 may represent borehole recharge.

The ITRC (2009) document “Evaluating LNAPL Remedial Technologies for Achieving Project Goals” suggests that potential thresholds for transmissivity using recovery technologies range from 0.1 to 0.8 ft<sup>2</sup>/day<sup>2</sup>. For DNAPL the hydraulic recovery endpoint is likely also within this range.

<sup>2</sup> ITRC LNAPL team members’ experience indicates that hydraulic or pneumatic recovery systems can practically reduce transmissivity to values between 0.1 and 0.8 ft<sup>2</sup>/day.

# Recommendations

## 4.1 Operating Recommendations

Table 4-1 below presents observations made during initial gauging and bail down testing relevant to the selection of an initial pumping frequency and baseline conditions for each recovery well.

**Table 4-1. Recommended Operating Conditions**  
*Quanta Resources Corporation Superfund Site*

Recovery Well ID	Recovery	Planned First Quarter Pumping Frequency	Notes
RW3-1 <sup>a</sup>	Returns to static conditions in 1 to 8 days during pre-design investigations. Low baseline transmissivity measured during pre-design investigation (0.06 to 0.09 ft <sup>2</sup> /day).	Weekly	Recommend reinstalling equipment; attempt to improve transducer function to obtain more recent transmissivity measurement during operations.
RW3-5	Returns to static conditions after approximately 5 days.	Weekly	
RW4-1	Returns to static conditions after approximately two weeks.	Weekly	Based on the recovery rate remove NAPL within casing and sump weekly. Measured transmissivity of 0.02 to 0.24 ft <sup>2</sup> /day or less is lower than all values measured in 2012. Evaluate for trends during subsequent baardown tests.
RW4-2	Returns to static conditions within hours	Weekly; consider daily pumping for a set period during operations if these conditions persist.	

<sup>a</sup>Two baardown tests were attempted at RW3-1 but failed to yield usable data to determine transmissivity. Additional attempts to gain a useable baardown test data will occur during ongoing operations, however at this time prior data is being used as a baseline to establish an initial pumping frequency.

The recommended pumping frequencies are based on the most recent successful bail-down test at each location. Subsequent tests may result in modification to these recommended frequencies; changes to pumping frequency will be discussed with EPA prior to modification of the schedule.

## 4.2 Deep NAPL Monitoring Wells

Downgradient deep NAPL monitoring wells provide data to demonstrate that the NAPL zones are stable. In NZ-6, MW-126 is used to confirm the continued lack of recoverable NAPL in this NAPL Zone. In NZ-3, the following wells are currently being used as sentries<sup>3</sup>: RW3-2, RW3-3, RW3-4, MW-121B, and MW-400. Sentry well TW-01 in NZ-3 cannot be located at this time, and may require rehabilitation as discussed below. At NZ-4, sufficient NAPL entered planned sentry well MW-402, therefore this well is being used as a recovery well. A new sentry well is proposed, as described in the following subsection.

<sup>3</sup> RW3-2, RW3-3, and RW3-4 were planned as recovery wells but do not contain sufficient NAPL to conduct a bail-down test (i.e., 0.5 ft of thickness above the top of the sump), therefore they are being used as sentry wells. If sufficient NAPL enters the well, a bail-down test will be conducted and the well(s) will be operated as recovery wells.

Water level and NAPL gauging will be conducted within the 4-inch (or 2-inch) well casing rather than through a drop pipe, based on challenges during field startup with inaccurate readings within the drop pipe. Gauging at the sentry wells is recommended on a standing monthly basis, rather than at each pumping event. This frequency is more in line with the pace at which NAPL conditions in the subsurface are likely to change and will allow the field teams to spend more time pumping at the recovery wells.

#### 4.2.1 TW-01 Rehabilitation

NZ-3 sentry well TW-01 was buried beneath a construction entrance for a new building on the iPark property, without notification to Honeywell. It is recommended that following completion of construction, a utility locate firm be engaged to attempt to locate the monitoring well for rehabilitation. If the well cannot be located, a replacement sentry well would be installed as close to the original location as possible.

#### 4.2.2 NZ-4 Sentry Well Construction

NAPL was observed at the newly-installed location MW-402, downgradient of recovery well RW4-1/MW-123. MW-402 was intended to serve as a sentry well for NZ-4. A bail-down test was conducted as described in this report, and MW-402 will be operated as a recovery well. A new sentry well is proposed at the location indicated on Figure 2-2. NAPL movement from the MW-123 and MW-402 areas will be controlled by the surface of the capillary barrier in this area which is represented by the top of a clayey peat layer starting at -9 ft amsl at MW-123 and observed at -15 ft amsl at MW-402. Based on the slope of this layer in the southerly direction, this monitoring well will be located to the south on the same side of River Road, collocated with prior TarGOST boring TL10.5-10.5.

Well installation will be performed in accordance with the design presented in the RD/RAWP for NAPL recovery (CH2M, 2015). As defined within the previously approved work plan, the screen depth will be selected in the field based upon the observed depth of a NAPL confining layer, expected to be either clayey peat or silty clay. A 5-foot sump will be installed below the screen.

Honeywell proposes installing this monitoring well during the mobilization for the monitoring wells recently approved for installation at the iPark peninsula, if not before, and will provide EPA with a two-week notice on mobilization.

### 4.3 O&M and Reporting Schedule

As detailed in the RD/RAWP (CH2M, 2015), the following three conditions will be evaluated to determine whether a specific recovery location has achieved its operational end point:

- Confirmation of stability
- Transmissivity reduced to below 0.8 square feet per day ( $\text{ft}^2/\text{day}$ )
- Asymptotic recovery conditions

Gauging and transmissivity data collected during the first year of O&M will be transmitted to EPA quarterly following bail-down testing, and a summary report will be prepared following four quarters of testing. Regular pumping operations commenced on November 4, 2015 with oversight by HDR, following evaluation of startup testing results. Table 4-2 presents the proposed data collection and reporting schedule for the first year of operations.

**Table 4-2. Operations Schedule**  
*Quanta Resources Corporation Superfund Site*

O&M Period	Gauging/Pumping Frequency	Bail-down Test	Reporting
Nov. 2015 through Jan. 2016	RW3-1 – Weekly pumping RW3-5 – Weekly pumping RW4-1 – Weekly pumping RW4-2 – Weekly pumping Sentry Wells – Monthly Gauging	Bail-down late January, transducer data collection mid-February	Data transmittal and recommendations for next quarter pumping/gauging frequency - March
Feb.–April 2016	RW3-1 – Weekly pumping RW3-5 – Weekly pumping RW4-1 – Weekly pumping RW4-2 – Weekly pumping Sentry Wells – Monthly Gauging	Bail-down late April, transducer data collection mid-May	Data transmittal and recommendations for next quarter pumping/gauging frequency - June
May–July 2016	RW3-1 – Weekly pumping RW3-5 – Weekly pumping RW4-1 – Weekly pumping RW4-2 – Weekly pumping Sentry Wells – Monthly Gauging	Bail-down late July, transducer data collection mid-August	Data transmittal and recommendations for next quarter pumping/gauging frequency - September
Aug.–Oct. 2016	RW3-1 – Weekly pumping RW3-5 – Weekly pumping RW4-1 – Weekly pumping RW4-2 – Weekly pumping Sentry Wells – Monthly Gauging	Bail-down late October, transducer data collection mid-November	Annual report with evaluation of progress toward recovery endpoint and recommendations for ongoing operations - December

SECTION 5

# References

- Bouwer, H., and R.C. Rice. 1976. A slug test method for determining hydraulic conductivity of unconfined aquifers with completely or partially penetrating wells. *Water Resources Research*. Vol. 12, no. 3, pp. 423–428.
- CH2M. 2008. *Remedial Investigation, Operable Unit 1, Quanta Resources Superfund Site, Edgewater, NJ*.
- CH2M. 2010a. *Technical Impracticability Evaluation, Operable Unit 1, Quanta Resources Superfund Site, Edgewater, N.J.*
- CH2M HILL. 2010b. *Supplemental Remedial Investigation Report, Quanta Resources Superfund Site, Operable Unit 1, Edgewater, N.J.* June.
- CH2M. 2013. Remedial Design Work Plan Addendum, Quanta Resources Superfund Site, Operable Unit 1, *Edgewater, New Jersey*. August.
- CH2M. 2014a. Final *Remedial Design Work Plan, Quanta Resources Superfund Site, OU1, Edgewater, NJ*. January.
- CH2M. 2014b. *Basis of Design Report, Quanta Resources Corporation Superfund Site, Operable Unit 1, Edgewater, NJ*. May.
- CH2M. 2015. *Remedial Design and Remedial Action Work Plan for NAPL Recovery, Quanta Resources Corporation Superfund Site, Operable Unit 1*.
- Cooper, H.H., and C.E. Jacob. 1946. A generalized graphical method for evaluating formation constants and summarizing well field history. *Am. Geophys. Union Trans.* Vol. 27, pp. 526–534.
- Cooper, H.H., J.D. Bredehoeft, and S.S. Papadopoulos. 1967. Response of a finite-diameter well to an instantaneous charge of water. *Water Resources Research*. Vol. 3, no. 1, pp. 263–269.
- EPA (U.S. Environmental Protection Agency). 2011. *Record of Decision, Operable Unit 1, Quanta Resources OU1, Edgewater, New Jersey*. September.
- ITRC (Interstate Technology and Regulatory Council). 2009. Evaluating LNAPL Remedial Technologies for Achieving Project Goals. December.

# Appendix A

## Boring Logs and Well Construction Details



CH2MHILL

## BORING LOG

BORING/WELL ID: RW 3-2

SHEET 1 OF 2

PROJECT NAME: Quanta SURFACE ELEVATION: 6.3 ft. MSL  
 LOCATION: Edgewater, NJ MEASURING POINT:  
 PROJECT NUMBER: 662525 MEASURING POINT ELEVATION:  
 CLIENT: Honeywell International, Inc. TOTAL DEPTH: 28.0 ft. bgs  
 DRILLING CONTRACTOR: Cascade FOREMAN: Jon Weeks  
 DRILLING METHOD: Minisonic DRILLING EQUIPMENT:  
 SAMPLING METHOD: CH2M OBSERVER: T. Salsburg  
 START DATE: 07/21/2015 FINISH DATE: 07/21/2015  
 NORTHING: 718743.20 EASTING: 633171.06 APPROX. DEPTH TO WATER: 3.0 ft. bgs

DEPTH (FT. BGS)	SAMPLE OR RUN DESIGNATION	SAMPLE TYPE	BLOWS PER 6 INCHES or CORE RUN (time/ft.)	RECOVERY/ PENETRATION (FT.)	PID	ELEVATION (ft. MSL)	MATERIALS DESCRIPTION		GRAPHICAL LOG	USCS GROUP SYMBOL	WELL CONSTRUCTION
							SOILS: TYPE, color, moisture, density/consistency, secondary structure.				
0	1 (0-5 ft.)	N/A	4.3/5.0	1.6 12.7 88.2 154 244 260 294 130 47.0 4.7 4.4 9.2 4.9 33.9 18.2 16.7 14.9 24.1 204 249 257 1.2		-5 0 -10 -15	ORGANICS, SILT, and SAND, dry, loose, subangular gravel, odor present.  Fine SILTY SAND, brown, moist, black product, sheen present.  FILL, brick and subangular gravel, saturated with NAPL, low viscosity, black product and sheen throughout.  Fine SAND and SILT (meadow mat), moist, some clay, moderate plasticity, cohesive, fibrous roots present.  Fine SAND, brown 7.5YR 4/2 with gray staining, wet, trace silt, trace subrounded gravel.  No recovery.  Fine to medium SAND, wet, trace silt, trace subrounded gravel, little product, sheen present, reduced product toward 15 ft. bgs.  Fine to medium SAND, dark brown 7.5YR 3/2, saturated with low viscosity black product, well graded, trace coarse sand, increased amount of product with depth (21.0 to 22.8 ft. bgs).  SILTY CLAY, light brown 7YR 3/2, moist, moderately soft.		SM GW ML SM SM SM SM CL	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25	
5	2 (5-10 ft.)	N/A	4.6/5.0								
10	3 (10-15 ft.)	N/A	5.0/5.0								
15	4 (15-20 ft.)	N/A	4.8/5.0								
20	5 (20-25 ft.)	N/A	5.0/5.0								
25											

**LEGEND:**  
 msl = mean sea level  
 bgs = below ground surface  
 ND = not detected  
 NM = not measured  
 N/A = not applicable

SAMPLE TYPES:  
 D: drive  
 W: washed  
 ST: Shelby Tube  
 A: Auger  
 HA: hand auger  
 C: cored  
 RC: rotasonic core

**SOIL:** GRANULAR SOILS DENSITY  
**MOISTURE:** PLASTIC SOILS DENSITY  
 dry 0-4: very loose 0-2: very soft  
 moist 5-10: loose 3-4: soft  
 wet 11-29: medium dense 5-8: medium soft  
 30-49: dense 9-15: stiff  
 50+: very dense 16-30: very stiff  
 >30: hard

**PROPORTIONS:**  
 Trace: <5% Few: 16-30%  
 Little: 6-15% Some: 31-49%

Density designation based on blow counts for each 12" of penetration using a 140 lb. hammer w/30" drop  
 When blow counts were not possible, density descriptions, as included in the "Materials Description" are based upon a thumb penetration test

**WELL LEGEND:**

	Well vault set in Portland Cement & Concrete		Riser
	Grout Slurry		Well Screen
	#0 Sand		#1 Filter Sand

**ROCK:**

RQD (rock quality designation):  
 reported in % = [length of core in pieces 4" and longer/ length of run] x100




CH2MHILL

## BORING LOG

BORING/WELL ID: RW 3-2

SHEET 2 OF 2

PROJECT NAME: Quanta SURFACE ELEVATION: 6.3 ft. MSL  
 LOCATION: Edgewater, NJ MEASURING POINT:  
 PROJECT NUMBER: 662525 MEASURING POINT ELEVATION:  
 CLIENT: Honeywell International, Inc. TOTAL DEPTH: 28.0 ft. bgs  
 DRILLING CONTRACTOR: Cascade FOREMAN: Jon Weeks  
 DRILLING METHOD: Minisonic DRILLING EQUIPMENT:  
 SAMPLING METHOD: CH2M OBSERVER: T. Salsburg  
 START DATE: 07/21/2015 FINISH DATE: 07/21/2015  
 NORTHING: 718743.20 EASTING: 633171.06 APPROX. DEPTH TO WATER: 3.0 ft. bgs



**LEGEND:**  
 msl = mean sea level  
 bgs = below ground surface  
 ND = not detected  
 NM = not measured  
 N/A = not applicable

**SAMPLE TYPES:**  
 D: drive  
 W: washed  
 ST: Shelby Tube  
 A: Auger  
 HA: hand auger  
 C: cored  
 RC: rotasonic core

**SOIL:** GRANULAR SOILS DENSITY PLASTIC SOILS DENSITY  
**MOISTURE:** 0-4: very loose 0-2: very soft  
 dry 5-10: loose 3-4: soft  
 moist 11-29: medium dense 5-8: medium soft  
 wet 30-49: dense 9-15: stiff  
 50+: very dense 16-30: very stiff  
 >30: hard

**PROPORTIONS:**  
 Trace: <5% Few: 16-30%  
 Little: 6-15% Some: 31-49%

Density designation based on blow counts for each 12" of penetration using a 140 lb. hammer w/30" drop  
 When blow counts were not possible, density descriptions, as included in the "Materials Description" are based upon a thumb penetration test

**WELL LEGEND:**

- Well vault set in Portland Cement & Concrete
- Riser
- Grout Slurry
- #00 Sand
- #1 Filter Sand
- Well Screen
- Sump

**ROCK:**

RQD (rock quality designation):  
 reported in % = [length of core in pieces 4" and longer/ length of run] x100



CH2MHILL

## BORING LOG

BORING/WELL ID: RW 3-3

SHEET 1 OF 2

PROJECT NAME: Quanta SURFACE ELEVATION: 6.4 ft. MSL  
 LOCATION: Edgewater, NJ MEASURING POINT:  
 PROJECT NUMBER: 662525 MEASURING POINT ELEVATION:  
 CLIENT: Honeywell International, Inc. TOTAL DEPTH: 27.0 ft. bgs  
 DRILLING CONTRACTOR: Cascade FOREMAN: Jon Weeks  
 DRILLING METHOD: Minisonic DRILLING EQUIPMENT:  
 SAMPLING METHOD: CH2M OBSERVER: T. Salsburg  
 START DATE: 07/21/2015 FINISH DATE: 07/21/2015  
 NORTHING: 718698.64 EASTING: 633247.76 APPROX. DEPTH TO WATER: 4.5 ft. bgs

DEPTH (FT. BGS)	SAMPLE OR RUN DESIGNATION	SAMPLE TYPE	BLOWS PER 6 INCHES or CORE RUN (time/ft.)	RECOVERY/ PENETRATION (FT.)	PID	ELEVATION (ft. MSL)	MATERIALS DESCRIPTION		GRAPHICAL LOG	USCS GROUP SYMBOL	WELL CONSTRUCTION
							SOILS: TYPE, color, moisture, density/consistency, secondary structure.				
0	1 (0-5 ft.)	N/A	5.0/5.0	0.0		-5	Fine to medium SAND, light brown, dry.		SM		0
5	2 (5-10 ft.)	N/A	5.0/5.0	4.2		-12.4	SILTY SAND and GRAVEL, dark brown to black, dry to moist, angular gravel, brick.		SM		1
10	3 (10-15 ft.)	N/A	5.0/5.0	12.4		-24.8	Medium SAND and fine GRAVEL, dark brown to stained black, moist, odor present.		SM		2
15	4 (15-18 ft.)	N/A	3.0/3.0	24.8		-48.2	Fine to medium SAND with GRAVEL, brown with black staining, moist, subrounded/subangular gravel, odor present, black product (honey), semi-solid pitch tar at 4.0 ft. bgs, sheen starts at 3.2 ft. bgs.		GW		3
20	5A (18-21 ft.)	N/A	3.0/3.0	48.2		-80.1	Fine SAND and SILT (meadow mat), moist, some clay, moderate plasticity, cohesive, fibrous roots present.		ML		4
25	5B (21-26 ft.)	N/A	5.0/5.0	80.1		-144	Fine SAND, very dark grayish brown 10YR 3/2, wet, some angular gravel, little to no silt with depth, heavy sheen, little product.		SM		5
				144		-148					6
				148		-98.1					7
				98.1		-101.9					8
				101.9		-77.4					9
				77.4		-14.8					10
				14.8		-28.8					11
				28.8		-42.7					12
				42.7		-98.4					13
				98.4		-90.8					14
				90.8		-14.2					15
				14.2		-28.3					16
				28.3		-68.2					17
				68.2		-24.1					18
				24.1		-65.4					19
				65.4		-88.2					20
				88.2		-20.9					21
				20.9		-214					22
				214		-32.2					23
				32.2							24
											25

LEGEND:	SAMPLE TYPES:	SOIL:	WELL LEGEND:
msl = mean sea level bgs = below ground surface	D: drive W: washed ST: Shelby Tube A: Auger HA: hand auger C: cored RC: rotasonic core	GRANULAR SOILS DENSITY MOISTURE: 0-4: very loose dry 5-10: loose moist 11-29: medium dense wet 30-49: dense 50+: very dense	PLASTIC SOILS DENSITY 0-2: very soft 3-4: soft 5-8: medium soft 9-15: stiff 16-30: very stiff >30: hard
ND = not detected NM = not measured N/A = not applicable	PROPORTIONS: Trace: <5% Few: 16-30% Little: 6-15% Some: 31-49%	Density designation based on blow counts for each 12" of penetration using a 140 lb. hammer w/30" drop When blow counts were not possible, density descriptions, as included in the "Materials Description" are based upon a thumb penetration test	WELL VULT SET IN PORTLAND CEMENT & CONCRETE Riser GROUT SLURRY #00 SAND #1 FILTER SAND Well Screen Sump
			ROCK: RQD (rock quality designation): reported in % = [length of core in pieces 4" and longer/ length of run] x100




CH2MHILL

## BORING LOG

BORING/WELL ID: RW 3-3

SHEET 2 OF 2

PROJECT NAME: Quanta SURFACE ELEVATION: 6.4 ft. MSL  
 LOCATION: Edgewater, NJ MEASURING POINT:  
 PROJECT NUMBER: 662525 MEASURING POINT ELEVATION:  
 CLIENT: Honeywell International, Inc. TOTAL DEPTH: 27.0 ft. bgs  
 DRILLING CONTRACTOR: Cascade FOREMAN: Jon Weeks  
 DRILLING METHOD: Minisonic DRILLING EQUIPMENT:  
 SAMPLING METHOD: CH2M OBSERVER: T. Salsburg  
 START DATE: 07/21/2015 FINISH DATE: 07/21/2015  
 NORTHING: 718698.64 EASTING: 633247.76 APPROX. DEPTH TO WATER: 4.5 ft. bgs



LEGEND:	SAMPLE TYPES:	SOIL:	WELL LEGEND:
msl = mean sea level bgs = below ground surface	D: drive W: washed ST: Shelby Tube A: Auger HA: hand auger C: cored RC: rotasonic core	GRANULAR SOILS DENSITY MOISTURE: 0-4: very loose dry 5-10: loose moist 11-29: medium dense wet 30-49: dense 50+: very dense	Well vault set in Portland Cement & Concrete Riser Grout Slurry #00 Sand #1 Filter Sand
ND = not detected NM = not measured N/A = not applicable		PLASTIC SOILS DENSITY 0-2: very soft 3-4: soft 5-8: medium soft 9-15: stiff 16-30: very stiff >30: hard	Well Screen Sump
		PROPORTIONS: Trace: <5% Few: 16-30% Little: 6-15% Some: 31-49%	Density designation based on blow counts for each 12" of penetration using a 140 lb. hammer w/30" drop When blow counts were not possible, density descriptions, as included in the "Materials Description" are based upon a thumb penetration test
			ROCK: RQD (rock quality designation): reported in % = [length of core in pieces 4" and longer/ length of run] x100



CH2MHILL

## BORING LOG

BORING/WELL ID: RW 3-4

SHEET 1 OF 2

PROJECT NAME: Quanta SURFACE ELEVATION: 8.0 ft. MSL  
 LOCATION: Edgewater, NJ MEASURING POINT:  
 PROJECT NUMBER: 662525 MEASURING POINT ELEVATION:  
 CLIENT: Honeywell International, Inc. TOTAL DEPTH: 28.0 ft. bgs  
 DRILLING CONTRACTOR: Cascade FOREMAN: Jon Weeks  
 DRILLING METHOD: Minisonic DRILLING EQUIPMENT:  
 SAMPLING METHOD: CH2M OBSERVER: T. Salsburg  
 START DATE: 07/22/2015 FINISH DATE: 07/22/2015  
 NORTHING: 718488.00 EASTING: 633227.00 APPROX. DEPTH TO WATER: 3.8 ft. bgs

DEPTH (FT. BGS)	SAMPLE OR RUN DESIGNATION	SAMPLE TYPE	BLOWS PER 6 INCHES or CORE RUN (time/ft.)	RECOVERY/ PENETRATION (FT.)	PID	ELEVATION (ft. MSL)	MATERIALS DESCRIPTION		GRAPHICAL LOG	USCS GROUP SYMBOL	WELL CONSTRUCTION	
							SOILS: TYPE, color, moisture, density/consistency, secondary structure.					
0	1 (0-5 ft.)	N/A	3.2/5.0	2.5 4.6 3.2 3.0 24.5 135 48.2 1124 1208 125 134 140 -5 12.2 10.1 16.4 12.7 10.1 23.6 61.3 452 724 1209 104 48.2			CONCRETE.  SILT with fine to medium SAND and GRAVEL, very dark gray 7.5YR 3/1, moist to saturated at 3.8 ft. bgs, loose, angular to subangular gravel, brick fragments up to 3 inches. Starting at 5.0 ft. bgs: increased silt content to 6.3 ft. bgs, sheen, little free product, odor present.		GW	ML-CL	SM	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25
5	2 (5-10 ft.)	N/A	4.7/5.0				SILT and CLAY, very dark gray 7.5YR 3/1, little fine sand and organics, moist to wet, moderately soft, cohesive, low plasticity, sheen present.  Fine to medium SAND, brown 7.5YR 4/4, wet, little silt, silt decreases with depth to only fine to medium sand at 7.8 ft. bgs, medium density, odor, little sheen staining, no product noted.					
10	3 (10-15 ft.)	N/A	5.0/5.0				Fine SAND and SILT, black 7.5YR 2.5/1, little medium sand, dense, stained.			SM		
15	4 (15-20 ft.)	N/A	5.0/5.0				Fine SAND, black 7.5YR 2.5/1, little silt, trace medium sand, sheen and odor present throughout, increased product with depth, free product present from 21.4 to 22.5 ft. bgs.			SM		
20	5 (20-25 ft.)	N/A	5.0/5.0				SILTY CLAY, orange/gray mottling 7.5YR 5/5, low plasticity, trace product and sheen.			CL		
25												

**LEGEND:**  
 msl = mean sea level  
 bgs = below ground surface  
 ND = not detected  
 NM = not measured  
 N/A = not applicable

**SAMPLE TYPES:**  
 D: drive  
 W: washed  
 ST: Shelby Tube  
 A: Auger  
 HA: hand auger  
 C: cored  
 RC: rotasonic core

**SOIL:** GRANULAR SOILS DENSITY  
**MOISTURE:** PLASTIC SOILS DENSITY  
 0-4: very loose 0-2: very soft  
 dry 5-10: loose 3-4: soft  
 moist 11-29: medium dense 5-8: medium soft  
 wet 30-49: dense 9-15: stiff  
 50+: very dense 16-30: very stiff  
 >30: hard

**PROPORTIONS:**  
 Trace: <5% Few: 16-30%  
 Little: 6-15% Some: 31-49%

Density designation based on blow counts for each 12" of penetration using a 140 lb. hammer w/30" drop  
 When blow counts were not possible, density descriptions, as included in the "Materials Description" are based upon a thumb penetration test

**WELL LEGEND:**

Well vault set in Portland Cement & Concrete  
 Grout Slurry  
 #00 Sand  
 #1 Filter Sand

Riser  
 Well Screen  
 Sump

**ROCK:**

RQD (rock quality designation):  
 reported in % = [length of core in pieces 4" and longer/ length of run] x100




CH2MHILL

## BORING LOG

BORING/WELL ID: RW 3-4

SHEET 2 OF 2

PROJECT NAME: Quanta SURFACE ELEVATION: 8.0 ft. MSL  
 LOCATION: Edgewater, NJ MEASURING POINT:  
 PROJECT NUMBER: 662525 MEASURING POINT ELEVATION:  
 CLIENT: Honeywell International, Inc. TOTAL DEPTH: 28.0 ft. bgs  
 DRILLING CONTRACTOR: Cascade FOREMAN: Jon Weeks  
 DRILLING METHOD: Minisonic DRILLING EQUIPMENT:  
 SAMPLING METHOD: CH2M OBSERVER: T. Salsburg  
 START DATE: 07/22/2015 FINISH DATE: 07/22/2015  
 NORTHING: 718488.00 EASTING: 633227.00 APPROX. DEPTH TO WATER: 3.8 ft. bgs



<b>LEGEND:</b> msl = mean sea level bgs = below ground surface ND = not detected NM = not measured N/A = not applicable	<b>SAMPLE TYPES:</b> D: drive W: washed ST: Shelby Tube A: Auger HA: hand auger C: cored RC: rotasonic core	<b>SOIL:</b> GRANULAR SOILS DENSITY MOISTURE: 0-4: very loose 0-2: very soft dry 5-10: loose 3-4: soft moist 11-29: medium dense 5-8: medium soft wet 30-49: dense 9-15: stiff 50+: very dense 16-30: very stiff >30: hard	<b>WELL LEGEND:</b> Well vault set in Portland Cement & Concrete Riser Grout Slurry #0 Sand #1 Filter Sand Sump
		<b>PROPORTIONS:</b> Trace: <5% Few: 16-30% Little: 6-15% Some: 31-49%	<b>ROCK:</b> RQD (rock quality designation): reported in % = [length of core in pieces 4" and longer/ length of run] x100



CH2MHILL

## BORING LOG

BORING/WELL ID: RW 3-5

SHEET 1 OF 2

PROJECT NAME: Quanta SURFACE ELEVATION: 7.4 ft. MSL  
 LOCATION: Edgewater, NJ MEASURING POINT:  
 PROJECT NUMBER: 662525 MEASURING POINT ELEVATION:  
 CLIENT: Honeywell International, Inc. TOTAL DEPTH: 29.0 ft. bgs  
 DRILLING CONTRACTOR: Cascade FOREMAN: Jon Weeks  
 DRILLING METHOD: Minisonic DRILLING EQUIPMENT:  
 SAMPLING METHOD: CH2M OBSERVER: T. Salsburg  
 START DATE: 07/23/2015 FINISH DATE: 07/23/2015  
 NORTHING: 718428.49 EASTING: 633131.11 APPROX. DEPTH TO WATER: 4.0 ft. bgs

DEPTH (FT. BGS)	SAMPLE OR RUN DESIGNATION	SAMPLE TYPE	BLOWS PER 6 INCHES or CORE RUN (time/ft.)	RECOVERY/ PENETRATION (FT.)	PID	ELEVATION (ft. MSL)	MATERIALS DESCRIPTION		GRAPHICAL LOG	USCS GROUP SYMBOL	WELL CONSTRUCTION
							SOILS: TYPE, color, moisture, density/consistency, secondary structure.				
0	1 (0-4 ft.)	N/A	4.0/4.0	0.0		0.0	CONCRETE.				0
				0.0		0.0	SILT, fine to coarse SAND and GRAVEL, brown 7.5YR 4/3, moist, loose, subangular to subrounded gravel, brick fragments present.	GW			1
				0.0		0.0	Fine to medium SAND and SILT, very dark gray 7.5 YR 3/1, some subrounded gravel, moist, loose to medium density, organics.	SW-ML			2
-5	2 (4-7 ft.)	N/A	0.0/3.0	0.0		0.0	CONCRETE, not bagged (4.0 to 7.0 ft. bgs).				3
				0.0		0.0					4
				187		0.0					5
				228		0.0					6
				327		0.0					7
				460		0.0					8
				372		0.0					9
				325		0.0					10
				278		0.0					11
				308		0.0					12
				318		0.0					13
				301		0.0					14
				389		0.0					15
				372		0.0					16
				407		0.0					17
				520		0.0					18
				20.9		0.0					19
							Varved CLAYEY SILT, light yellowish (olive) brown 2.5Y 6/3, becomes gray with depth, non-plastic, firm, pockets of fine black sand with sheen.	ML			20
											21
											22
											23
											24
											25

**LEGEND:**  
 msl = mean sea level  
 bgs = below ground surface  
 ND = not detected  
 NM = not measured  
 N/A = not applicable

**SAMPLE TYPES:**  
 D: drive  
 W: washed  
 ST: Shelby Tube  
 A: Auger  
 HA: hand auger  
 C: cored  
 RC: rotasonic core

**SOIL:** GRANULAR SOILS DENSITY  
**MOISTURE:** PLASTIC SOILS DENSITY  
 0-4: very loose 0-2: very soft  
 dry 5-10: loose 3-4: soft  
 moist 11-29: medium dense 5-8: medium soft  
 wet 30-49: dense 9-15: stiff  
 50+: very dense 16-30: very stiff  
 >30: hard

**PROPORTIONS:**  
 Trace: <5% Few: 16-30%  
 Little: 6-15% Some: 31-49%

Density designation based on blow counts for each 12" of penetration using a 140 lb. hammer w/30" drop  
 When blow counts were not possible, density descriptions, as included in the "Materials Description" are based upon a thumb penetration test

**WELL LEGEND:**
  
 Riser  
  
 Well Screen  
  
 Sump  
**ROCK:**

RQD (rock quality designation):  
 reported in % = [length of core in pieces 4" and longer/ length of run] x100




CH2MHILL

## BORING LOG

BORING/WELL ID: RW 3-5

SHEET 2 OF 2

PROJECT NAME: Quanta SURFACE ELEVATION: 7.4 ft. MSL  
 LOCATION: Edgewater, NJ MEASURING POINT:  
 PROJECT NUMBER: 662525 MEASURING POINT ELEVATION:  
 CLIENT: Honeywell International, Inc. TOTAL DEPTH: 29.0 ft. bgs  
 DRILLING CONTRACTOR: Cascade FOREMAN: Jon Weeks  
 DRILLING METHOD: Minisonic DRILLING EQUIPMENT:  
 SAMPLING METHOD: CH2M OBSERVER: T. Salsburg  
 START DATE: 07/23/2015 FINISH DATE: 07/23/2015  
 NORTHING: 718428.49 EASTING: 633131.11 APPROX. DEPTH TO WATER: 4.0 ft. bgs



**LEGEND:**  
 msl = mean sea level  
 bgs = below ground surface  
 ND = not detected  
 NM = not measured  
 N/A = not applicable

**SAMPLE TYPES:**  
 D: drive  
 W: washed  
 ST: Shelby Tube  
 A: Auger  
 HA: hand auger  
 C: cored  
 RC: rotasonic core

**SOIL:** GRANULAR SOILS DENSITY  
 MOISTURE: 0-4: very loose 0-2: very soft  
 dry 5-10: loose 3-4: soft  
 moist 11-29: medium dense 5-8: medium soft  
 wet 30-49: dense 9-15: stiff  
 50+: very dense 16-30: very stiff  
 >30: hard

**PROPORTIONS:**  
 Trace: <5% Few: 16-30%  
 Little: 6-15% Some: 31-49%

Density designation based on blow counts for each 12" of penetration using a 140 lb. hammer w/30" drop  
 When blow counts were not possible, density descriptions, as included in the "Materials Description" are based upon a thumb penetration test

**WELL LEGEND:**

Well vault set in Portland Cement & Concrete  
 Grout Slurry  
 #00 Sand  
 #1 Filter Sand

**ROCK:**

RQD (rock quality designation):  
 reported in % = [length of core in pieces 4" and longer/ length of run] x100



CH2MHILL

## BORING LOG

BORING/WELL ID: MW-400

SHEET 1 OF 2

PROJECT NAME: Quanta SURFACE ELEVATION: 7.7 ft. MSL  
 LOCATION: Edgewater, NJ MEASURING POINT:  
 PROJECT NUMBER: 662525 MEASURING POINT ELEVATION:  
 CLIENT: Honeywell International, Inc. TOTAL DEPTH: 39.0 ft. bgs  
 DRILLING CONTRACTOR: Cascade FOREMAN: Jon Weeks  
 DRILLING METHOD: Minisonic DRILLING EQUIPMENT:  
 SAMPLING METHOD: CH2M OBSERVER: T. Salsburg  
 START DATE: 07/25/2015 FINISH DATE: 07/25/2015  
 NORTHING: 718353.75 EASTING: 633201.32 APPROX. DEPTH TO WATER:

DEPTH (FT. BGS)	SAMPLE OR RUN DESIGNATION	SAMPLE TYPE	BLOWS PER 6 INCHES or CORE RUN (time/ft.)	RECOVERY/ PENETRATION (FT.)	PID	ELEVATION (ft. MSL)	MATERIALS DESCRIPTION		GRAPHICAL LOG	USCS GROUP SYMBOL	WELL CONSTRUCTION
							SOILS: TYPE, color, moisture, density/consistency, secondary structure.				
0	1 (0-5 ft.)	N/A	5.0/5.0	0.0		0.0	PAVEMENT.			GW	0
5	2 (5-10 ft.)	N/A	3.5/5.0	0.0		0.0	SANDY GRAVEL (fill), dark brown, dry, loose.				1
10	3 (10-15 ft.)	N/A	4.9/5.0	0.0		0.4	CONCRETE.				2
15	4 (15-20 ft.)	N/A	5.0/5.0	0.0		1.3					3
20	5 (20-25 ft.)	N/A	5.0/5.0	0.0		2.4					4
25				0.0		4.3	Fine to coarse GRAVELLY SAND, black 7.5YR 2/1, saturated, surrounded to subangular gravel, organics, wood and fractured rock, odor present.		SP		5
				0.0		10.4	CLAYEY SILT (meadow mat), dark gray 7.5YR 4/1, a lot of organics, soft, cohesive, moderate plasticity, little sheen. From 15.0 to 20.0 ft. bgs, stronger odor present and less cohesive (more crumbly), meadow mat even less cohesive from 20.0 to 25.0 ft. bgs. At 24.3 ft. bgs: abrupt increase in cohesiveness and is more plastic, higher clay content, soft, still a lot of organics, strong odor present.		ML	6	
				0.0		14.2					7
				0.0		7.8					8
				0.0		6.9					9
				0.0		9.4					10
				0.0		20.1					11
				0.0		21.4					12
				0.0		17.5					13
				0.0		13.2					14
				0.0		-10					15
				0.0		6.9					16
				0.0		9.4					17
				0.0		20.1					18
				0.0		21.4					19
				0.0		17.5					20
				0.0		13.2					21
				0.0		-15					22
				0.0		17.1	CLAYEY SILT (meadow mat), dark gray 7.5YR 4/1, a lot of organics,				23
											24
											25

**LEGEND:**  
 msl = mean sea level  
 bgs = below ground surface  
 ND = not detected  
 NM = not measured  
 N/A = not applicable

**SAMPLE TYPES:**  
 D: drive  
 W: washed  
 ST: Shelby Tube  
 A: Auger  
 HA: hand auger  
 C: cored  
 RC: rotasonic core

**SOIL:** GRANULAR SOILS DENSITY PLASTIC SOILS DENSITY  
**MOISTURE:** 0-4: very loose 0-2: very soft  
 dry 5-10: loose 3-4: soft  
 moist 11-29: medium dense 5-8: medium soft  
 wet 30-49: dense 9-15: stiff  
 50+: very dense 16-30: very stiff  
 >30: hard

**PROPORTIONS:**  
 Trace: <5% Few: 16-30%  
 Little: 6-15% Some: 31-49%

Density designation based on blow counts for each 12" of penetration using a 140 lb. hammer w/30" drop  
 When blow counts were not possible, density descriptions, as included in the "Materials Description" are based upon a thumb penetration test

**WELL LEGEND:**

	Well vault set in Portland Cement & Concrete		Riser
	Grout Slurry		Well Screen
	#00 Sand		#1 Filter Sand
	Sump		

**ROCK:**

RQD (rock quality designation):  
 reported in % = [length of core in pieces 4" and longer/ length of run] x100




CH2MHILL

## BORING LOG

BORING/WELL ID: MW-400

SHEET 2 OF 2

PROJECT NAME: Quanta SURFACE ELEVATION: 7.7 ft. MSL  
 LOCATION: Edgewater, NJ MEASURING POINT:  
 PROJECT NUMBER: 662525 MEASURING POINT ELEVATION:  
 CLIENT: Honeywell International, Inc. TOTAL DEPTH: 39.0 ft. bgs  
 DRILLING CONTRACTOR: Cascade FOREMAN: Jon Weeks  
 DRILLING METHOD: Minisonic DRILLING EQUIPMENT:  
 SAMPLING METHOD: CH2M OBSERVER: T. Salsburg  
 START DATE: 07/25/2015 FINISH DATE: 07/25/2015  
 NORTHING: 718353.75 EASTING: 633201.32 APPROX. DEPTH TO WATER:



<b>LEGEND:</b> msl = mean sea level bgs = below ground surface ND = not detected NM = not measured N/A = not applicable	<b>SAMPLE TYPES:</b> D: drive W: washed ST: Shelby Tube A: Auger HA: hand auger C: cored RC: rotasonic core	<b>SOIL:</b> GRANULAR SOILS DENSITY MOISTURE: 0-4: very loose 0-2: very soft dry 5-10: loose 3-4: soft moist 11-29: medium dense 5-8: medium soft wet 30-49: dense 9-15: stiff 50+: very dense 16-30: very stiff >30: hard	<b>WELL LEGEND:</b> Well vault set in Portland Cement & Concrete Grout Slurry #0 Sand #1 Filter Sand
		<b>PROPORTIONS:</b> Trace: <5% Few: 16-30% Little: 6-15% Some: 31-49%	<b>ROCK:</b> RQD (rock quality designation): reported in % = [length of core in pieces 4" and longer/ length of run] x100




CH2MHILL

## BORING LOG

BORING/WELL ID: MW-402

SHEET 1 OF 1

PROJECT NAME: Quanta SURFACE ELEVATION: 7.1 ft. MSL  
 LOCATION: Edgewater, NJ MEASURING POINT:  
 PROJECT NUMBER: 662525 MEASURING POINT ELEVATION:  
 CLIENT: Honeywell International, Inc. TOTAL DEPTH: 21.2 ft. bgs  
 DRILLING CONTRACTOR: Cascade FOREMAN: Jon Weeks  
 DRILLING METHOD: Minisonic DRILLING EQUIPMENT:  
 SAMPLING METHOD: CH2M OBSERVER: T. Salsburg  
 START DATE: 07/27/2015 FINISH DATE: 07/27/2015  
 NORTHING: 718685.04 EASTING: 632585.24 APPROX. DEPTH TO WATER: 6 ft. bgs



**LEGEND:**  
 msl = mean sea level  
 bgs = below ground surface  
 ND = not detected  
 NM = not measured  
 N/A = not applicable

**SAMPLE TYPES:**  
 D: drive  
 W: washed  
 ST: Shelby Tube  
 A: Auger  
 HA: hand auger  
 C: cored  
 RC: rotasonic core

**SOIL:** GRANULAR SOILS DENSITY  
 PLASTIC SOILS DENSITY  
 MOISTURE: 0-4: very loose 0-2: very soft  
 dry 5-10: loose 3-4: soft  
 moist 11-29: medium dense 5-8: medium soft  
 wet 30-49: dense 9-15: stiff  
 50+: very dense 16-30: very stiff  
 >30: hard

**PROPORTIONS:**  
 Trace: <5% Few: 16-30%  
 Little: 6-15% Some: 31-49%

Density designation based on blow counts for each 12" of penetration using a 140 lb. hammer w/30" drop  
 When blow counts were not possible, density descriptions, as included in the "Materials Description" are based upon a thumb penetration test

**WELL LEGEND:**

Well vault set in Portland Cement & Concrete  
 Riser  
 Grout Slurry  
 #0 Sand  
 #1 Filter Sand  
 Well Screen  
 Sump

**ROCK:**

RQD (rock quality designation):  
 reported in % = [length of core in pieces 4" and longer/ length of run] x100

**MONITORING WELL CERTIFICATION - FORM A - AS-BUILT CERTIFICATION**

(One form must be completed for each well)

Name of Permittee: Quanta  
 Name of Facility: Edgewater N.J.  
 Location: Edgewater N.J.  
 NJPDES Permit No.: E201507616

**CERTIFICATION**

1. Well Permit Number (As assigned by NJDEP's Bureau of Water Allocation): RW3-3
2. Owner's Well Number (As shown on the application or plans): 7-22-15
3. Well Completion Date:
4. Distance from Top of Casing (cap off) to ground surface  
(One-hundredth of a foot): Flush
5. Total Depth of Well to the nearest ½ foot: 28'
6. Depth to Top of Screen From Top of Casing (or depth to open hole)  
To the nearest ½ foot: 13'
7. Screen Length (or length of open hole) in feet: 10'
8. Screen or Slot Size: 20 slot
9. Screen or Slot Material: Stainless
10. Casing Material: (PVC, Steel or Other-Specify): PVC
11. Casing Diameter (inches): 4"
12. Static Water Level From Top of Casing at the Time of Installation  
(One-hundredth of a foot): 1.95
13. Yield (gallons per minute): 36pm
14. Development Technique (specify): Waterra
15. Length of Time Well is Developed/ Pumped or Bailed: 2 Hours \_\_\_\_\_ Minutes
16. Lithologic Log: Attach

**AUTHENTICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

Jon Weeks

Name (Type or Print)

MW195190

Certification or License No.

J.J. Wehr

Signature

Seal

Certification by Executive Officer or Duly Authorized Representative

Name (Type or Print)

Signature

Title

Date

## **MONITORING WELL CERTIFICATION – FORM A – AS-BUILT CERTIFICATION**

(One form must be completed for each well)

Name of Permittee: Quanta  
Name of Facility: Edgewater NJ  
Location: Edgewater NJ  
NJPDES Permit No.: E 201507667

### **CERTIFICATION**

1. Well Permit Number (As assigned by NJDEP's Bureau of Water Allocation): RW3-2
2. Owner's Well Number (As shown on the application or plans): 7-22-15
3. Well Completion Date:
4. Distance from Top of Casing (cap off) to ground surface  
(One-hundredth of a foot): flush
5. Total Depth of Well to the nearest ½ foot: 27'
6. Depth to Top of Screen From Top of Casing (or depth to open hole)  
To the nearest ½ foot:  
12'
7. Screen Length (or length of open hole) in feet: 10'
8. Screen or Slot Size: 205 slot
9. Screen or Slot Material: Stainless
10. Casing Material: (PVC, Steel or Other-Specify): PVC
11. Casing Diameter (inches): 4"
12. Static Water Level From Top of Casing at the Time of Installation  
(One-hundredth of a foot): 2.45
13. Yield (gallons per minute): 2 GPM
14. Development Technique (specify): Waterfall
15. Length of Time Well is Developed/ Pumped or Bailed: 2 Hours \_\_\_\_\_ Minutes \_\_\_\_\_
16. Lithologic Log: Attach \_\_\_\_\_

### **AUTHENTICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

Jon Weeks

Name (Type or Print)

MW195190

Certification or License No.

J. Weeks

Signature

Seal

Certification by Executive Officer or Duly Authorized Representative

Name (Type or Print)

Signature

Title

Date

## **MONITORING WELL CERTIFICATION - FORM A - AS-BUILT CERTIFICATION**

(One form must be completed for each well)

Name of Permittee: Quarfa  
Name of Facility: Edge water NJ  
Location: Edge water NJ  
NJPDES Permit No.: E201507697

### **CERTIFICATION**

1. Well Permit Number (As assigned by NJDEP's Bureau of Water Allocation): RW3-4
2. Owner's Well Number (As shown on the application or plans): 7-23-15
3. Well Completion Date: flush
4. Distance from Top of Casing (cap off) to ground surface (One-hundredth of a foot): 28'
5. Total Depth of Well to the nearest 1/2 foot: 13'
6. Depth to Top of Screen From Top of Casing (or depth to open hole)  
To the nearest 1/2 foot: 10'
7. Screen Length (or length of open hole) in feet: 20.510f
8. Screen or Slot Size: Stainless
9. Screen or Slot Material: PVC
10. Casing Material: (PVC, Steel or Other-Specify): 4"
11. Casing Diameter (inches): 2.36
12. Static Water Level From Top of Casing at the Time of Installation  
(One-hundredth of a foot): 2 GPM
13. Yield (gallons per minute): Water
14. Development Technique (specify): 1 Hours 30 Minutes
15. Length of Time Well is Developed/ Pumped or Bailed: Attach
16. Lithologic Log:

### **AUTHENTICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

Jon Weeks

Name (Type or Print)

MW195190

Certification or License No.

J Weeks

Signature

Seal

Certification by Executive Officer or Duly Authorized Representative

Name (Type or Print)

Signature

Title

Date

## **MONITORING WELL CERTIFICATION - FORM A - AS-BUILT CERTIFICATION**

(One form must be completed for each well)

Name of Permittee: Quanta  
Name of Facility: Edge Water NJ  
Location: Edge Water NJ  
NJPDES Permit No.: E 201507895

### **CERTIFICATION**

1. Well Permit Number (As assigned by NJDEP's Bureau of Water Allocation): RW3-5
2. Owner's Well Number (As shown on the application or plans): 7-24-15
3. Well Completion Date: flush
4. Distance from Top of Casing (cap off) to ground surface  
(One-hundredth of a foot): 29'
5. Total Depth of Well to the nearest ½ foot: 9'
6. Depth to Top of Screen From Top of Casing (or depth to open hole)  
To the nearest ½ foot: 15'
7. Screen Length (or length of open hole) in feet: 20.50 ft
8. Screen or Slot Size: Stainless
9. Screen or Slot Material: PVC
10. Casing Material: (PVC, Steel or Other-Specify): 4"
11. Casing Diameter (inches): 3.45
12. Static Water Level From Top of Casing at the Time of Installation  
(One-hundredth of a foot): 2 GPM
13. Yield (gallons per minute): water
14. Development Technique (specify):
15. Length of Time Well is Developed/ Pumped or Bailed: 2 Hours \_\_\_\_\_ Minutes
16. Lithologic Log: Attach

### **AUTHENTICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

Jon Weeks

Name (Type or Print)

MW195190

Certification or License No.

JZ Weeks

Signature

Seal

Certification by Executive Officer or Duly Authorized Representative

Name (Type or Print)

Signature

Title

Date

**MONITORING WELL CERTIFICATION - FORM A - AS-BUILT CERTIFICATION**

(One form must be completed for each well)

Name of Permittee: Quantu  
 Name of Facility: Edgewater NJ  
 Location: Edgewater NJ  
 NJPDES Permit No.: E201507686

**CERTIFICATION**

1. Well Permit Number (As assigned by NJDEP's Bureau of Water Allocation): MW-400
2. Owner's Well Number (As shown on the application or plans): 7-27-15
3. Well Completion Date: flush
4. Distance from Top of Casing (cap off) to ground surface  
(One-hundredth of a foot): 36'
5. Total Depth of Well to the nearest ½ foot: 29'
6. Depth to Top of Screen From Top of Casing (or depth to open hole)  
To the nearest ½ foot: 5'
7. Screen Length (or length of open hole) in feet: 20 8 lot
8. Screen or Slot Size: PVC
9. Screen or Slot Material: PVC
10. Casing Material: (PVC, Steel or Other-Specify): 4"
11. Casing Diameter (inches): 3,06
12. Static Water Level From Top of Casing at the Time of Installation  
(One-hundredth of a foot): 1/2 6 pm
13. Yield (gallons per minute): Water
14. Development Technique (specify): 3 Hours \_\_\_\_\_ Minutes
15. Length of Time Well is Developed/ Pumped or Bailed: Attach
16. Lithologic Log:

**AUTHENTICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

Jon Weeks

Name (Type or Print)

JJ Weeks

Signature

MW195190

Certification or License No.

Seal

Certification by Executive Officer or Duly Authorized Representative

Name (Type or Print)

Signature

Title

Date

**MONITORING WELL CERTIFICATION - FORM A - AS-BUILT CERTIFICATION**

(One form must be completed for each well)

Name of Permittee: Quantec  
 Name of Facility: Edge Water N.J.  
 Location: Edge Water N.J.  
 NJPDES Permit No.: E201507669

**CERTIFICATION**

1. Well Permit Number (As assigned by NJDEP's Bureau of Water Allocation): MW402
2. Owner's Well Number (As shown on the application or plans): 7-28-15
3. Well Completion Date:
4. Distance from Top of Casing (cap off) to ground surface  
(One-hundredth of a foot): flush
5. Total Depth of Well to the nearest ½ foot: 21'
6. Depth to Top of Screen From Top of Casing (or depth to open hole)  
To the nearest ½ foot: 6'
7. Screen Length (or length of open hole) in feet: 10'
8. Screen or Slot Size: 205 slot
9. Screen or Slot Material: Stainless
10. Casing Material: (PVC, Steel or Other-Specify): PVC
11. Casing Diameter (inches): 4"
12. Static Water Level From Top of Casing at the Time of Installation  
(One-hundredth of a foot): 3.32
13. Yield (gallons per minute): 1.5
14. Development Technique (specify): waterra
15. Length of Time Well is Developed/ Pumped or Bailed: 1 Hours 30 Minutes
16. Lithologic Log: Attach

**AUTHENTICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

Jon Weeks

Name (Type or Print)

MW195190

Certification or License No.

JJ Weeks

Signature

Seal

Certification by Executive Officer or Duly Authorized Representative

Name (Type or Print)

Signature

Title

Date

**MONITORING WELL CERTIFICATION - FORM A - AS-BUILT CERTIFICATION**

(One form must be completed for each well)

Name of Permittee: \_\_\_\_\_

Name of Facility: \_\_\_\_\_

Location: \_\_\_\_\_

NJPDES Permit No.: \_\_\_\_\_

**CERTIFICATION**

1. Well Permit Number (As assigned by NJDEP's Bureau of Water Allocation): \_\_\_\_\_
2. Owner's Well Number (As shown on the application or plans): \_\_\_\_\_
3. Well Completion Date: \_\_\_\_\_
4. Distance from Top of Casing (cap off) to ground surface  
(One-hundredth of a foot): \_\_\_\_\_
5. Total Depth of Well to the nearest ½ foot: \_\_\_\_\_
6. Depth to Top of Screen From Top of Casing (or depth to open hole)  
To the nearest ½ foot: \_\_\_\_\_
7. Screen Length (or length of open hole) in feet: \_\_\_\_\_
8. Screen or Slot Size: \_\_\_\_\_
9. Screen or Slot Material: \_\_\_\_\_
10. Casing Material: (PVC, Steel or Other-Specify): \_\_\_\_\_
11. Casing Diameter (inches): \_\_\_\_\_
12. Static Water Level From Top of Casing at the Time of Installation  
(One-hundredth of a foot): \_\_\_\_\_
13. Yield (gallons per minute): \_\_\_\_\_
14. Development Technique (specify): \_\_\_\_\_
15. Length of Time Well is Developed/ Pumped or Bailed: \_\_\_\_\_ Hours \_\_\_\_\_ Minutes
16. Lithologic Log: \_\_\_\_\_ Attach \_\_\_\_\_

**AUTHENTICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

\_\_\_\_\_  
Name (Type or Print)\_\_\_\_\_  
Signature\_\_\_\_\_  
Seal\_\_\_\_\_  
Certification or License No.\_\_\_\_\_  
Certification by Executive Officer or Duly Authorized Representative\_\_\_\_\_  
Name (Type or Print)\_\_\_\_\_  
Signature\_\_\_\_\_  
Title\_\_\_\_\_  
Date



New Jersey Department of Environmental Protection  
Site Remediation Program

Monitoring Well Certification Form B - Location Certification

Date Stamp  
(For Department use only)

**SECTION A. SITE NAME AND LOCATION**

Site Name: Quanta Resources Corporation Superfund Site  
List all AKAs: Bryan Christensen c/o Daibes Enterprises  
Street Address: 45 River Road  
Municipality: Borough of Edgewater (Township, Borough or City)  
County: Bergen Zip Code: 07020  
Program Interest (PI) Number(s): Case Tracking Number(s): NJD000606442

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner I Park Edgewater LLC  
2. Well Location (Street Address) 45 River Road  
3. Well Location (Municipal Block and Lot) Block# 99 Lot # 1

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201507686  
2. Site Well Number (As shown on application or plans): MW-400  
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:  
Latitude: North 40° 48' 15.90" Longitude: West 73° 59' 25.33"  
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:  
North 718,354 feet East 633,201 feet  
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 6.74  
Elevation Top of Outer casing: 7.70 Elevation of ground: 7.7  
Check One:  NAVD 88  NGVD 29  On Site Datum  Other  
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).  
Elevations are referenced to NAVD 1988, Horiz. Datum is NAD 1983 based on NGS Opus Solution 83431992.05o, dated 07/19/05. Base Stations used are NJI2 (PID AJ3348), SHK1 (PID AF9509) and LAMT (PID AJ4872).  
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: M. V. Date: 09-16-15  
Surveyor's Name: Robert E. Vargo License Number: GS43261  
Firm Name: Vargo Associates Certificate Authorization #: 24GA28021200  
Mailing Address: 2771 Delsea Drive  
City/Town: Franklinville State: NJ Zip Code: 08322  
Phone Number: 856-694-1716 Ext.: 110 Fax: 856-694-3102



New Jersey Department of Environmental Protection  
Site Remediation Program

Monitoring Well Certification Form B - Location Certification

Date Stamp  
(For Department use only)

**SECTION A. SITE NAME AND LOCATION**

Site Name: Quanta Resources Corporation Superfund Site  
List all AKAs: Bryan Christensen c/o Daibes Enterprises  
Street Address: 125 River Road  
Municipality: Borough of Edgewater (Township, Borough or City)  
County: Bergen Zip Code: 07020  
Program Interest (PI) Number(s): Case Tracking Number(s): NJD000606442

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Metropolitan Consom, LLC  
2. Well Location (Street Address) 125 River Road  
3. Well Location (Municipal Block and Lot) Block# 93 Lot # 4

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201507669  
2. Site Well Number (As shown on application or plans): MW 402  
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:  
Latitude: North 40° 48' 19.20" Longitude: West 73° 59' 33.32"  
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:  
North 718,685 feet East 632,585 feet  
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 6.16  
Elevation Top of Outer casing: 7.13 Elevation of ground: 7.1  
Check One:  NAVD 88  NGVD 29  On Site Datum  Other  
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).  
Elevations are referenced to NAVD 1988, Horiz. Datum is NAD 1983 based on NGS Opus Solution 83431992.05o, dated 07/19/05. Base Stations used are NJI2 (PID AJ3348), SHK1 (PID AF9509) and LAMT (PID AJ4872).  
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Robert E. Vargo Date: 09-16-15  
Surveyor's Name: Robert E. Vargo License Number: GS43261  
Firm Name: Vargo Associates Certificate Authorization #: 24GA28021200  
Mailing Address: 2771 Delsea Drive  
City/Town: Franklinville State: NJ Zip Code: 08322  
Phone Number: 856-694-1716 Ext.: 110 Fax: 856-694-3102



New Jersey Department of Environmental Protection  
Site Remediation Program

Monitoring Well Certification Form B - Location Certification

Date Stamp  
(For Department use only)

**SECTION A. SITE NAME AND LOCATION**

Site Name: Quanta Resources Corporation Superfund Site  
List all AKAs: Bryan Christensen c/o Daibes Enterprises  
Street Address: 145 River Road  
Municipality: Borough of Edgewater (Township, Borough or City)  
County: Bergen Zip Code: 07020  
Program Interest (PI) Number(s): Case Tracking Number(s): NJD000606442

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Hudson River Association  
2. Well Location (Street Address) 145 River Road  
3. Well Location (Municipal Block and Lot) Block# 95 Lot # 1

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201507667
2. Site Well Number (As shown on application or plans): RW3-2
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:  
Latitude: North 40° 48' 19.75" Longitude: West 73° 59' 25.69"
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:  
North 718,743 feet East 633,171 feet
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 5.30  
Elevation Top of Outer casing: 6.25 Elevation of ground: 6.3  
Check One:  NAVD 88  NGVD 29  On Site Datum  Other
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).  
Elevations are referenced to NAVD 1988, Horiz. Datum is NAD 1983 based on NGS Opus Solution 83431992.050, dated 07/19/05. Base Stations used are NJI2 (PID AJ3348), SHK1 (PID AF9509) and LAMT (PID AJ4872).
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: R.E. Vargo Date: 09-16-15  
Surveyor's Name: Robert E. Vargo License Number: GS43261  
Firm Name: Vargo Associates Certificate Authorization #: 24GA28021200  
Mailing Address: 2771 Delsea Drive  
City/Town: Franklinville State: NJ Zip Code: 08322  
Phone Number: 856-694-1716 Ext.: 110 Fax: 856-694-3102



New Jersey Department of Environmental Protection  
Site Remediation Program

Monitoring Well Certification Form B - Location Certification

Date Stamp  
(For Department use only)

**SECTION A. SITE NAME AND LOCATION**

Site Name: Quanta Resources Corporation Superfund Site  
List all AKAs: Bryan Christensen c/o Daibes Enterprises  
Street Address: 145 River Road  
Municipality: Borough of Edgewater (Township, Borough or City)  
County: Bergen Zip Code: 07020  
Program Interest (PI) Number(s): Case Tracking Number(s): NJD000606442

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner Hudson River Association  
2. Well Location (Street Address) 145 River Road  
3. Well Location (Municipal Block and Lot) Block# 95 Lot # 1

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201507616  
2. Site Well Number (As shown on application or plans): RW3-3  
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:  
Latitude: North 40° 48' 19.30" Longitude: West 73° 59' 24.70"  
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:  
North 718,699 feet East 633,248 feet  
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 5.61  
Elevation Top of Outer casing: 6.44 Elevation of ground: 6.4  
Check One:  NAVD 88  NGVD 29  On Site Datum  Other  
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).  
Elevations are referenced to NAVD 1988, Horiz. Datum is NAD 1983 based on NGS Opus Solution 83431992.050, dated 07/19/05. Base Stations used are NJI2 (PID AJ3348), SHK1 (PID AF9509) and LAMT (PID AJ4872).  
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: M. R. V. Date: 09-16-15  
Surveyor's Name: Robert E. Vargo License Number: GS43261  
Firm Name: Vargo Associates Certificate Authorization #: 24GA28021200  
Mailing Address: 2771 Delsea Drive  
City/Town: Franklinville State: NJ Zip Code: 08322  
Phone Number: 856-694-1716 Ext.: 110 Fax: 856-694-3102



New Jersey Department of Environmental Protection  
Site Remediation Program

Monitoring Well Certification Form B - Location Certification

Date Stamp  
(For Department use only)

**SECTION A. SITE NAME AND LOCATION**

Site Name: Quanta Resources Corporation Superfund Site  
List all AKAs: Bryan Christensen c/o Daibes Enterprises  
Street Address: 45 River Road  
Municipality: Borough of Edgewater (Township, Borough or City)  
County: Bergen Zip Code: 07020  
Program Interest (PI) Number(s): \_\_\_\_\_ Case Tracking Number(s): NJD000606442

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner 115 River Road LLC  
2. Well Location (Street Address) 115 River Road  
3. Well Location (Municipal Block and Lot) Block# 96 Lot # 3.04

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201507697  
2. Site Well Number (As shown on application or plans): RW3-4  
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:  
Latitude: North 40° 48' 17.22" Longitude: West 73° 59' 24.99"  
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:  
North 718,488 feet East 633,227 feet  
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 6.90  
Elevation Top of Outer casing: 7.96 Elevation of ground: 8.0  
Check One:  NAVD 88  NGVD 29  On Site Datum  Other  
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).  
Elevations are referenced to NAVD 1988, Horiz. Datum is NAD 1983 based on NGS Opus Solution 83431992.050, dated 07/19/05. Base Stations used are NJI2 (PID AJ3348), SHK1 (PID AF9509) and LAMT (PID AJ4872).  
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL

Professional Land Surveyor's Signature: Robert E. Vargo Date: 09-16-15  
Surveyor's Name: Robert E. Vargo License Number: GS43261  
Firm Name: Vargo Associates Certificate Authorization #: 24GA28021200  
Mailing Address: 2771 Delsea Drive  
City/Town: Franklinville State: NJ Zip Code: 08322  
Phone Number: 856-694-1716 Ext.: 110 Fax: 856-694-3102



New Jersey Department of Environmental Protection  
Site Remediation Program

Monitoring Well Certification Form B - Location Certification

Date Stamp  
(For Department use only)

**SECTION A. SITE NAME AND LOCATION**

Site Name: Quanta Resources Corporation Superfund Site  
List all AKAs: Bryan Christensen c/o Daibes Enterprises  
Street Address: 45 River Road  
Municipality: Borough of Edgewater (Township, Borough or City)  
County: Bergen Zip Code: 07020  
Program Interest (PI) Number(s): Case Tracking Number(s): NJD000606442

**SECTION B. WELL OWNER AND LOCATION**

1. Name of Well Owner I Park Edgewater LLC  
2. Well Location (Street Address) 45 River Road  
3. Well Location (Municipal Block and Lot) Block# 99 Lot # 1

**SECTION C. WELL LOCATION SPECIFICS**

1. Well Permit Number (This number must be permanently affixed to the well casing): E201507895  
2. Site Well Number (As shown on application or plans): RW3-5  
3. Geographic Coordinate NAD 83 to nearest 1/100 of a second:  
Latitude: North 40° 48' 16.64" Longitude: West 73° 59' 26.24"  
4. New Jersey State Plane Coordinates NAD 83 datum, US survey feet units, to nearest foot:  
North 718,428 feet East 633,131 feet  
5. Elevation of Top of Inner Casing (cap off) at reference mark (nearest 0.01'): 6.44  
Elevation Top of Outer casing: 7.36 Elevation of ground: 7.4  
Check One:  NAVD 88  NGVD 29  On Site Datum  Other  
6. Source of elevation datum (benchmark, number/description and elevation/datum). If an on-site datum is used, identify here, assume datum of 100', and give approximated actual elevation (referencing NAVD 88).  
Elevations are referenced to NAVD 1988, Horiz. Datum is NAD 1983 based on NGS Opus Solution 83431992.050, dated 07/19/05. Base Stations used are NJI2 (PID AJ3348), SHK1 (PID AF9509) and LAMT (PID AJ4872).  
7. Significant observations and notes:

**SECTION D. LAND SURVEYOR'S CERTIFICATION**

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe the submitted information is true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment.

SEAL


Professional Land Surveyor's Signature: Robert E. Vargo Date: 09-16-15  
Surveyor's Name: Robert E. Vargo License Number: GS43261  
Firm Name: Vargo Associates Certificate Authorization #: 24GA28021200  
Mailing Address: 2771 Delsea Drive  
City/Town: Franklinville State: NJ Zip Code: 08322  
Phone Number: 856-694-1716 Ext.: 110 Fax: 856-694-3102

# Appendix B

## Transducer Data and Transmissivity Calculations

# RW3-5 Transducer Data Representation

September 2, 2015 Baildown Test



Well Designation:  
Date:

RW3-5  
2-Sep-15

Amount of volume to remove (gal)

6.21

TEST 1	
Ground Surface Elev (ft msl)	7.40
Top of Casing Elev (ft msl)	6.44
Well Casing Radius, $r_c$ (ft):	0.167
Well Radius, $r_w$ (ft):	0.333
DNAPL Specific Yield, $S_y$ :	0.175
DNAPL Density Ratio, $\rho_r$ :	1.050
Top of Screen (ft bgs):	9.00
Bottom of Screen (ft bgs):	24.00
DNAPL Baildown Vol. (gal.):	3.8
Effective Radius, $r_{e3}$ (ft):	0.206
Effective Radius, $r_{e2}$ (ft):	0.167
Initial Casing DNAPL Vol. (gal.):	4.90
Initial Filter DNAPL Vol. (gal.):	1.31
Sump Length (ft)	3.7
DNAPL Well Volume Rem (%)	60%

Drawdown  
Adjustment  
(ft)  
0

Submerged Screen	no
Radius of Influence Ratio	18.6
Theim Transmissivity (ft^2/day)	1.207
Constant Drawdown (ft)	0.10
Constant Discharge (ft^3/day)	0.245
DNAPL Behavior	Perched
Formation Thickness (ft)	2.10


DNAPL Transmissivity (ft^2/day)			
B&R Method	C&J Method	CB&P Method	Theim Method
0.33	1.30	0.60	1.21

Recovery Rate Estimates	
Average Transmissivity (ft^2/day)	0.74
Skimming Systems	
Maximum Skimming Drawdown (ft)	0.10
Estimated Skimming Recovery Rate (gpd)	0.80
Enhanced Skimming System	
Drawdown Enhancement (Vacuum or Water) (ft H2O)	1.00
Estimated Enhanced Skimming Recovery Rate (gpd)	8.03


Date and Time	Enter Data Here				DTP (ft bgs)	DTW (ft bgs)	TD (ft bgs)	Identified constant discharge conditions		Borehole Recharge			
	Time (min)	DTP (ft btoc)	DTW (ft btoc)	TD (ft btoc)				Water Table Depth	DNAPL Drawdown (ft)	$s_n$ (ft)	Average Time (min)	DNAPL Discharge $Q_n$ (ft^3/d)	$s_n$ (ft)
	9/2/15 13:05	-20.00	19.20	2.90	26.70	20.17	3.87	27.67	3.87	0.10			7.50
9/2/15 13:57	32	26.18	2.91	26.70	27.15	3.87	27.67	3.87	0.10	16.0			
9/2/15 14:09	44	26.12	2.89	26.70	27.09	3.85	27.67	3.85	0.10	38.0	1.077	0.10	0.58
9/2/15 14:15	50	25.96	2.89	26.70	26.93	3.86	27.67	3.86	0.10	47.0	1.063	0.10	0.74
9/2/15 14:25	60	25.94	2.89	26.70	26.91	3.85	27.67	3.85	0.10	55.0	0.269	0.10	0.76
9/2/15 14:35	70	25.90	2.88	26.70	26.87	3.84	27.67	3.84	0.10	65.0	0.457	0.10	0.80
9/2/15 14:43	78	25.90	2.88	26.70	26.87	3.84	27.67	3.84	0.10	74.0	0.628	0.10	0.80
9/2/15 14:47	81.99999999	25.86	2.87	26.70	26.83	3.84	27.67	3.84	0.10	80.0	1.257	0.10	0.84
9/2/15 14:51	86	25.82	2.87	26.70	26.79	3.84	27.67	3.84	0.10	84.0	0.677	0.10	0.88
9/2/15 14:55	90	25.78	2.87	26.70	26.75	3.84	27.67	3.84	0.10	88.0	0.595	0.10	0.92
9/2/15 15:13	108	25.72	2.86	26.70	26.69	3.83	27.67	3.83	0.10	99.0	0.298	0.10	0.98
9/2/15 15:29	124	25.64	2.86	26.70	26.61	3.83	27.67	3.83	0.10	116.0	0.287	0.10	1.06
9/2/15 16:11	166	25.60	2.84	26.70	26.57	3.81	27.67	3.81	0.10	145.0	0.146	0.10	1.10
9/2/15 16:23	178	25.56	2.85	26.70	26.53	3.81	27.67	3.81	0.10	172.0	0.314	0.10	1.14
9/2/15 16:55	210	25.54	2.84	26.70	26.51	3.80	27.67	3.80	0.10	194.0	0.321	0.10	1.16
9/2/15 17:03	218	25.52	2.84	26.70	26.49	3.80	27.67	3.80	0.10	214.0	0.268	0.10	1.18
9/2/15 17:11	226	25.52	2.84	26.70	26.49	3.80	27.67	3.80	0.10	222.0	0.262	0.10	1.18
9/2/15 17:15	230	25.48	2.84	26.70	26.45	3.80	27.67	3.80	0.10	228.0	0.237	0.10	1.22
9/2/15 17:33	248	25.46	2.83	26.70	26.43	3.80	27.67	3.80	0.10	239.0	0.265	0.10	1.24
9/2/15 17:35	250	25.44	2.83	26.70	26.41	3.80	27.67	3.80	0.10	249.0	0.310	0.10	1.26
9/2/15 17:43	258	25.38	2.84	26.70	26.35	3.80	27.67	3.80	0.10	254.0	0.296	0.10	1.32
9/2/15 18:21	296	25.34	2.83	26.70	26.31	3.79	27.67	3.79	0.10	277.0	0.284	0.10	1.36
9/2/15 18:25	300	25.32	2.83	26.70	26.29	3.79	27.67	3.79	0.10	298.0	0.284	0.10	1.38
9/2/15 18:29	304	25.30	2.83	26.70	26.27	3.79	27.67	3.79	0.10	302.0	0.254	0.10	1.40
9/2/15 18:33	308	25.30	2.83	26.70	26.27	3.79	27.67	3.79	0.10	306.0	0.254	0.10	1.40
9/2/15 18:57	332	25.18	2.83	26.70	26.15	3.79	27.67	3.79	0.10	320.0	0.295	0.10	1.52
9/2/15 19:45	380	25.14	2.83	26.70	26.11	3.79	27.67	3.79	0.10	356.0	0.227	0.10	1.56

Well Designation:	RW3-5
Date:	9/2/15


**Figure 1**




**Figure 2**




**Figure 3**




**Figure 4**



**Figure 5**




**Figure 6**




Well Designation:	RW3-5
Date:	9/2/15


**Figure 7**




**Figure 8**



**Figure 9**




**Figure 10**



## RW4-1 (MW-123) Transducer Data Representation

September 2, 2015 Baildown Test



Well Designation:

MW-123

Date:

2-Sep-15

Amount of volume to remove (gal)

7.52

TEST 1	
Ground Surface Elev (ft msl)	6.00
Top of Casing Elev (ft msl)	5.54
Well Casing Radius, $r_c$ (ft):	0.167
Well Radius, $r_w$ (ft):	0.417
DNAPL Specific Yield, $S_y$ :	0.175
DNAPL Density Ratio, $\rho_r$ :	1.110
Top of Screen (ft bgs):	6.00
Bottom of Screen (ft bgs):	16.00
DNAPL Baildown Vol. (gal.):	4.0
Effective Radius, $r_{e3}$ (ft):	0.231
Effective Radius, $r_{e2}$ (ft):	0.167
Initial Casing DNAPL Vol. (gal.):	4.47
Initial Filter DNAPL Vol. (gal.):	3.04
Sump Length (ft)	1.8
DNAPL Well Volume Rem (%)	53%

Drawdown  
Adjustment  
(ft)

Submerged Screen	no
Radius of Influence Ratio	22.0
Theim Transmissivity (ft^2/day)	0.150
Constant Drawdown (ft)	0.34
Constant Discharge (ft^3/day)	0.099
DNAPL Behavior	Perched
Formation Thickness (ft)	3.07


DNAPL Transmissivity (ft^2/day)			
B&R Method	C&J Method	CB&P Method	Theim Method
0.08	0.12	0.07	0.15

Recovery Rate Estimates	
Average Transmissivity (ft^2/day)	0.09
Skimming Systems	
Maximum Skimming Drawdown (ft)	0.34
Estimated Skimming Recovery Rate (gpd)	0.31
Enhanced Skimming System	
Drawdown Enhancement (Vacuum or Water) (ft H2O)	1.00
Estimated Enhanced Skimming Recovery Rate (gpd)	1.14


Date and Time	Enter Data Here				DTP (ft bgs)	DTW (ft bgs)	TD (ft bgs)	Identified constant discharge conditions		Borehole Recharge			
	Time (min)	DTP (ft btoc)	DTW (ft btoc)	TD (ft btoc)				Water Table Depth	DNAPL Drawdown (ft)	$s_n$ (ft)	Average Time (min)	DNAPL Discharge $Q_n$ (ft^3/d)	$s_n$ (ft)
	9/2/16 17:02	-10.00	10.47	3.17	17.32	10.93	3.63	17.78	3.63	0.34			6.85
9/2/16 21:00	48	15.33	3.21	17.32	15.79	3.67	17.78	3.67	0.34	24.0			
9/2/16 21:18	66.00000001	15.32	3.17	17.32	15.78	3.63	17.78	3.63	0.34	57.0	0.101	0.34	2.00
9/3/16 2:04	352	15.31	3.19	17.32	15.77	3.65	17.78	3.65	0.34	209.0	0.006	0.34	2.01
9/3/16 2:18	366	15.31	3.19	17.32	15.77	3.65	17.78	3.65	0.34	359.0	0.130	0.34	2.01
9/3/16 2:22	370	15.30	3.19	17.32	15.76	3.65	17.78	3.65	0.34	368.0	0.454	0.34	2.02
9/3/16 2:32	380	15.28	3.19	17.32	15.74	3.65	17.78	3.65	0.34	375.0	0.147	0.34	2.04
9/3/16 3:10	418	15.28	3.18	17.32	15.74	3.64	17.78	3.64	0.34	399.0	0.085	0.34	2.04
9/3/16 3:24	432	15.26	3.18	17.32	15.72	3.64	17.78	3.64	0.34	425.0	0.143	0.34	2.06
9/3/16 3:36	444	15.26	3.18	17.32	15.72	3.64	17.78	3.64	0.34	438.0	0.079	0.34	2.06
9/3/16 3:48	456	15.25	3.17	17.32	15.71	3.63	17.78	3.63	0.34	450.0	0.151	0.34	2.07
9/3/16 4:10	478	15.25	3.17	17.32	15.71	3.63	17.78	3.63	0.34	467.0	0.117	0.34	2.07
9/3/16 4:12	480	15.24	3.17	17.32	15.70	3.63	17.78	3.63	0.34	479.0	0.151	0.34	2.08
9/3/16 4:50	518	15.22	3.17	17.32	15.68	3.63	17.78	3.63	0.34	499.0	0.113	0.34	2.10
9/3/16 4:58	526	15.22	3.17	17.32	15.68	3.63	17.78	3.63	0.34	522.0	0.108	0.34	2.10
9/3/16 5:10	538	15.20	3.17	17.32	15.66	3.63	17.78	3.63	0.34	532.0	0.112	0.34	2.12
9/3/16 6:24	612	15.19	3.17	17.32	15.65	3.63	17.78	3.63	0.34	575.0	0.108	0.34	2.13
9/3/16 6:50	638	15.19	3.18	17.32	15.65	3.64	17.78	3.64	0.34	625.0	0.110	0.34	2.13
9/3/16 6:52	640	15.17	3.18	17.32	15.63	3.64	17.78	3.64	0.34	639.0	0.107	0.34	2.15
9/3/16 7:12	660	15.16	3.18	17.32	15.62	3.64	17.78	3.64	0.34	650.0	0.120	0.34	2.16
9/3/16 7:20	668	15.16	3.18	17.32	15.62	3.64	17.78	3.64	0.34	664.0	0.114	0.34	2.16
9/3/16 7:56	704	15.14	3.18	17.32	15.60	3.64	17.78	3.64	0.34	686.0	0.117	0.34	2.18
9/3/16 8:18	726	15.13	3.18	17.32	15.59	3.64	17.78	3.64	0.34	715.0	0.137	0.34	2.19
9/3/16 8:34	742	15.13	3.18	17.32	15.59	3.64	17.78	3.64	0.34	734.0	0.162	0.34	2.19
9/3/16 8:44	752	15.12	3.18	17.32	15.58	3.64	17.78	3.64	0.34	747.0	0.115	0.34	2.20
9/3/16 8:52	760	15.10	3.18	17.32	15.56	3.64	17.78	3.64	0.34	756.0	0.124	0.34	2.22
9/3/16 9:12	780	15.10	3.19	17.32	15.56	3.65	17.78	3.65	0.34	770.0	0.114	0.34	2.22

Well Designation:	MW-123
Date:	9/2/15


**Figure 1**




**Figure 2**




**Figure 3**




**Figure 4**



**Figure 5**




**Figure 6**




Well Designation:	MW-123
Date:	9/2/15


**Figure 7**




**Figure 8**



**Figure 9**



**Figure 10**



## RW4-2 (MW-402) Transducer Data Representation

October 1, 2015 Baildown Test

12:00 PM      2:00 PM      4:00 PM      6:00 PM      8:00 PM      10:00 PM      12:00 AM

0

Depth (ft bTOC)


5

10

15

20

25



— Depth to Water

— Total Depth

— Depth to NAPL

● Depth to NAPL (Manual)

— · · Top of Screen

● Depth to Water (Manual)

— — Bottom of Screen

Well Designation:  
Date:

MW-402  
1-Oct-15

Amount of volume to remove (gal) 6.37

TEST 1	
Ground Surface Elev (ft msl)	7.10
Top of Casing Elev (ft msl)	6.16
Well Casing Radius, $r_c$ (ft):	0.167
Well Radius, $r_w$ (ft):	0.333
DNAPL Specific Yield, $S_y$ :	0.175
DNAPL Density Ratio, $\rho_r$ :	1.110
Top of Screen (ft bgs):	6.20
Bottom of Screen (ft bgs):	16.20
DNAPL Baildown Vol. (gal.):	4.0
Effective Radius, $r_{e3}$ (ft):	0.206
Effective Radius, $r_{e2}$ (ft):	0.167
Initial Casing DNAPL Vol. (gal.):	5.30
Initial Filter DNAPL Vol. (gal.):	1.07
Sump Length (ft)	5.0
DNAPL Well Volume Rem (%)	63%

**Drawdown  
Adjustment**


Submerged Screen	no
Radius of Influence Ratio	15.2
Theim Transmissivity (ft <sup>2</sup> /day)	28.136
Constant Drawdown (ft)	0.20
Constant Discharge (ft <sup>3</sup> /day)	10.995
DNAPL Behavior	Perched
Formation Thickness (ft)	2.12

DNAPL Transmissivity (ft <sup>2</sup> /day)			
B&R Method	C&J Method	CB&P Method	Theim Method
14.12	22.00	10.00	28.14


<b>Recovery Rate Estimates</b>	
Average Transmissivity (ft <sup>2</sup> /day)	15.37
<b>Skimming Systems</b>	
Maximum Skimming Drawdown (ft)	0.23
Estimated Skimming Recovery Rate (gpd)	36.59
<b>Enhanced Skimming System</b>	
Drawdown Enhancement (Vacuum or Water) (ft H <sub>2</sub> O)	1.00
Estimated Enhanced Skimming Recovery Rate (gpd)	177.93

Well Designation:	MW-402
Date:	9/2/15

Figure 1



**Figure 2**



**Figure 3**







Figure 4



**Figure 5**




**Figure 6**




Well Designation:	MW-402
Date:	9/2/15


**Figure 7**




**Figure 8**



**Figure 9**



**Figure 10**



# Appendix C

## NAPL Physical Parameters Lab Report



## **ANALYTICAL REPORT**

For:

**Quanta - NAPL Recovery**

**ASL Report #: P3049**

**Project ID: 662566.HW.50.54**

**Attn: Kyle Block**

Authorized and Released By:

**Laboratory Project Manager**

**Tiffany Hill**

**(541) 758-0235 ext.23109**

**October 01, 2015**

All analyses performed by CH2M HILL are clearly indicated. Any subcontracted analyses are included as appended reports as received from the subcontracted laboratory. The results included in this report only relate to the samples listed on the following Sample Cross-Reference page. This report shall not be reproduced except in full, without the written approval of the laboratory.

Any unusual difficulties encountered during the analysis of your samples are discussed in the attached case narratives.



Accredited in accordance with NELAP:  
Oregon (100022)  
Louisiana (05031)

**Sample Receipt Comments**

We certify that the test results meet all NELAP requirements.

**Sample Cross-Reference**

<b>ASL Sample ID</b>	<b>Client Sample ID</b>	<b>Date/Time Collected</b>	<b>Date Received</b>
P304901	RW3-5-GW-083115	08/31/15 10:50	09/04/15
P304902	MW-402-GW-083115	08/31/15 15:20	09/04/15
P304903	RW3-5-NAPL-090215	09/02/15 10:30	09/04/15
P304904	MW-402-NAPL-090215	09/02/15 13:50	09/04/15



**Density and Specific Gravity by ASTM D1217 and Viscosity by ASTM D445**
*Quanta*
*Analysis By: KGC*
*Reviewed By: SMB*

Sample Name	Matrix	Temperature	Specific Gravity	Density	Viscosity
		°F	-	g/mL	cP
RW3-5-GW	Water	50	1.00	1.00	1.14
		70	1.00	1.00	1.08
		100	1.00	0.99	0.87
MW-402-GW	Water	50	1.01	1.01	1.23
		70	1.00	1.00	1.13
		101	0.99	0.98	0.84
RW3-5-NAPL	NAPL	50	1.06	1.06	7.59
		70	1.05	1.05	5.00
		100	1.05	1.04	3.63
MW-402-NAPL	NAPL	50	1.11	1.11	267
		70	1.11	1.11	110
		100	1.11	1.10	25.3
MW-402-Emulsion	NAPL	50	1.01	1.01	35.3
		70	1.00	1.00	7.51
		100	0.99	0.99	2.38
<b>Previous Results (2014)</b>					
TW-01-GW	Water	50	1.00	1.00	1.06
		70	1.00	1.00	1.04
		100	1.00	0.99	0.94
TW-01-NAPL	NAPL	50	1.05	1.05	16.0
		70	1.04	1.04	10.1
		100	1.03	1.02	6.27
<b>Previous Results (2013)</b>					
MW123B	Water	50	0.99	0.99	1.06
		70.9	0.98	0.98	1.05
		100	0.97	0.96	0.89
MW130B	Water	50	1.03	1.03	1.13
		70.9	1.01	1.01	1.08
		100	1.00	0.99	0.95
MW123B-NP	NAPL	50	1.11	1.11	522
		70.9	1.11	1.11	244
		100	1.11	1.10	83.3
MW130B-NP	NAPL	50	1.06	1.06	15.4
		70.9	1.06	1.06	14.2
		100	1.06	1.05	12.2

Density and specific gravity measured by ASTM D1217

\*Groundwater viscosity was measured by ASTM D445 with a glass viscometer. NAPL viscosity was measured with a Brookfield rotational viscometer.

Quality Control	
<i>Density of millipore water measured at 70 °F</i>	
Measured Density (g/mL):	0.9797
Published Density (g/mL):	0.9983
RPD:	-1.8791
Quality Control- Glass Tube Viscometer	
<i>Viscosity of millipore water measured at 70 °F</i>	
Measured Viscosity (cP):	1.066
Published Viscosity (cP):	1.000
RPD:	6.383
Quality Control- Rotational Viscometer	
<i>Viscosity of QC Standard measured at 70 °F</i>	
Measured Viscosity (cP):	9.4
Viscosity of QC Standard (cP):	9.3
RPD:	0.803

## Chain of Custody Record

Client Contact		Analysis Turnaround Time					Preservation Used							For Lab Use Only:			
Project Name: Quanta NAPL Recovery		TAT is business days TAT if different from below _____  <input checked="" type="checkbox"/> 14 days (STD) <input type="checkbox"/> 3 day * <input type="checkbox"/> 7 days * <input type="checkbox"/> 2 days * <input type="checkbox"/> 5 days * <input type="checkbox"/> 1 day *  * (Surcharges will apply)					Analysis Requested							Job / SDG No.: P30419			
Project # or PO #: 662566.HW.50.54														Custody Seals intact? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
Company Name: CH2M							Cooler Temp : 89 °C <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No										
Address: 18 Tremont St, Suite 700							Therm ID No.: 173 Therm Exp. 10/15										
City/State/Zip: Boston, MA 02108							Packing Material: Circle below										
Project Manager: Kyle Block							Ice Blue Ice Box Bubble Wrap										
Phone #: 617-626-7013							Radiological Screen? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No										
Report to email: kyle.block@ch2m.com																	
Sample Identification (Limit of 20 characters)		Sample Date	Sample Time	Sample Type (C=Comp, G=Grab)	Matrix (Water, Soil, Air)	Total # of Cont.	Density ASTM D1217	Viscosity ASTM D445	Sample Specific Notes:							Lab ID:	
RW3-5-GW-083115		8/31/2015	10:50	G	W	1	X	X								1	
MW-402-GW-083115		8/31/15	15:20	G	W	1	X	X								2	
RW3-5-NAPL-090215		9/2/15	10:30	G	N	1	X	X								3	
MW-402-NAPL-090215		9/2/15	13:50	G	N	1	X	X								4	
Preservation Used: 1=Ice, 2=HCl; 3=H2SO4; 4=HNO3; 5=NaOH; 6= Other _____																	
Possible Hazard Identification: Are any samples from a listed EPA Hazardous Waste?							Sample Disposal (A fee may be added if samples are retained longer than 30 day per client request, samples are returned to client, or classified as hazardous.)										
<input type="checkbox"/> Non-Hazard <input type="checkbox"/> Flammable <input type="checkbox"/> Skin Irritant <input type="checkbox"/> Poison B <input type="checkbox"/> Unknown							<input type="checkbox"/> Return to Client <input type="checkbox"/> Disposal by Lab <input type="checkbox"/> Archive for _____ months										
Sampled By: <i>Kyle Block</i>		Date/Time: 9/3/15 1800			Relinquished by: <i>Kyle Block</i>			Date/Time: 9/3/15 1800									
Received by: <i>John</i>		Date/Time:			Relinquished by:			Date/Time:									
Received by: <i>John</i>		Date/Time:			Relinquished by:			Date/Time:									
Received in Laboratory by: <i>Bengt Castro</i>		Date/Time: 9/4/15 10:00			Shipped Via: <input type="checkbox"/> UPS <input type="checkbox"/> Fed-Ex <input type="checkbox"/> USPS <input type="checkbox"/> Other			Tracking #:									
Special Instructions/QC Requirements																	

SDG ID: P3049

Date Received:09/04/15

Client/Project: Quanta NAPL

Received By:JVP

Were custody seals intact and on the outside of the cooler?	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A	
Shipping Record:	<input type="checkbox"/> Hand Delivered	<input checked="" type="checkbox"/> On File	<input type="checkbox"/> COC	
Radiological Screening for DoD	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A	
Packing Material:	<input type="checkbox"/> Hand Delivered	<input type="checkbox"/> Ice	<input type="checkbox"/> Blue Ice	<input checked="" type="checkbox"/> Box
Temp OK? (<6C) Therm ID: TH173 Exp. 10/15	18.9 °C	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Was a Chain of Custody (CoC) Provided?	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A	
Was the CoC correctly filled out (If No, document below)	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A	
Did sample labels agree with COC? (If No, document below)	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A	
Did the CoC list a correct bottle count and the preservative types (No=Correct on CoC)	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A	
Were the sample containers in good condition (broken or leaking)?	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A	
Was enough sample volume provided for analysis? (If No, document below)	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A	
Containers supplied by ASL?	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A	
Any sample with < 1/2 holding time remaining? If so contact LPM	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No	<input type="checkbox"/> N/A	
Samples have multi-phase? If yes, document on SRER	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No	<input type="checkbox"/> N/A	
All water VOCs free of air bubbles? No, document on SRER	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A	
pH of all samples met criteria on receipt? If "No", preserve and document below.	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A	
Dissolved/Soluble metals filtered in the field?	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A	
Dissolved/Soluble metals have sediment in bottom of container? If so document below.	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A	

**Preservation Adjustment**

Sample ID	Reagent	Reagent Lot Number	Volume Added	Initials/Time	24 hour pH check Initials/Time

Did pH of all metals samples preserved upon receipt meet criteria 24 hours after preservation?  Yes  No

**Sample Exception Report** (The following exceptions were noted)

Client was notified on:	Client contact:
<u>Resolution to Exception:</u>	

## Appendix D

# Waste Characterization and Disposal

Please print or type. (Form designed for use on elite (12-pitch) typewriter.)

Form Approved. OMB No. 2050-0039

<b>UNIFORM HAZARDOUS WASTE MANIFEST</b>		1. Generator ID Number NJD 981 139 371	2. Page 1 of 1	3. Emergency Response Phone (800) 535-5053	4. Manifest Tracking Number <b>013642781 JJK</b>	
5. Generator's Name and Mailing Address 6100 PHILADELPHIA AVE		Generator's Site Address (if different than mailing address) HONEYWELL INTERNATIONAL INC 163 RIVER ROAD				
CLAYMONT, DE 19703 Generator's Phone: (302) 791-6738		EDGEWATER, NJ 07020				
6. Transporter 1 Company Name EQ NORTHEAST, INC.		U.S. EPA ID Number <b>MAD 084 814 136</b>				
7. Transporter 2 Company Name E&L Industrial Services		U.S. EPA ID Number <b>MIL 435642742</b>				
8. Designated Facility Name and Site Address 49350 N I-94 SERVICE DRIVE BELLEVILLE, MI 48111 Facility's Phone: (800) 592-5489		U.S. EPA ID Number <b>MID 000 724 831</b>				
<b>GENERATOR</b>	9a. HM 9b. U.S. DOT Description (including Proper Shipping Name, Hazard Class, ID Number, and Packing Group (if any)) <b>1. Non Hazardous Solid Waste, Not DOT Not RCRA Regulated, None, None, None</b>		10. Containers No. OM 25	11. Total Quantity 10,000	12. Unit Wt./Vol. P	
	2.					
	3.					
	4.					
14. Special Handling Instructions and Additional Information 1. C142137MDI / (S) Soil from Sampling Drilling Event						
15. GENERATOR/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations. If export shipment and I am the Primary Exporter, I certify that the contents of this consignment conform to the terms of the attached EPA Acknowledgment of Consent. I certify that the waste minimization statement identified in 40 CFR 262.27(a) (if I am a large quantity generator) or (b) (if I am a small quantity generator) is true.						
Generator/Offeror's Printed/Typed Name <i>Austin Harclerode as Agent of Honeywell International Inc.</i>		Signature <i>Austin Harclerode as Agent of Honeywell International Inc.</i> Month Day Year 10 19 15				
16. International Shipments <input type="checkbox"/> Import to U.S. <input type="checkbox"/> Export from U.S.		Port of entry/exit: Date leaving U.S.:				
Transporter signature (for exports only):						
<b>TRANSPORTER INT'L</b>	17. Transporter Acknowledgment of Receipt of Materials Transporter 1 Printed/Typed Name <i>Joseph J. Done</i>		Signature <i>JJD</i>	Month 10	Day 19	Year 15
	Transporter 2 Printed/Typed Name <i>Tonya L Stewart</i>		Signature <i>TL</i>	Month 10	Day 31	Year 15
18. Discrepancy						
18a. Discrepancy Indication Space <input type="checkbox"/> Quantity <input type="checkbox"/> Type <input type="checkbox"/> Residue <input type="checkbox"/> Partial Rejection <input type="checkbox"/> Full Rejection		Manifest Reference Number:				
18b. Alternate Facility (or Generator)		U.S. EPA ID Number				
Facility's Phone:						
18c. Signature of Alternate Facility (or Generator)		Month Day Year				
19. Hazardous Waste Report Management Method Codes (i.e., codes for hazardous waste treatment, disposal, and recycling systems)						
1. LIW		2.	3.	4.		
20. Designated Facility Owner or Operator: Certification of receipt of hazardous materials covered by the manifest except as noted in Item 18a						
Printed/Typed Name <i>Unit Serial</i>		Signature <i>RL</i>		Month 10	Day 19	Year 15

Please print or type. (Form designed for use on elite (12-pitch) typewriter.)

Form Approved. OMB No. 2050-0039

<b>UNIFORM HAZARDOUS WASTE MANIFEST</b>		1. Generator ID Number NJD 981 139 371	2. Page 1 of 1	3. Emergency Response Phone (800) 535-5053	4. Manifest Tracking Number <b>013642782 JJK</b>		
5. Generator's Name and Mailing Address 6100 PHILADELPHIA PIKE		Generator's Site Address (if different than mailing address) 163 RIVER ROAD					
CLAYMONT, DE 19703 Generator's Phone: (302) 791-6738		EDGEWATER, NJ 07020					
6. Transporter 1 Company Name <b>EQ NORTHEAST, INC.</b>		U.S. EPA ID Number <b>MAD 084 814 136</b>					
7. Transporter 2 Company Name		U.S. EPA ID Number					
8. Designated Facility Name and Site Address 1923 FREDERICK DETROIT, MI 48211 Facility's Phone: (313) 347-1300		U.S. EPA ID Number <b>MID 980 991 566</b>					
<b>GENERATOR</b>	9a. HM	9b. U.S. DOT Description (including Proper Shipping Name, Hazard Class, ID Number, and Packing Group (if any))  <b>X</b> 1. NA3082, Hazardous waste, liquid, n.o.s., (Benzene), 9, PGIII, ERG #171	10. Containers No.  <b>14</b>	11. Total Quantity  <b>700</b>	12. Unit Wt./Vol.  <b>G</b>	13. Waste Codes  <b>D018</b>	
		2. Non Hazardous Solid Waste, Not DOT Not RCRA Regulated, None, None, None	  <b>003</b>	  <b>225</b>	  <b>P</b>		
		3. Non Hazardous Liquid Waste, Not DOT Not RCRA Regulated, None, None, None	  <b>002</b>	  <b>110</b>	  <b>G</b>	  <b>029L</b>	
		4.					
14. Special Handling Instructions and Additional Information 1. J150019DET / (L,E) Water with NAPL 2. J150018DET / (S) PPE & Plastic from Drilling 3. J150020DET / (L) Drilling Fluid/Mud							
15. GENERATOR'S/OFFEROR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by the proper shipping name, and are classified, packaged, marked and labeled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations. If export shipment and I am the Primary Exporter, I certify that the contents of this consignment conform to the terms of the attached EPA Acknowledgment of Consent. I certify that the waste minimization statement identified in 40 CFR 262.27(a) (if I am a large quantity generator) or (b) (if I am a small quantity generator) is true.							
<b>TRANSPORTER INT'L</b>	Generators/Offeror's Printed/Typed Name <b>Austin Harrelson as Agent of Honeywell International Inc.</b>		Signature <i>Austin Harrelson as Agent of Honeywell International Inc.</i>		Month	Day	Year
	16. International Shipments <input checked="" type="checkbox"/> Import to U.S. <input type="checkbox"/> Export from U.S.		Port of entry/exit:				
	Transporter signature (for exports only):		Date leaving U.S.:				
<b>DESIGNATED FACILITY</b>	17. Transporter Acknowledgment of Receipt of Materials  <b>Joseph J. Doners</b>		Signature <i>Joseph J. Doners</i>		Month	Day	Year
	Transporter 2 Printed/Typed Name  <b>Branch Hough</b>		Signature <i>Branch Hough</i>		Month	Day	Year
	18. Discrepancy 18a. Discrepancy Indication Space <input type="checkbox"/> Quantity <input type="checkbox"/> Type <input type="checkbox"/> Residue <input type="checkbox"/> Partial Rejection <input type="checkbox"/> Full Rejection		Manifest Reference Number:				
18b. Alternate Facility (or Generator)		U.S. EPA ID Number					
Facility's Phone:							
18c. Signature of Alternate Facility (or Generator)		Month Day Year					
19. Hazardous Waste Report Management Method Codes (i.e., codes for hazardous waste treatment, disposal, and recycling systems)							
1. <b>H141</b>		2. <b>NONE</b>		3. <b>LIW</b>		4.	
20. Designated Facility Owner or Operator: Certification of receipt of hazardous materials covered by the manifest except as noted in Item 18a							
Printed/Typed Name  <b>Branch Hough</b>		Signature <i>Branch Hough</i>		Month Day Year <b>06/21/15</b>			



Reissue #1  
11/04/15

Technical Report for

Honeywell International Inc.

CHMHLMB: Quanta Resources Corporation Superfund Site, Edgewater, NJ

Accutest Job Number: JC1982

Sampling Date: 08/19/15

Report to:

CH2M Hill

Theresa.Himmer@CH2M.com

ATTN: Theresa Himmer

Total number of pages in report: **65**



Test results contained within this data package meet the requirements of the National Environmental Laboratory Accreditation Program and/or state specific certification programs as applicable.

*Nancy T. Cole*

Nancy Cole  
Laboratory Director

Client Service contact: Marty Vitanza 732-329-0200

Certifications: NJ(12129), NY(10983), CA, CT, DE, FL, IL, IN, KS, KY, LA, MA, MD, MI, MT, NC, OH VAP (CL0056), AK (UST-103), AZ (AZ0786), PA, RI, SC, TN, TX, VA, WV, DoD ELAP (L-A-B L2248)

This report shall not be reproduced, except in its entirety, without the written approval of Accutest Laboratories.  
Test results relate only to samples analyzed.



October 22, 2015

Mr. Kyle Block  
CH2M Hill  
18 Tremont Street  
Suite 700  
Boston, MA 02108

Re: Extraction Method Documentation Correction

In a recent internal review, Accutest identified some extraction method data entry errors for the projects and samples listed below. The proper extraction method was used, however the wrong method reference was entered in LIMS. The extraction method documentation change has no impact on the reported data or associated quality control. The extraction methods in use were approved and certified methods, and the laboratory adhered to all quality control requirements for these methods.

Project	Sample Numbers
CHMHLMAB: Quanta Resources Corporation Superfund Site, Edgewater, NJ	JC1982-1, -2, -3

The LIMS has been corrected so that the extraction method is in line with the extraction method as documented on the raw data. We are not planning to automatically reissue these reports, however if you need a re-issued report or EDD, please let us know, and we'll be happy to do so.

A corrective action has been generated to prevent issues of this type in the future. We apologize for any inconvenience that this may have caused. Should you have any further questions or require additional information, please do not hesitate to contact me.

Sincerely,

A handwritten signature in black ink that reads "Nancy T. Cole".

Nancy Cole  
Laboratory Director, Accutest, NJ  
732-329-0200, ext 1301

# Table of Contents

-1-

<b>Section 1: Sample Summary .....</b>	<b>4</b>
<b>Section 2: Summary of Hits .....</b>	<b>5</b>
<b>Section 3: Sample Results .....</b>	<b>10</b>
<b>3.1: JC1982-1: IDW-SO-1-081915 .....</b>	<b>11</b>
<b>3.2: JC1982-1A: IDW-SO-1-081915 .....</b>	<b>20</b>
<b>3.3: JC1982-2: IDW-SO-2-081915 .....</b>	<b>25</b>
<b>3.4: JC1982-2A: IDW-SO-2-081915 .....</b>	<b>33</b>
<b>3.5: JC1982-3: IDW-SO-3-081915 .....</b>	<b>38</b>
<b>3.6: JC1982-3A: IDW-SO-3-081915 .....</b>	<b>46</b>
<b>3.7: JC1982-4: IDW-AQ-081915 .....</b>	<b>51</b>
<b>Section 4: Misc. Forms .....</b>	<b>63</b>
<b>4.1: Chain of Custody .....</b>	<b>64</b>



## Sample Summary

Honeywell International Inc.

Job No: JC1982

CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ

Sample Number	Collected Date	Time By	Received	Matrix Code	Type	Client Sample ID
JC1982-1	08/19/15	10:30 AH	08/20/15	SO	Soil	IDW-SO-1-081915
JC1982-1A	08/19/15	10:30 AH	08/20/15	SO	Soil	IDW-SO-1-081915
JC1982-2	08/19/15	10:45 AH	08/20/15	SO	Soil	IDW-SO-2-081915
JC1982-2A	08/19/15	10:45 AH	08/20/15	SO	Soil	IDW-SO-2-081915
JC1982-3	08/19/15	11:00 AH	08/20/15	SO	Soil	IDW-SO-3-081915
JC1982-3A	08/19/15	11:00 AH	08/20/15	SO	Soil	IDW-SO-3-081915
JC1982-4	08/19/15	11:15 AH	08/20/15	AQ	Water	IDW-AQ-081915

---

Soil samples reported on a dry weight basis unless otherwise indicated on result page.

**Summary of Hits**

Job Number: JC1982

Account: Honeywell International Inc.

Project: CHMHLMB: Quanta Resources Corporation Superfund Site, Edgewater, NJ

Collected: 08/19/15

Lab Sample ID Analyte	Client Sample ID IDW-SO-1-081915	Result/ Qual	RL	MDL	Units	Method
--------------------------	-------------------------------------	-----------------	----	-----	-------	--------

Benzene <sup>a</sup>	7920	3000	790	ug/kg	SW846 8260C
Ethylbenzene <sup>a</sup>	21700	5900	970	ug/kg	SW846 8260C
Isopropylbenzene <sup>a</sup>	5310 J	12000	630	ug/kg	SW846 8260C
Styrene <sup>a</sup>	12700	12000	1100	ug/kg	SW846 8260C
Toluene <sup>a</sup>	35400	5900	1200	ug/kg	SW846 8260C
m,p-Xylene <sup>a</sup>	55500	5900	2100	ug/kg	SW846 8260C
o-Xylene <sup>a</sup>	25700	5900	1600	ug/kg	SW846 8260C
Xylene (total) <sup>a</sup>	81200	5900	1600	ug/kg	SW846 8260C
Total TIC, Volatile	4165000 J			ug/kg	
2,4-Dimethylphenol	2450	210	93	ug/kg	SW846 8270D
3&4-Methylphenol	452	85	47	ug/kg	SW846 8270D
Phenol	293	85	28	ug/kg	SW846 8270D
Acenaphthene	67400	2100	430	ug/kg	SW846 8270D
Acenaphthylene	9770	210	32	ug/kg	SW846 8270D
Anthracene	43900	2100	480	ug/kg	SW846 8270D
Benzo(a)anthracene	18100	210	41	ug/kg	SW846 8270D
Benzo(a)pyrene	13600	210	51	ug/kg	SW846 8270D
Benzo(b)fluoranthene	14500	210	42	ug/kg	SW846 8270D
Benzo(g,h,i)perylene	7580	210	70	ug/kg	SW846 8270D
Benzo(k)fluoranthene	5730	210	68	ug/kg	SW846 8270D
1,1'-Biphenyl	25100	4200	420	ug/kg	SW846 8270D
Carbazole	12900	420	47	ug/kg	SW846 8270D
Chrysene	18300	210	52	ug/kg	SW846 8270D
Dibenzo(a,h)anthracene	1640	42	10	ug/kg	SW846 8270D
Dibenzofuran	53100	4200	340	ug/kg	SW846 8270D
bis(2-Ethylhexyl)phthalate	579	85	14	ug/kg	SW846 8270D
Fluoranthene	81200	2100	740	ug/kg	SW846 8270D
Fluorene	72000	2100	1600	ug/kg	SW846 8270D
Indeno(1,2,3-cd)pyrene	7740	210	68	ug/kg	SW846 8270D
2-Methylnaphthalene	184000	4200	490	ug/kg	SW846 8270D
Naphthalene	661000	8500	1300	ug/kg	SW846 8270D
Phenanthrene	171000	2100	450	ug/kg	SW846 8270D
Pyrene	55000	2100	480	ug/kg	SW846 8270D
Total TIC, Semi-Volatile	59810 J			ug/kg	
delta-BHC	7.9	0.77	0.30	ug/kg	SW846 8081B
4,4'-DDT <sup>b</sup>	62.5	0.77	0.29	ug/kg	SW846 8081B
Endosulfan sulfate <sup>b</sup>	38.4	0.77	0.44	ug/kg	SW846 8081B
Endrin ketone	23.4	0.77	0.40	ug/kg	SW846 8081B

**JC1982-1A IDW-SO-1-081915**

Corrosivity as pH	7.60 NC		su	SW846 CHAP7
Ignitability (Flashpoint)	> 200		Deg. F	SW846 CHAP7/ASTM D93

**Summary of Hits**

Job Number: JC1982

Account: Honeywell International Inc.

Project: CHMHLMB: Quanta Resources Corporation Superfund Site, Edgewater, NJ

Collected: 08/19/15

Lab Sample ID Analyte	Client Sample ID	Result/ Qual	RL	MDL	Units	Method
--------------------------	------------------	-----------------	----	-----	-------	--------

Benzene	0.139	0.0025	0.0012	mg/l	SW846 8260C
3&4-Methylphenol	0.0168 J	0.020	0.0067	mg/l	SW846 8270D
Pyridine	0.0047 J	0.020	0.0027	mg/l	SW846 8270D

**JC1982-2 IDW-SO-2-081915**

Benzene a	26500	2900	760	ug/kg	SW846 8260C
Ethylbenzene a	116000	5700	940	ug/kg	SW846 8260C
Isopropylbenzene a	10300 J	11000	610	ug/kg	SW846 8260C
Methylcyclohexane a	5170 J	11000	1300	ug/kg	SW846 8260C
Toluene a	24500	5700	1200	ug/kg	SW846 8260C
m,p-Xylene a	185000	5700	2000	ug/kg	SW846 8260C
o-Xylene a	86800	5700	1600	ug/kg	SW846 8260C
Xylene (total) a	272000	5700	1600	ug/kg	SW846 8260C
Total TIC, Volatile	6868000 J			ug/kg	
Acenaphthene	13600	470	94	ug/kg	SW846 8270D
Acenaphthylene	776	47	7.0	ug/kg	SW846 8270D
Acetophenone	366	230	15	ug/kg	SW846 8270D
Anthracene	11300	470	100	ug/kg	SW846 8270D
Benzo(a)anthracene	14800	470	90	ug/kg	SW846 8270D
Benzo(a)pyrene	13200	470	110	ug/kg	SW846 8270D
Benzo(b)fluoranthene	13900	470	92	ug/kg	SW846 8270D
Benzo(g,h,i)perylene	7400	470	150	ug/kg	SW846 8270D
Benzo(k)fluoranthene	5890	470	150	ug/kg	SW846 8270D
1,1'-Biphenyl	1200	93	9.2	ug/kg	SW846 8270D
Carbazole	1740	93	10	ug/kg	SW846 8270D
Chrysene	15000	470	110	ug/kg	SW846 8270D
Dibenzo(a,h)anthracene	1720	47	11	ug/kg	SW846 8270D
Dibenzofuran	7090	930	76	ug/kg	SW846 8270D
Fluoranthene	37500	470	160	ug/kg	SW846 8270D
Fluorene	12400	470	350	ug/kg	SW846 8270D
Indeno(1,2,3-cd)pyrene	8090	470	150	ug/kg	SW846 8270D
2-Methylnaphthalene	2530	93	11	ug/kg	SW846 8270D
Naphthalene	7840	470	69	ug/kg	SW846 8270D
Phenanthrene	40100	470	99	ug/kg	SW846 8270D
Pyrene	28000	470	110	ug/kg	SW846 8270D
Total TIC, Semi-Volatile	45640 J			ug/kg	

**JC1982-2A IDW-SO-2-081915**

Corrosivity as pH	7.62 NC		su	SW846 CHAP7
Ignitability (Flashpoint)	> 200		Deg. F	SW846 CHAP7/ASTM D93
Benzene	0.0482	0.0025	mg/l	SW846 8260C

**Summary of Hits**

Job Number: JC1982

Account: Honeywell International Inc.

Project: CHMHLMB: Quanta Resources Corporation Superfund Site, Edgewater, NJ

Collected: 08/19/15

Lab Sample ID Analyte	Client Sample ID IDW-SO-3-081915	Result/ Qual	RL	MDL	Units	Method
--------------------------	-------------------------------------	-----------------	----	-----	-------	--------

3&4-Methylphenol <sup>c</sup>	157	140	77	ug/kg	SW846 8270D
Phenol <sup>c</sup>	99.7 J	140	45	ug/kg	SW846 8270D
Acenaphthene	17800	690	140	ug/kg	SW846 8270D
Acenaphthylene <sup>c</sup>	1190	69	10	ug/kg	SW846 8270D
Anthracene	21400	690	150	ug/kg	SW846 8270D
Benzo(a)anthracene	57900	690	130	ug/kg	SW846 8270D
Benzo(a)pyrene	62200	690	170	ug/kg	SW846 8270D
Benzo(b)fluoranthene	68000	690	140	ug/kg	SW846 8270D
Benzo(g,h,i)perylene	33900	690	230	ug/kg	SW846 8270D
Benzo(k)fluoranthene	24900	690	220	ug/kg	SW846 8270D
1,1'-Biphenyl <sup>c</sup>	554	140	14	ug/kg	SW846 8270D
Carbazole	9290	1400	150	ug/kg	SW846 8270D
Chrysene	57900	690	170	ug/kg	SW846 8270D
Dibenz(a,h)anthracene	10200	690	170	ug/kg	SW846 8270D
Dibenzofuran <sup>c</sup>	4700	140	11	ug/kg	SW846 8270D
Fluoranthene	92400	6900	2400	ug/kg	SW846 8270D
Fluorene	9540	690	520	ug/kg	SW846 8270D
Indeno(1,2,3-cd)pyrene	39400	690	220	ug/kg	SW846 8270D
2-Methylnaphthalene <sup>c</sup>	2470	140	16	ug/kg	SW846 8270D
Naphthalene <sup>c</sup>	5860	69	10	ug/kg	SW846 8270D
Phenanthrene	64300	6900	1500	ug/kg	SW846 8270D
Pyrene	75200	6900	1600	ug/kg	SW846 8270D
Total TIC, Semi-Volatile	18280 J			ug/kg	
4,4'-DDT <sup>b</sup>	17.4	0.66	0.25	ug/kg	SW846 8081B
Endrin aldehyde <sup>b</sup>	26.0	0.66	0.49	ug/kg	SW846 8081B

**JC1982-3A IDW-SO-3-081915**

Corrosivity as pH	7.11 NC		su	SW846 CHAP7
Ignitability (Flashpoint)	> 200		Deg. F	SW846 CHAP7/ASTM D93
Hexachlorobenzene	0.0064 J	0.020	0.0042 mg/l	SW846 8270D

**JC1982-4 IDW-AQ-081915**

Acetone	88.6	20	6.6	ug/l	SW846 8260C
Benzene	195	1.0	0.47	ug/l	SW846 8260C
Bromodichloromethane	0.94 J	2.0	0.45	ug/l	SW846 8260C
2-Butanone (MEK)	14.4 J	20	11	ug/l	SW846 8260C
Carbon disulfide	0.68 J	4.0	0.51	ug/l	SW846 8260C
Chloroform	1.9 J	2.0	0.37	ug/l	SW846 8260C
Dibromochloromethane	0.39 J	2.0	0.31	ug/l	SW846 8260C
1,2-Dichlorobenzene	2.2	2.0	0.37	ug/l	SW846 8260C
Ethylbenzene	144	2.0	0.54	ug/l	SW846 8260C

**Summary of Hits**

Job Number: JC1982

Account: Honeywell International Inc.

Project: CHMHLMB: Quanta Resources Corporation Superfund Site, Edgewater, NJ

Collected: 08/19/15

Lab Sample ID Analyte	Client Sample ID	Result/ Qual	RL	MDL	Units	Method
Isopropylbenzene	11.3	2.0	0.47	ug/l	SW846 8260C	
Methylcyclohexane	1.7 J	10	0.44	ug/l	SW846 8260C	
4-Methyl-2-pentanone(MIBK)	7.6 J	10	2.0	ug/l	SW846 8260C	
Styrene	86.4	2.0	0.54	ug/l	SW846 8260C	
Toluene	218	2.0	0.32	ug/l	SW846 8260C	
m,p-Xylene	326	2.0	0.75	ug/l	SW846 8260C	
o-Xylene	208	2.0	0.33	ug/l	SW846 8260C	
Xylene (total)	534	2.0	0.33	ug/l	SW846 8260C	
Total TIC, Volatile	4757 J			ug/l		
2,4-Dimethylphenol	85.0	6.3	2.3	ug/l	SW846 8270D	
2-Methylphenol	4.4	2.5	1.6	ug/l	SW846 8270D	
Acenaphthene	254	50	15	ug/l	SW846 8270D	
Acenaphthylene	21.2	1.3	0.25	ug/l	SW846 8270D	
Anthracene	29.4	1.3	0.24	ug/l	SW846 8270D	
Benzo(g,h,i)perylene	1.2 J	1.3	0.39	ug/l	SW846 8270D	
1,1'-Biphenyl	70.4	1.3	0.34	ug/l	SW846 8270D	
Carbazole	199	50	8.4	ug/l	SW846 8270D	
Chrysene	3.6	1.3	0.20	ug/l	SW846 8270D	
1,4-Dioxane	1.6	1.3	0.89	ug/l	SW846 8270D	
Dibenzofuran	185 J	250	11	ug/l	SW846 8270D	
Fluoranthene	29.0	1.3	0.20	ug/l	SW846 8270D	
Fluorene	160	50	14	ug/l	SW846 8270D	
2-Methylnaphthalene	742	50	15	ug/l	SW846 8270D	
Naphthalene	4030	50	13	ug/l	SW846 8270D	
Phenanthrene	220	50	9.3	ug/l	SW846 8270D	
Pyrene	17.0	1.3	0.24	ug/l	SW846 8270D	
Benzo(a)anthracene	1.09	0.063	0.023	ug/l	SW846 8270D BY SIM	
Benzo(a)pyrene	2.53	0.063	0.037	ug/l	SW846 8270D BY SIM	
Benzo(b)fluoranthene	3.64	0.13	0.026	ug/l	SW846 8270D BY SIM	
Benzo(k)fluoranthene	0.809	0.13	0.024	ug/l	SW846 8270D BY SIM	
Dibenzo(a,h)anthracene	0.394	0.13	0.044	ug/l	SW846 8270D BY SIM	
Indeno(1,2,3-cd)pyrene	1.14	0.13	0.039	ug/l	SW846 8270D BY SIM	
Total TIC, Semi-Volatile	1418 J			ug/l		
gamma-BHC (Lindane) <sup>d</sup>	0.042	0.0074	0.0039	ug/l	SW846 8081B	
Endrin ketone <sup>e</sup>	0.024	0.0074	0.0035	ug/l	SW846 8081B	
Barium	246	200		ug/l	SW846 6010C	
Calcium	922000	25000		ug/l	SW846 6010C	
Chromium	205	10		ug/l	SW846 6010C	
Copper	33.6	10		ug/l	SW846 6010C	
Iron	1240	100		ug/l	SW846 6010C	
Lead <sup>f</sup>	24.4	15		ug/l	SW846 6010C	
Manganese	16.1	15		ug/l	SW846 6010C	
Potassium	642000	50000		ug/l	SW846 6010C	
Selenium	18.8	10		ug/l	SW846 6010C	
Sodium	814000	50000		ug/l	SW846 6010C	

**Summary of Hits**

Job Number: JC1982

Account: Honeywell International Inc.

Project: CHMHLMB: Quanta Resources Corporation Superfund Site, Edgewater, NJ

Collected: 08/19/15

Lab Sample ID Analyte	Client Sample ID	Result/ Qual	RL	MDL	Units	Method
Corrosivity as pH		12.45 NC			su	SW846 CHAP7
Ignitability (Flashpoint)		> 200			Deg. F	SW846 1010A/ASTM D93

- (a) Diluted due to high concentration of non-target compound.
- (b) More than 40 % RPD for detected concentrations between the two GC columns.
- (c) Dilution required due to viscosity of the extract matrix
- (d) There is no additional sample for re-extraction. More than 40 % RPD for detected concentrations between the two GC columns.
- (e) There is no additional sample for re-extraction.
- (f) Elevated detection limit due to dilution required for high interfering element.



## Sample Results

---

## Report of Analysis

---

**Report of Analysis**

Page 1 of 3

3

<b>Client Sample ID:</b>	IDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Method:</b>	SW846 8260C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1 <sup>a</sup>	E228675.D	1	08/28/15	TDN	n/a	n/a	VE10012
Run #2							

	<b>Initial Weight</b>	<b>Final Volume</b>	<b>Methanol Aliquot</b>
Run #1	6.2 g	10.0 ml	2.0 ul
Run #2			

**VOA TCL List**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
67-64-1	Acetone	ND	59000	13000	ug/kg	
71-43-2	Benzene	7920	3000	790	ug/kg	
74-97-5	Bromochloromethane	ND	30000	1800	ug/kg	
75-27-4	Bromodichloromethane	ND	12000	930	ug/kg	
75-25-2	Bromoform	ND	30000	1400	ug/kg	
74-83-9	Bromomethane	ND	30000	2200	ug/kg	
78-93-3	2-Butanone (MEK)	ND	59000	11000	ug/kg	
75-15-0	Carbon disulfide	ND	12000	1400	ug/kg	
56-23-5	Carbon tetrachloride	ND	12000	1400	ug/kg	
108-90-7	Chlorobenzene	ND	12000	920	ug/kg	
75-00-3	Chloroethane	ND	30000	2900	ug/kg	
67-66-3	Chloroform	ND	12000	890	ug/kg	
74-87-3	Chloromethane	ND	30000	1600	ug/kg	
110-82-7	Cyclohexane	ND	12000	1900	ug/kg	
96-12-8	1,2-Dibromo-3-chloropropane	ND	12000	3200	ug/kg	
124-48-1	Dibromochloromethane	ND	12000	1200	ug/kg	
106-93-4	1,2-Dibromoethane	ND	5900	780	ug/kg	
95-50-1	1,2-Dichlorobenzene	ND	5900	720	ug/kg	
541-73-1	1,3-Dichlorobenzene	ND	5900	930	ug/kg	
106-46-7	1,4-Dichlorobenzene	ND	5900	1300	ug/kg	
75-71-8	Dichlorodifluoromethane	ND	30000	2100	ug/kg	
75-34-3	1,1-Dichloroethane	ND	5900	840	ug/kg	
107-06-2	1,2-Dichloroethane	ND	5900	800	ug/kg	
75-35-4	1,1-Dichloroethene	ND	5900	3500	ug/kg	
156-59-2	cis-1,2-Dichloroethene	ND	5900	4600	ug/kg	
156-60-5	trans-1,2-Dichloroethene	ND	5900	3500	ug/kg	
78-87-5	1,2-Dichloropropane	ND	12000	1400	ug/kg	
10061-01-5	cis-1,3-Dichloropropene	ND	12000	700	ug/kg	
10061-02-6	trans-1,3-Dichloropropene	ND	12000	1100	ug/kg	
100-41-4	Ethylbenzene	21700	5900	970	ug/kg	
76-13-1	Freon 113	ND	30000	2700	ug/kg	
591-78-6	2-Hexanone	ND	30000	8000	ug/kg	

ND = Not detected      MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 2 of 3

3-1

3

<b>Client Sample ID:</b>	IDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Method:</b>	SW846 8260C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**VOA TCL List**

CAS No.	Compound	Result	RL	MDL	Units	Q
98-82-8	Isopropylbenzene	5310	12000	630	ug/kg	J
79-20-9	Methyl Acetate	ND	30000	5100	ug/kg	
108-87-2	Methylcyclohexane	ND	12000	1300	ug/kg	
1634-04-4	Methyl Tert Butyl Ether	ND	5900	910	ug/kg	
108-10-1	4-Methyl-2-pentanone(MIBK)	ND	30000	2700	ug/kg	
75-09-2	Methylene chloride	ND	30000	5800	ug/kg	
100-42-5	Styrene	12700	12000	1100	ug/kg	
79-34-5	1,1,2,2-Tetrachloroethane	ND	12000	1000	ug/kg	
127-18-4	Tetrachloroethene	ND	12000	1800	ug/kg	
108-88-3	Toluene	35400	5900	1200	ug/kg	
87-61-6	1,2,3-Trichlorobenzene	ND	30000	1000	ug/kg	
120-82-1	1,2,4-Trichlorobenzene	ND	30000	1000	ug/kg	
71-55-6	1,1,1-Trichloroethane	ND	12000	890	ug/kg	
79-00-5	1,1,2-Trichloroethane	ND	12000	870	ug/kg	
79-01-6	Trichloroethene	ND	5900	870	ug/kg	
75-69-4	Trichlorofluoromethane	ND	30000	1500	ug/kg	
75-01-4	Vinyl chloride	ND	12000	1200	ug/kg	
	m,p-Xylene	55500	5900	2100	ug/kg	
95-47-6	o-Xylene	25700	5900	1600	ug/kg	
1330-20-7	Xylene (total)	81200	5900	1600	ug/kg	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
1868-53-7	Dibromofluoromethane	93%		70-122%
17060-07-0	1,2-Dichloroethane-D4	87%		68-124%
2037-26-5	Toluene-D8	98%		77-125%
460-00-4	4-Bromofluorobenzene	100%		72-130%

CAS No.	Tentatively Identified Compounds	R.T.	Est. Conc.	Units	Q
	C3 alkyl benzene	15.92	38000	ug/kg	J
95-63-6	Benzene, 1,2,4-trimethyl-	16.45	61000	ug/kg	JN
496-11-7	Indane	17.23	250000	ug/kg	JN
95-13-6	Indene	17.49	140000	ug/kg	JN
	1H-Indene-dihydro-methyl- isomer	18.48	45000	ug/kg	J
622-76-4	Benzene, 1-butynyl-	18.77	40000	ug/kg	JN
2177-47-1	2-Methylindene	18.91	62000	ug/kg	JN
91-20-3	Naphthalene	19.52	3000000	ug/kg	JN
95-15-8	Benzo[b]thiophene	19.68	49000	ug/kg	JN
	Naphthalene, methyl- isomer	20.87	360000	ug/kg	J

ND = Not detected      MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 3 of 3

3.1

3

<b>Client Sample ID:</b>	IDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Method:</b>	SW846 8260C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**VOA TCL List**

CAS No.	Tentatively Identified Compounds	R.T.	Est. Conc.	Units	Q
	Naphthalene, methyl- isomer	21.15	120000	ug/kg	J
	Total TIC, Volatile		4165000	ug/kg	J
	Total Alkanes		0	ug/kg	

(a) Diluted due to high concentration of non-target compound.

ND = Not detected      MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 4

31

3

<b>Client Sample ID:</b>	JDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Method:</b>	SW846 8270D SW846 3550C		
<b>Project:</b>	CHMHLMB: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	5P20827.D	1	08/28/15	AD	08/26/15	OP86719	E5P1070
Run #2	5P20853.D	5	08/28/15	AP	08/26/15	OP86719	E5P1071
Run #3	5P20854.D	50	08/28/15	AP	08/26/15	OP86719	E5P1071
Run #4	5P20900.D	200	09/01/15	SD	08/26/15	OP86719	E5P1073

	<b>Initial Weight</b>	<b>Final Volume</b>
Run #1	30.4 g	1.0 ml
Run #2	30.4 g	1.0 ml
Run #3	30.4 g	1.0 ml
Run #4	30.4 g	1.0 ml

**ABN TCL List (SOM0 2.0)**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
95-57-8	2-Chlorophenol	ND	85	39	ug/kg	
59-50-7	4-Chloro-3-methyl phenol	ND	210	79	ug/kg	
120-83-2	2,4-Dichlorophenol	ND	210	79	ug/kg	
105-67-9	2,4-Dimethylphenol	2450	210	93	ug/kg	
51-28-5	2,4-Dinitrophenol	ND	210	180	ug/kg	
534-52-1	4,6-Dinitro-o-cresol	ND	210	35	ug/kg	
95-48-7	2-Methylphenol	ND	85	56	ug/kg	
	3&4-Methylphenol	452	85	47	ug/kg	
88-75-5	2-Nitrophenol	ND	210	39	ug/kg	
100-02-7	4-Nitrophenol	ND	420	130	ug/kg	
87-86-5	Pentachlorophenol	ND	210	100	ug/kg	
108-95-2	Phenol	293	85	28	ug/kg	
58-90-2	2,3,4,6-Tetrachlorophenol	ND	210	99	ug/kg	
95-95-4	2,4,5-Trichlorophenol	ND	210	94	ug/kg	
88-06-2	2,4,6-Trichlorophenol	ND	210	66	ug/kg	
83-32-9	Acenaphthene	67400 <sup>a</sup>	2100	430	ug/kg	
208-96-8	Acenaphthylene	9770 <sup>b</sup>	210	32	ug/kg	
98-86-2	Acetophenone	ND	210	13	ug/kg	
120-12-7	Anthracene	43900 <sup>a</sup>	2100	480	ug/kg	
1912-24-9	Atrazine	ND	85	25	ug/kg	
56-55-3	Benzo(a)anthracene	18100 <sup>b</sup>	210	41	ug/kg	
50-32-8	Benzo(a)pyrene	13600 <sup>b</sup>	210	51	ug/kg	
205-99-2	Benzo(b)fluoranthene	14500 <sup>b</sup>	210	42	ug/kg	
191-24-2	Benzo(g,h,i)perylene	7580 <sup>b</sup>	210	70	ug/kg	
207-08-9	Benzo(k)fluoranthene	5730 <sup>b</sup>	210	68	ug/kg	
101-55-3	4-Bromophenyl phenyl ether	ND	85	17	ug/kg	
85-68-7	Butyl benzyl phthalate	ND	85	17	ug/kg	
92-52-4	1,1'-Biphenyl	25100 <sup>a</sup>	4200	420	ug/kg	

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 2 of 4

31  
3

<b>Client Sample ID:</b>	IDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Method:</b>	SW846 8270D SW846 3550C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**ABN TCL List (SOM0 2.0)**

CAS No.	Compound	Result	RL	MDL	Units	Q
100-52-7	Benzaldehyde	ND	210	10	ug/kg	
91-58-7	2-Chloronaphthalene	ND	85	9.6	ug/kg	
106-47-8	4-Chloroaniline	ND	210	14	ug/kg	
86-74-8	Carbazole	12900 <sup>b</sup>	420	47	ug/kg	
105-60-2	Caprolactam	ND	85	27	ug/kg	
218-01-9	Chrysene	18300 <sup>b</sup>	210	52	ug/kg	
111-91-1	bis(2-Chloroethoxy)methane	ND	85	28	ug/kg	
111-44-4	bis(2-Chloroethyl)ether	ND	85	9.8	ug/kg	
108-60-1	bis(2-Chloroisopropyl)ether	ND	85	15	ug/kg	
7005-72-3	4-Chlorophenyl phenyl ether	ND	85	9.0	ug/kg	
121-14-2	2,4-Dinitrotoluene	ND	42	14	ug/kg	
606-20-2	2,6-Dinitrotoluene	ND	42	9.0	ug/kg	
91-94-1	3,3'-Dichlorobenzidine	ND	85	23	ug/kg	
123-91-1	1,4-Dioxane	ND	42	28	ug/kg	
53-70-3	Dibenzo(a,h)anthracene	1640	42	10	ug/kg	
132-64-9	Dibenzofuran	53100 <sup>a</sup>	4200	340	ug/kg	
84-74-2	Di-n-butyl phthalate	ND	85	11	ug/kg	
117-84-0	Di-n-octyl phthalate	ND	85	11	ug/kg	
84-66-2	Diethyl phthalate	ND	85	10	ug/kg	
131-11-3	Dimethyl phthalate	ND	85	8.5	ug/kg	
117-81-7	bis(2-Ethylhexyl)phthalate	579	85	14	ug/kg	
206-44-0	Fluoranthene	81200 <sup>a</sup>	2100	740	ug/kg	
86-73-7	Fluorene	72000 <sup>a</sup>	2100	1600	ug/kg	
118-74-1	Hexachlorobenzene	ND	85	11	ug/kg	
87-68-3	Hexachlorobutadiene	ND	42	14	ug/kg	
77-47-4	Hexachlorocyclopentadiene	ND	420	16	ug/kg	
67-72-1	Hexachloroethane	ND	210	21	ug/kg	
193-39-5	Indeno(1,2,3-cd)pyrene	7740 <sup>b</sup>	210	68	ug/kg	
78-59-1	Isophorone	ND	85	7.3	ug/kg	
91-57-6	2-Methylnaphthalene	184000 <sup>a</sup>	4200	490	ug/kg	
88-74-4	2-Nitroaniline	ND	210	20	ug/kg	
99-09-2	3-Nitroaniline	ND	210	14	ug/kg	
100-01-6	4-Nitroaniline	ND	210	12	ug/kg	
91-20-3	Naphthalene	661000 <sup>c</sup>	8500	1300	ug/kg	
98-95-3	Nitrobenzene	ND	85	17	ug/kg	
621-64-7	N-Nitroso-di-n-propylamine	ND	85	12	ug/kg	
86-30-6	N-Nitrosodiphenylamine	ND	210	10	ug/kg	
85-01-8	Phenanthrene	171000 <sup>a</sup>	2100	450	ug/kg	
129-00-0	Pyrene	55000 <sup>a</sup>	2100	480	ug/kg	
95-94-3	1,2,4,5-Tetrachlorobenzene	ND	210	7.1	ug/kg	

ND = Not detected      MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 3 of 4

3-1  
3

<b>Client Sample ID:</b>	IDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Method:</b>	SW846 8270D SW846 3550C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**ABN TCL List (SOM0 2.0)**

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Run# 3	Limits
367-12-4	2-Fluorophenol	81%	96%	100%	22-121%
4165-62-2	Phenol-d5	84%	99%	101%	27-119%
118-79-6	2,4,6-Tribromophenol	154%	146%	136%	17-158%
4165-60-0	Nitrobenzene-d5	196% <sup>d</sup>	109%	108%	33-127%
321-60-8	2-Fluorobiphenyl	80%	102%	112%	41-121%
1718-51-0	Terphenyl-d14	94%	111%	128%	44-137%

CAS No.	Tentatively Identified Compounds	R.T.	Est. Conc.	Units	Q
	C3 alkyl benzene	5.05	1700	ug/kg	J
	C3 alkyl benzene	5.38	5100	ug/kg	J
271-89-6	Benzofuran	5.41	1500	ug/kg	JN
	C3 alkyl benzene	5.63	1700	ug/kg	J
496-11-7	Indane	5.77	7400	ug/kg	JN
95-13-6	Indene	5.86	8100	ug/kg	JN
	C4 alkyl benzene	5.92	1600	ug/kg	J
90-12-0	Naphthalene, 1-methyl-	8.07	750	ug/kg	JN
	Naphthalene ethyl	8.59	2400	ug/kg	J
	Naphthalene dimethyl	8.69	3800	ug/kg	J
	Naphthalene dimethyl	8.78	4200	ug/kg	J
	Naphthalene dimethyl	8.81	2100	ug/kg	J
	Naphthalene dimethyl	8.91	2900	ug/kg	J
	Naphthalene trimethyl	9.31	1200	ug/kg	J
	unknown	9.37	1100	ug/kg	J
	Naphthalene trimethyl	9.57	1100	ug/kg	J
	Naphthalene trimethyl	9.60	890	ug/kg	J
	Naphthalene trimethyl	9.68	1400	ug/kg	J
	unknown	9.94	1700	ug/kg	J
	unknown	9.96	1300	ug/kg	J
	unknown	10.05	1600	ug/kg	J
	Pyrene methyl	13.57	1300	ug/kg	J
	Pyrene methyl	13.67	670	ug/kg	J
	unknown PAH substance	16.61	1200	ug/kg	J
	unknown PAH substance	16.86	3100	ug/kg	J
	Total TIC, Semi-Volatile		59810	ug/kg	J
	Total Alkanes		0	ug/kg	

(a) Result is from Run# 3

(b) Result is from Run# 2

(c) Result is from Run# 4

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 4 of 4

3.1

3

<b>Client Sample ID:</b>	IDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Method:</b>	SW846 8270D SW846 3550C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**ABN TCL List (SOM0 2.0)**

CAS No.	Compound	Result	RL	MDL	Units	Q
---------	----------	--------	----	-----	-------	---

(d) Outside control limits due to matrix interference.

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

3.1

3

<b>Client Sample ID:</b>	IDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Method:</b>	SW846 8081B SW846 3546		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	4G59942.D	1	09/03/15	YD	08/24/15	OP86662	G4G1565
Run #2							

	<b>Initial Weight</b>	<b>Final Volume</b>
Run #1	16.8 g	10.0 ml
Run #2		

**Pesticide TCL List**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
309-00-2	Aldrin	ND	0.77	0.69	ug/kg	
319-84-6	alpha-BHC	ND	0.77	0.51	ug/kg	
319-85-7	beta-BHC	ND	0.77	0.47	ug/kg	
319-86-8	delta-BHC	7.9	0.77	0.30	ug/kg	
58-89-9	gamma-BHC (Lindane)	ND	0.77	0.35	ug/kg	
5103-71-9	alpha-Chlordane	ND	0.77	0.41	ug/kg	
5103-74-2	gamma-Chlordane	ND	0.77	0.59	ug/kg	
57-74-9	Chlordane (alpha and gamma)	ND	0.77	0.41	ug/kg	
60-57-1	Dieldrin	ND	0.77	0.60	ug/kg	
72-54-8	4,4'-DDD	ND	0.77	0.28	ug/kg	
72-55-9	4,4'-DDE	ND	0.77	0.26	ug/kg	
50-29-3	4,4'-DDT <sup>a</sup>	62.5	0.77	0.29	ug/kg	
72-20-8	Endrin	ND	0.77	0.27	ug/kg	
1031-07-8	Endosulfan sulfate <sup>a</sup>	38.4	0.77	0.44	ug/kg	
7421-93-4	Endrin aldehyde	ND	0.77	0.57	ug/kg	
959-98-8	Endosulfan-I	ND	0.77	0.25	ug/kg	
33213-65-9	Endosulfan-II	ND	0.77	0.73	ug/kg	
76-44-8	Heptachlor	ND	0.77	0.63	ug/kg	
1024-57-3	Heptachlor epoxide	ND	0.77	0.32	ug/kg	
72-43-5	Methoxychlor	ND	1.5	0.43	ug/kg	
53494-70-5	Endrin ketone	23.4	0.77	0.40	ug/kg	
8001-35-2	Toxaphene	ND	19	13	ug/kg	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
877-09-8	Tetrachloro-m-xylene	79%		24-136%
877-09-8	Tetrachloro-m-xylene	67%		24-136%
2051-24-3	Decachlorobiphenyl	674% <sup>b</sup>		10-153%
2051-24-3	Decachlorobiphenyl	739% <sup>b</sup>		10-153%

(a) More than 40 % RPD for detected concentrations between the two GC columns.

(b) Outside control limits due to matrix interference.

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

3

<b>Client Sample ID:</b>	IDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Method:</b>	SW846 8082A SW846 3546		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	2G119163.D	1	08/28/15	DG	08/24/15	OP86661	G2G3447
Run #2							

	<b>Initial Weight</b>	<b>Final Volume</b>
Run #1	16.8 g	10.0 ml
Run #2		

**PCB List**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
12674-11-2	Aroclor 1016	ND	38	12	ug/kg	
11104-28-2	Aroclor 1221	ND	38	23	ug/kg	
11141-16-5	Aroclor 1232	ND	38	13	ug/kg	
53469-21-9	Aroclor 1242	ND	38	17	ug/kg	
12672-29-6	Aroclor 1248	ND	38	12	ug/kg	
11097-69-1	Aroclor 1254	ND	38	17	ug/kg	
11096-82-5	Aroclor 1260	ND	38	16	ug/kg	
11100-14-4	Aroclor 1268	ND	38	12	ug/kg	
37324-23-5	Aroclor 1262	ND	38	11	ug/kg	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
877-09-8	Tetrachloro-m-xylene	103%		20-152%
877-09-8	Tetrachloro-m-xylene	135%		20-152%
2051-24-3	Decachlorobiphenyl	36%		12-157%
2051-24-3	Decachlorobiphenyl	387% <sup>a</sup>		12-157%

(a) Outside control limits due to matrix interference.

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

32  
3

<b>Client Sample ID:</b>	IDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Method:</b>	SW846 8260C SW846 1311		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	2V25435.D	5	08/24/15	HA	08/23/15	GP91434	V2V1021
Run #2							

	<b>Purge Volume</b>
Run #1	5.0 ml
Run #2	

**VOA TCLP Leachate****TCLP Leachate method SW846 1311**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>HW#</b>	<b>MCL</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
71-43-2	Benzene	0.139	D018	0.50	0.0025	0.0012	mg/l	
78-93-3	2-Butanone (MEK)	ND	D035	200	0.10	0.028	mg/l	
56-23-5	Carbon tetrachloride	ND	D019	0.50	0.0050	0.0011	mg/l	
108-90-7	Chlorobenzene	ND	D021	100	0.0050	0.00093	mg/l	
67-66-3	Chloroform	ND	D022	6.0	0.0050	0.00094	mg/l	
106-46-7	1,4-Dichlorobenzene	ND	D027	7.5	0.0050	0.0014	mg/l	
107-06-2	1,2-Dichloroethane	ND	D028	0.50	0.0050	0.00090	mg/l	
75-35-4	1,1-Dichloroethene	ND	D029	0.70	0.0050	0.0026	mg/l	
127-18-4	Tetrachloroethene	ND	D039	0.70	0.0050	0.0020	mg/l	
79-01-6	Trichloroethene	ND	D040	0.50	0.0050	0.0011	mg/l	
75-01-4	Vinyl chloride	ND	D043	0.20	0.0050	0.00074	mg/l	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
1868-53-7	Dibromofluoromethane	94%		76-120%
17060-07-0	1,2-Dichloroethane-D4	92%		64-135%
2037-26-5	Toluene-D8	97%		76-117%
460-00-4	4-Bromofluorobenzene	93%		72-122%

ND = Not detected      MDL = Method Detection Limit  
 MCL = Maximum Contamination Level (40 CFR 261 6/96)  
 E = Indicates value exceeds calibration range

J = Indicates an estimated value  
 B = Indicates analyte found in associated method blank  
 N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

32  
3

<b>Client Sample ID:</b>	IDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Method:</b>	SW846 8270D SW846 3510C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	5P20743.D	1	08/26/15	SD	08/25/15	OP86663	E5P1067
Run #2							

	<b>Initial Volume</b>	<b>Final Volume</b>
Run #1	100 ml	1.0 ml
Run #2		

**ABN TCLP Leachate****TCLP Leachate method SW846 1311**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>HW#</b>	<b>MCL</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
95-48-7	2-Methylphenol	ND	D023	200	0.020	0.0082	mg/l	
	3&4-Methylphenol	0.0168	D024	200	0.020	0.0067	mg/l	J
87-86-5	Pentachlorophenol	ND	D037	100	0.10	0.014	mg/l	
95-95-4	2,4,5-Trichlorophenol	ND	D041	400	0.050	0.015	mg/l	
88-06-2	2,4,6-Trichlorophenol	ND	D042	2.0	0.050	0.014	mg/l	
106-46-7	1,4-Dichlorobenzene	ND	D027	7.5	0.020	0.0023	mg/l	
121-14-2	2,4-Dinitrotoluene	ND	D030	0.13	0.020	0.0026	mg/l	
118-74-1	Hexachlorobenzene	ND	D032	0.13	0.020	0.0042	mg/l	
87-68-3	Hexachlorobutadiene	ND	D033	0.50	0.010	0.0036	mg/l	
67-72-1	Hexachloroethane	ND	D034	3.0	0.050	0.0022	mg/l	
98-95-3	Nitrobenzene	ND	D036	2.0	0.020	0.0046	mg/l	
110-86-1	Pyridine	0.0047	D038	5.0	0.020	0.0027	mg/l	J

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
367-12-4	2-Fluorophenol	56%		12-110%
4165-62-2	Phenol-d5	37%		10-110%
118-79-6	2,4,6-Tribromophenol	92%		42-154%
4165-60-0	Nitrobenzene-d5	89%		29-139%
321-60-8	2-Fluorobiphenyl	84%		33-129%
1718-51-0	Terphenyl-d14	99%		10-140%

ND = Not detected      MDL = Method Detection Limit  
 MCL = Maximum Contamination Level (40 CFR 261 6/96)  
 E = Indicates value exceeds calibration range

J = Indicates an estimated value  
 B = Indicates analyte found in associated method blank  
 N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

32  
3

<b>Client Sample ID:</b>	IDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Method:</b>	SW846 8081B SW846 3510C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	6G26587.D	1	09/02/15	YD	08/25/15	OP86672	G6G780
Run #2							

	<b>Initial Volume</b>	<b>Final Volume</b>
Run #1	100 ml	10.0 ml
Run #2		

**Pesticide TCLP Leachate****TCLP Leachate method SW846 1311**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>HW#</b>	<b>MCL</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
58-89-9	gamma-BHC (Lindane)	ND	D013	0.40	0.00010	0.000052	mg/l	
12789-03-6	Chlordane	ND	D020	0.030	0.0050	0.00092	mg/l	
72-20-8	Endrin	ND	D012	0.020	0.00010	0.000045	mg/l	
76-44-8	Heptachlor	ND	D031	0.0080	0.00010	0.000049	mg/l	
1024-57-3	Heptachlor epoxide	ND	D031	0.0080	0.00010	0.000082	mg/l	
72-43-5	Methoxychlor	ND	D014	10	0.00020	0.000072	mg/l	
8001-35-2	Toxaphene	ND	D015	0.50	0.0025	0.0015	mg/l	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
877-09-8	Tetrachloro-m-xylene	77%		30-137%
877-09-8	Tetrachloro-m-xylene	66%		30-137%
2051-24-3	Decachlorobiphenyl	91%		10-137%
2051-24-3	Decachlorobiphenyl	112%		10-137%

ND = Not detected      MDL = Method Detection Limit  
 MCL = Maximum Contamination Level (40 CFR 261 6/96)  
 E = Indicates value exceeds calibration range

J = Indicates an estimated value  
 B = Indicates analyte found in associated method blank  
 N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

32  
3

<b>Client Sample ID:</b>	IDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**Metals Analysis, TCLP Leachate SW846 1311**

Analyte	Result	HW#	MCL	RL	Units	DF	Prep	Analyzed By	Method	Prep Method
Arsenic	< 0.50	D004	5.0	0.50	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Barium	< 1.0	D005	100	1.0	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Cadmium	< 0.025	D006	1.0	0.025	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Chromium	< 0.050	D007	5.0	0.050	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Lead	< 0.50	D008	5.0	0.50	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Mercury	< 0.00020	D009	0.20	0.00020	mg/l	1	08/24/15	08/24/15	MA	SW846 7470A <sup>1</sup>
Selenium	< 0.50	D010	1.0	0.50	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Silver	< 0.050	D011	5.0	0.050	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>

(1) Instrument QC Batch: MA37397

(2) Instrument QC Batch: MA37414

(3) Prep QC Batch: MP88566

(4) Prep QC Batch: MP88584

RL = Reporting Limit

MCL = Maximum Contamination Level (40 CFR 261 6/96)

**Report of Analysis**

Page 1 of 1

32  
3

<b>Client Sample ID:</b>	IDW-SO-1-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-1A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	77.4
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**General Chemistry**

Analyte	Result	RL	Units	DF	Analyzed	By	Method
Corrosivity as pH	7.60 NC		su	1	08/22/15 14:23	SA	SW846 CHAP7
Cyanide Reactivity	< 12	12	mg/kg	1	08/24/15 15:04	BM	SW846 CHAP7/9012 B
Ignitability (Flashpoint)	> 200		Deg. F	1	08/22/15	SA	SW846 CHAP7/ASTM D93
Sulfide Reactivity	< 120	120	mg/kg	1	08/24/15	MP	SW846 CHAP7/9034

RL = Reporting Limit

**Report of Analysis**

Page 1 of 3

33  
3

<b>Client Sample ID:</b>	IDW-SO-2-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-2	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	68.7
<b>Method:</b>	SW846 8260C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1 <sup>a</sup>	E228676.D	1	08/28/15	TDN	n/a	n/a	VE10012
Run #2							

	<b>Initial Weight</b>	<b>Final Volume</b>	<b>Methanol Aliquot</b>
Run #1	7.9 g	10.0 ml	2.0 ul
Run #2			

**VOA TCL List**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
67-64-1	Acetone	ND	57000	13000	ug/kg	
71-43-2	Benzene	26500	2900	760	ug/kg	
74-97-5	Bromochloromethane	ND	29000	1800	ug/kg	
75-27-4	Bromodichloromethane	ND	11000	900	ug/kg	
75-25-2	Bromoform	ND	29000	1400	ug/kg	
74-83-9	Bromomethane	ND	29000	2100	ug/kg	
78-93-3	2-Butanone (MEK)	ND	57000	11000	ug/kg	
75-15-0	Carbon disulfide	ND	11000	1300	ug/kg	
56-23-5	Carbon tetrachloride	ND	11000	1300	ug/kg	
108-90-7	Chlorobenzene	ND	11000	890	ug/kg	
75-00-3	Chloroethane	ND	29000	2800	ug/kg	
67-66-3	Chloroform	ND	11000	860	ug/kg	
74-87-3	Chloromethane	ND	29000	1500	ug/kg	
110-82-7	Cyclohexane	ND	11000	1800	ug/kg	
96-12-8	1,2-Dibromo-3-chloropropane	ND	11000	3100	ug/kg	
124-48-1	Dibromochloromethane	ND	11000	1200	ug/kg	
106-93-4	1,2-Dibromoethane	ND	5700	750	ug/kg	
95-50-1	1,2-Dichlorobenzene	ND	5700	700	ug/kg	
541-73-1	1,3-Dichlorobenzene	ND	5700	900	ug/kg	
106-46-7	1,4-Dichlorobenzene	ND	5700	1300	ug/kg	
75-71-8	Dichlorodifluoromethane	ND	29000	2100	ug/kg	
75-34-3	1,1-Dichloroethane	ND	5700	810	ug/kg	
107-06-2	1,2-Dichloroethane	ND	5700	770	ug/kg	
75-35-4	1,1-Dichloroethene	ND	5700	3400	ug/kg	
156-59-2	cis-1,2-Dichloroethene	ND	5700	4500	ug/kg	
156-60-5	trans-1,2-Dichloroethene	ND	5700	3400	ug/kg	
78-87-5	1,2-Dichloropropane	ND	11000	1400	ug/kg	
10061-01-5	cis-1,3-Dichloropropene	ND	11000	680	ug/kg	
10061-02-6	trans-1,3-Dichloropropene	ND	11000	1000	ug/kg	
100-41-4	Ethylbenzene	116000	5700	940	ug/kg	
76-13-1	Freon 113	ND	29000	2600	ug/kg	
591-78-6	2-Hexanone	ND	29000	7700	ug/kg	

ND = Not detected      MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 2 of 3

33  
3

<b>Client Sample ID:</b>	IDW-SO-2-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-2	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	68.7
<b>Method:</b>	SW846 8260C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**VOA TCL List**

CAS No.	Compound	Result	RL	MDL	Units	Q
98-82-8	Isopropylbenzene	10300	11000	610	ug/kg	J
79-20-9	Methyl Acetate	ND	29000	4900	ug/kg	
108-87-2	Methylcyclohexane	5170	11000	1300	ug/kg	J
1634-04-4	Methyl Tert Butyl Ether	ND	5700	880	ug/kg	
108-10-1	4-Methyl-2-pentanone(MIBK)	ND	29000	2600	ug/kg	
75-09-2	Methylene chloride	ND	29000	5600	ug/kg	
100-42-5	Styrene	ND	11000	1000	ug/kg	
79-34-5	1,1,2,2-Tetrachloroethane	ND	11000	1000	ug/kg	
127-18-4	Tetrachloroethene	ND	11000	1700	ug/kg	
108-88-3	Toluene	24500	5700	1200	ug/kg	
87-61-6	1,2,3-Trichlorobenzene	ND	29000	1000	ug/kg	
120-82-1	1,2,4-Trichlorobenzene	ND	29000	970	ug/kg	
71-55-6	1,1,1-Trichloroethane	ND	11000	860	ug/kg	
79-00-5	1,1,2-Trichloroethane	ND	11000	840	ug/kg	
79-01-6	Trichloroethene	ND	5700	840	ug/kg	
75-69-4	Trichlorofluoromethane	ND	29000	1400	ug/kg	
75-01-4	Vinyl chloride	ND	11000	1100	ug/kg	
	m,p-Xylene	185000	5700	2000	ug/kg	
95-47-6	o-Xylene	86800	5700	1600	ug/kg	
1330-20-7	Xylene (total)	272000	5700	1600	ug/kg	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
1868-53-7	Dibromofluoromethane	94%		70-122%
17060-07-0	1,2-Dichloroethane-D4	87%		68-124%
2037-26-5	Toluene-D8	101%		77-125%
460-00-4	4-Bromofluorobenzene	96%		72-130%

CAS No.	Tentatively Identified Compounds	R.T.	Est. Conc.	Units	Q
	C3 alkyl benzene	15.93	110000	ug/kg	J
95-63-6	Benzene, 1,2,4-trimethyl-	16.45	130000	ug/kg	JN
496-11-7	Indane	17.23	320000	ug/kg	JN
95-13-6	Indene	17.49	200000	ug/kg	JN
	1H-Indene-dihydro-methyl- isomer	17.83	42000	ug/kg	J
	1H-Indene-dihydro-methyl- isomer	18.48	63000	ug/kg	J
	1H-Indene-dihydro-methyl- isomer	18.69	66000	ug/kg	J
	1H-Indene, methyl-isomer	18.77	65000	ug/kg	J
	Methylindene-isomer	18.90	84000	ug/kg	J
91-20-3	Naphthalene	19.52	4800000	ug/kg	JN

ND = Not detected      MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 3 of 3

33  
3

<b>Client Sample ID:</b>	IDW-SO-2-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-2	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	68.7
<b>Method:</b>	SW846 8260C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**VOA TCL List**

CAS No.	Tentatively Identified Compounds	R.T.	Est. Conc.	Units	Q
270-82-6	2-Benzothiophene	19.68	74000	ug/kg	JN
	Naphthalene, methyl- isomer	20.87	560000	ug/kg	J
	Naphthalene, methyl- isomer	21.15	270000	ug/kg	J
	Naphthalene, ethyl-	21.84	38000	ug/kg	J
	Naphthalene, dimethyl- isomer	22.35	46000	ug/kg	J
	Total TIC, Volatile		6868000	ug/kg	J
	Total Alkanes		0	ug/kg	

(a) Diluted due to high concentration of non-target compound.

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 3

33

<b>Client Sample ID:</b>	IDW-SO-2-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-2	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	68.7
<b>Method:</b>	SW846 8270D SW846 3550C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	5P20828.D	1	08/28/15	AD	08/26/15	OP86719	E5P1070
Run #2	5P20855.D	10	08/28/15	AP	08/26/15	OP86719	E5P1071

	<b>Initial Weight</b>	<b>Final Volume</b>
Run #1	31.2 g	1.0 ml
Run #2	31.2 g	1.0 ml

**ABN TCL List (SOM0 2.0)**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
95-57-8	2-Chlorophenol	ND	93	42	ug/kg	
59-50-7	4-Chloro-3-methyl phenol	ND	230	87	ug/kg	
120-83-2	2,4-Dichlorophenol	ND	230	86	ug/kg	
105-67-9	2,4-Dimethylphenol	ND	230	100	ug/kg	
51-28-5	2,4-Dinitrophenol	ND	230	200	ug/kg	
534-52-1	4,6-Dinitro-o-cresol	ND	230	38	ug/kg	
95-48-7	2-Methylphenol	ND	93	61	ug/kg	
	3&4-Methylphenol	ND	93	52	ug/kg	
88-75-5	2-Nitrophenol	ND	230	42	ug/kg	
100-02-7	4-Nitrophenol	ND	470	140	ug/kg	
87-86-5	Pentachlorophenol	ND	230	110	ug/kg	
108-95-2	Phenol	ND	93	30	ug/kg	
58-90-2	2,3,4,6-Tetrachlorophenol	ND	230	110	ug/kg	
95-95-4	2,4,5-Trichlorophenol	ND	230	100	ug/kg	
88-06-2	2,4,6-Trichlorophenol	ND	230	73	ug/kg	
83-32-9	Acenaphthene	13600 a	470	94	ug/kg	
208-96-8	Acenaphthylene	776	47	7.0	ug/kg	
98-86-2	Acetophenone	366	230	15	ug/kg	
120-12-7	Anthracene	11300 a	470	100	ug/kg	
1912-24-9	Atrazine	ND	93	28	ug/kg	
56-55-3	Benzo(a)anthracene	14800 a	470	90	ug/kg	
50-32-8	Benzo(a)pyrene	13200 a	470	110	ug/kg	
205-99-2	Benzo(b)fluoranthene	13900 a	470	92	ug/kg	
191-24-2	Benzo(g,h,i)perylene	7400 a	470	150	ug/kg	
207-08-9	Benzo(k)fluoranthene	5890 a	470	150	ug/kg	
101-55-3	4-Bromophenyl phenyl ether	ND	93	19	ug/kg	
85-68-7	Butyl benzyl phthalate	ND	93	18	ug/kg	
92-52-4	1,1'-Biphenyl	1200	93	9.2	ug/kg	
100-52-7	Benzaldehyde	ND	230	11	ug/kg	
91-58-7	2-Chloronaphthalene	ND	93	11	ug/kg	
106-47-8	4-Chloroaniline	ND	230	15	ug/kg	
86-74-8	Carbazole	1740	93	10	ug/kg	

ND = Not detected      MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 2 of 3

33  
3

<b>Client Sample ID:</b>	IDW-SO-2-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-2	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	68.7
<b>Method:</b>	SW846 8270D SW846 3550C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**ABN TCL List (SOM0 2.0)**

CAS No.	Compound	Result	RL	MDL	Units	Q
105-60-2	Caprolactam	ND	93	29	ug/kg	
218-01-9	Chrysene	15000 <sup>a</sup>	470	110	ug/kg	
111-91-1	bis(2-Chloroethoxy)methane	ND	93	31	ug/kg	
111-44-4	bis(2-Chloroethyl)ether	ND	93	11	ug/kg	
108-60-1	bis(2-Chloroisopropyl)ether	ND	93	16	ug/kg	
7005-72-3	4-Chlorophenyl phenyl ether	ND	93	9.8	ug/kg	
121-14-2	2,4-Dinitrotoluene	ND	47	15	ug/kg	
606-20-2	2,6-Dinitrotoluene	ND	47	9.9	ug/kg	
91-94-1	3,3'-Dichlorobenzidine	ND	93	25	ug/kg	
123-91-1	1,4-Dioxane	ND	47	31	ug/kg	
53-70-3	Dibenz(a,h)anthracene	1720	47	11	ug/kg	
132-64-9	Dibenzofuran	7090 <sup>a</sup>	930	76	ug/kg	
84-74-2	Di-n-butyl phthalate	ND	93	12	ug/kg	
117-84-0	Di-n-octyl phthalate	ND	93	12	ug/kg	
84-66-2	Diethyl phthalate	ND	93	11	ug/kg	
131-11-3	Dimethyl phthalate	ND	93	9.4	ug/kg	
117-81-7	bis(2-Ethylhexyl)phthalate	ND	93	15	ug/kg	
206-44-0	Fluoranthene	37500 <sup>a</sup>	470	160	ug/kg	
86-73-7	Fluorene	12400 <sup>a</sup>	470	350	ug/kg	
118-74-1	Hexachlorobenzene	ND	93	12	ug/kg	
87-68-3	Hexachlorobutadiene	ND	47	16	ug/kg	
77-47-4	Hexachlorocyclopentadiene	ND	470	18	ug/kg	
67-72-1	Hexachloroethane	ND	230	23	ug/kg	
193-39-5	Indeno(1,2,3-cd)pyrene	8090 <sup>a</sup>	470	150	ug/kg	
78-59-1	Isophorone	ND	93	8.0	ug/kg	
91-57-6	2-Methylnaphthalene	2530	93	11	ug/kg	
88-74-4	2-Nitroaniline	ND	230	22	ug/kg	
99-09-2	3-Nitroaniline	ND	230	15	ug/kg	
100-01-6	4-Nitroaniline	ND	230	13	ug/kg	
91-20-3	Naphthalene	7840 <sup>a</sup>	470	69	ug/kg	
98-95-3	Nitrobenzene	ND	93	19	ug/kg	
621-64-7	N-Nitroso-di-n-propylamine	ND	93	13	ug/kg	
86-30-6	N-Nitrosodiphenylamine	ND	230	11	ug/kg	
85-01-8	Phenanthrene	40100 <sup>a</sup>	470	99	ug/kg	
129-00-0	Pyrene	28000 <sup>a</sup>	470	110	ug/kg	
95-94-3	1,2,4,5-Tetrachlorobenzene	ND	230	7.8	ug/kg	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
367-12-4	2-Fluorophenol	68%	82%	22-121%

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 3 of 3

33  
3

<b>Client Sample ID:</b>	IDW-SO-2-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-2	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	68.7
<b>Method:</b>	SW846 8270D SW846 3550C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**ABN TCL List (SOM0 2.0)**

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
4165-62-2	Phenol-d5	65%	78%	27-119%
118-79-6	2,4,6-Tribromophenol	93%	96%	17-158%
4165-60-0	Nitrobenzene-d5	64%	79%	33-127%
321-60-8	2-Fluorobiphenyl	65%	84%	41-121%
1718-51-0	Terphenyl-d14	64%	85%	44-137%
CAS No.	Tentatively Identified Compounds	R.T.	Est. Conc.	Units Q
	unknown	4.85	1400	ug/kg J
	unknown	7.12	1100	ug/kg J
83-33-0	1H-Inden-1-one, 2,3-dihydro-	7.75	3100	ug/kg JN
90-12-0	Naphthalene, 1-methyl-	8.01	2400	ug/kg JN
	Naphthalene dimethyl	8.66	3500	ug/kg J
	Naphthalene dimethyl	8.75	3800	ug/kg J
	Naphthalene dimethyl	8.78	2000	ug/kg J
	Naphthalene dimethyl	8.89	2700	ug/kg J
	Naphthalene, trimethyl	9.29	1300	ug/kg J
	unknown	9.35	930	ug/kg J
	Naphthalene trimethyl	9.47	790	ug/kg J
	Naphthalene trimethyl	9.56	910	ug/kg J
	Naphthalene trimethyl	9.67	1300	ug/kg J
4780-79-4	1-Naphthalenemethanol	9.76	1500	ug/kg JN
	unknown	9.91	1700	ug/kg J
	unknown	9.94	1000	ug/kg J
	unknown	10.03	1500	ug/kg J
	unknown	15.97	850	ug/kg J
	Dibenzopyrene	16.15	920	ug/kg J
	unknown PAH substance	16.60	2400	ug/kg J
	unknown PAH substance	16.86	5100	ug/kg J
	unknown PAH substance	18.61	1400	ug/kg J
	unknown PAH substance	19.04	1500	ug/kg J
	unknown PAH substance	19.11	940	ug/kg J
	unknown PAH substance	19.64	1600	ug/kg J
	Total TIC, Semi-Volatile		45640	ug/kg J
	Total Alkanes		0	ug/kg

(a) Result is from Run# 2

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

33  
3

<b>Client Sample ID:</b>	IDW-SO-2-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-2	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	68.7
<b>Method:</b>	SW846 8081B SW846 3546		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	1G114753.D	1	09/02/15	YD	08/24/15	OP86662	G1G3770
Run #2							

	<b>Initial Weight</b>	<b>Final Volume</b>
Run #1	15.6 g	10.0 ml
Run #2		

**Pesticide TCL List**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
309-00-2	Aldrin	ND	0.93	0.83	ug/kg	
319-84-6	alpha-BHC	ND	0.93	0.62	ug/kg	
319-85-7	beta-BHC	ND	0.93	0.58	ug/kg	
319-86-8	delta-BHC	ND	0.93	0.37	ug/kg	
58-89-9	gamma-BHC (Lindane)	ND	0.93	0.42	ug/kg	
5103-71-9	alpha-Chlordane	ND	0.93	0.50	ug/kg	
5103-74-2	gamma-Chlordane	ND	0.93	0.71	ug/kg	
57-74-9	Chlordane (alpha and gamma)	ND	0.93	0.50	ug/kg	
60-57-1	Dieldrin	ND	0.93	0.73	ug/kg	
72-54-8	4,4'-DDD	ND	0.93	0.35	ug/kg	
72-55-9	4,4'-DDE	ND	0.93	0.31	ug/kg	
50-29-3	4,4'-DDT	ND	0.93	0.36	ug/kg	
72-20-8	Endrin	ND	0.93	0.33	ug/kg	
1031-07-8	Endosulfan sulfate	ND	0.93	0.53	ug/kg	
7421-93-4	Endrin aldehyde	ND	0.93	0.69	ug/kg	
959-98-8	Endosulfan-I	ND	0.93	0.31	ug/kg	
33213-65-9	Endosulfan-II	ND	0.93	0.88	ug/kg	
76-44-8	Heptachlor	ND	0.93	0.77	ug/kg	
1024-57-3	Heptachlor epoxide	ND	0.93	0.39	ug/kg	
72-43-5	Methoxychlor	ND	1.9	0.52	ug/kg	
53494-70-5	Endrin ketone	ND	0.93	0.49	ug/kg	
8001-35-2	Toxaphene	ND	23	16	ug/kg	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
877-09-8	Tetrachloro-m-xylene	69%		24-136%
877-09-8	Tetrachloro-m-xylene	25%		24-136%
2051-24-3	Decachlorobiphenyl	19%		10-153%
2051-24-3	Decachlorobiphenyl	83%		10-153%

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

33

<b>Client Sample ID:</b>	IDW-SO-2-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-2	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	68.7
<b>Method:</b>	SW846 8082A SW846 3546		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	2G119164.D	1	08/28/15	DG	08/24/15	OP86661	G2G3447
Run #2							

	<b>Initial Weight</b>	<b>Final Volume</b>
Run #1	15.6 g	10.0 ml
Run #2		

**PCB List**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
12674-11-2	Aroclor 1016	ND	47	15	ug/kg	
11104-28-2	Aroclor 1221	ND	47	27	ug/kg	
11141-16-5	Aroclor 1232	ND	47	15	ug/kg	
53469-21-9	Aroclor 1242	ND	47	21	ug/kg	
12672-29-6	Aroclor 1248	ND	47	14	ug/kg	
11097-69-1	Aroclor 1254	ND	47	21	ug/kg	
11096-82-5	Aroclor 1260	ND	47	20	ug/kg	
11100-14-4	Aroclor 1268	ND	47	14	ug/kg	
37324-23-5	Aroclor 1262	ND	47	13	ug/kg	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
877-09-8	Tetrachloro-m-xylene	68%		20-152%
877-09-8	Tetrachloro-m-xylene	31%		20-152%
2051-24-3	Decachlorobiphenyl	22%		12-157%
2051-24-3	Decachlorobiphenyl	34%		12-157%

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

34  
3

<b>Client Sample ID:</b>	IDW-SO-2-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-2A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	68.7
<b>Method:</b>	SW846 8260C SW846 1311		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	2V25436.D	5	08/24/15	HA	08/23/15	GP91434	V2V1021
Run #2							

	<b>Purge Volume</b>
Run #1	5.0 ml
Run #2	

**VOA TCLP Leachate****TCLP Leachate method SW846 1311**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>HW#</b>	<b>MCL</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
71-43-2	Benzene	0.0482	D018	0.50	0.0025	0.0012	mg/l	
78-93-3	2-Butanone (MEK)	ND	D035	200	0.10	0.028	mg/l	
56-23-5	Carbon tetrachloride	ND	D019	0.50	0.0050	0.0011	mg/l	
108-90-7	Chlorobenzene	ND	D021	100	0.0050	0.00093	mg/l	
67-66-3	Chloroform	ND	D022	6.0	0.0050	0.00094	mg/l	
106-46-7	1,4-Dichlorobenzene	ND	D027	7.5	0.0050	0.0014	mg/l	
107-06-2	1,2-Dichloroethane	ND	D028	0.50	0.0050	0.00090	mg/l	
75-35-4	1,1-Dichloroethene	ND	D029	0.70	0.0050	0.0026	mg/l	
127-18-4	Tetrachloroethene	ND	D039	0.70	0.0050	0.0020	mg/l	
79-01-6	Trichloroethene	ND	D040	0.50	0.0050	0.0011	mg/l	
75-01-4	Vinyl chloride	ND	D043	0.20	0.0050	0.00074	mg/l	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
1868-53-7	Dibromofluoromethane	98%		76-120%
17060-07-0	1,2-Dichloroethane-D4	96%		64-135%
2037-26-5	Toluene-D8	98%		76-117%
460-00-4	4-Bromofluorobenzene	93%		72-122%

ND = Not detected      MDL = Method Detection Limit  
 MCL = Maximum Contamination Level (40 CFR 261 6/96)  
 E = Indicates value exceeds calibration range

J = Indicates an estimated value  
 B = Indicates analyte found in associated method blank  
 N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

34  
3

<b>Client Sample ID:</b>	IDW-SO-2-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-2A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	68.7
<b>Method:</b>	SW846 8270D SW846 3510C		
<b>Project:</b>	CHMHLMB: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	5P20744.D	1	08/26/15	SD	08/25/15	OP86663	E5P1067
Run #2							

	<b>Initial Volume</b>	<b>Final Volume</b>
Run #1	100 ml	1.0 ml
Run #2		

**ABN TCLP Leachate****TCLP Leachate method SW846 1311**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>HW#</b>	<b>MCL</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
95-48-7	2-Methylphenol	ND	D023	200	0.020	0.0082	mg/l	
	3&4-Methylphenol	ND	D024	200	0.020	0.0067	mg/l	
87-86-5	Pentachlorophenol	ND	D037	100	0.10	0.014	mg/l	
95-95-4	2,4,5-Trichlorophenol	ND	D041	400	0.050	0.015	mg/l	
88-06-2	2,4,6-Trichlorophenol	ND	D042	2.0	0.050	0.014	mg/l	
106-46-7	1,4-Dichlorobenzene	ND	D027	7.5	0.020	0.0023	mg/l	
121-14-2	2,4-Dinitrotoluene	ND	D030	0.13	0.020	0.0026	mg/l	
118-74-1	Hexachlorobenzene	ND	D032	0.13	0.020	0.0042	mg/l	
87-68-3	Hexachlorobutadiene	ND	D033	0.50	0.010	0.0036	mg/l	
67-72-1	Hexachloroethane	ND	D034	3.0	0.050	0.0022	mg/l	
98-95-3	Nitrobenzene	ND	D036	2.0	0.020	0.0046	mg/l	
110-86-1	Pyridine	ND	D038	5.0	0.020	0.0027	mg/l	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
367-12-4	2-Fluorophenol	54%		12-110%
4165-62-2	Phenol-d5	34%		10-110%
118-79-6	2,4,6-Tribromophenol	94%		42-154%
4165-60-0	Nitrobenzene-d5	90%		29-139%
321-60-8	2-Fluorobiphenyl	75%		33-129%
1718-51-0	Terphenyl-d14	99%		10-140%

ND = Not detected      MDL = Method Detection Limit  
 MCL = Maximum Contamination Level (40 CFR 261 6/96)  
 E = Indicates value exceeds calibration range

J = Indicates an estimated value  
 B = Indicates analyte found in associated method blank  
 N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

34  
3

<b>Client Sample ID:</b>	IDW-SO-2-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-2A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	68.7
<b>Method:</b>	SW846 8081B SW846 3510C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	6G26588.D	1	09/02/15	YD	08/25/15	OP86672	G6G780
Run #2							

	<b>Initial Volume</b>	<b>Final Volume</b>
Run #1	100 ml	10.0 ml
Run #2		

**Pesticide TCLP Leachate****TCLP Leachate method SW846 1311**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>HW#</b>	<b>MCL</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
58-89-9	gamma-BHC (Lindane)	ND	D013	0.40	0.00010	0.000052	mg/l	
12789-03-6	Chlordane	ND	D020	0.030	0.0050	0.00092	mg/l	
72-20-8	Endrin	ND	D012	0.020	0.00010	0.000045	mg/l	
76-44-8	Heptachlor	ND	D031	0.0080	0.00010	0.000049	mg/l	
1024-57-3	Heptachlor epoxide	ND	D031	0.0080	0.00010	0.000082	mg/l	
72-43-5	Methoxychlor	ND	D014	10	0.00020	0.000072	mg/l	
8001-35-2	Toxaphene	ND	D015	0.50	0.0025	0.0015	mg/l	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
877-09-8	Tetrachloro-m-xylene	98%		30-137%
877-09-8	Tetrachloro-m-xylene	77%		30-137%
2051-24-3	Decachlorobiphenyl	55%		10-137%
2051-24-3	Decachlorobiphenyl	110%		10-137%

ND = Not detected      MDL = Method Detection Limit  
 MCL = Maximum Contamination Level (40 CFR 261 6/96)  
 E = Indicates value exceeds calibration range

J = Indicates an estimated value  
 B = Indicates analyte found in associated method blank  
 N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

34  
3

<b>Client Sample ID:</b>	IDW-SO-2-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-2A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	68.7
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**Metals Analysis, TCLP Leachate SW846 1311**

Analyte	Result	HW#	MCL	RL	Units	DF	Prep	Analyzed By	Method	Prep Method
Arsenic	< 0.50	D004	5.0	0.50	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Barium	< 1.0	D005	100	1.0	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Cadmium	< 0.025	D006	1.0	0.025	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Chromium	< 0.050	D007	5.0	0.050	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Lead	< 0.50	D008	5.0	0.50	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Mercury	< 0.00020	D009	0.20	0.00020	mg/l	1	08/24/15	08/24/15	MA	SW846 7470A <sup>1</sup>
Selenium	< 0.50	D010	1.0	0.50	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Silver	< 0.050	D011	5.0	0.050	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>

(1) Instrument QC Batch: MA37397

(2) Instrument QC Batch: MA37414

(3) Prep QC Batch: MP88566

(4) Prep QC Batch: MP88584

RL = Reporting Limit

MCL = Maximum Contamination Level (40 CFR 261 6/96)

**Report of Analysis**

Page 1 of 1

34  
3

<b>Client Sample ID:</b>	IDW-SO-2-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-2A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	68.7
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**General Chemistry**

Analyte	Result	RL	Units	DF	Analyzed	By	Method
Corrosivity as pH	7.62 NC		su	1	08/22/15 14:23	SA	SW846 CHAP7
Cyanide Reactivity	< 14	14	mg/kg	1	08/24/15 15:07	BM	SW846 CHAP7/9012 B
Ignitability (Flashpoint)	> 200		Deg. F	1	08/22/15	SA	SW846 CHAP7/ASTM D93
Sulfide Reactivity	< 140	140	mg/kg	1	08/24/15	MP	SW846 CHAP7/9034

RL = Reporting Limit

**Report of Analysis**

Page 1 of 2

35  
3

<b>Client Sample ID:</b>	IDW-SO-3-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-3	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	89.7
<b>Method:</b>	SW846 8260C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	X157474.D	1	09/02/15	PR	n/a	n/a	VX6773
Run #2							

	<b>Initial Weight</b>
Run #1	5.3 g
Run #2	

**VOA TCL List**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
67-64-1	Acetone	ND	11	2.4	ug/kg	
71-43-2	Benzene	ND	0.53	0.14	ug/kg	
74-97-5	Bromochloromethane	ND	5.3	0.32	ug/kg	
75-27-4	Bromodichloromethane	ND	2.1	0.16	ug/kg	
75-25-2	Bromoform	ND	5.3	0.25	ug/kg	
74-83-9	Bromomethane	ND	5.3	0.38	ug/kg	
78-93-3	2-Butanone (MEK)	ND	11	2.0	ug/kg	
75-15-0	Carbon disulfide	ND	2.1	0.24	ug/kg	
56-23-5	Carbon tetrachloride	ND	2.1	0.24	ug/kg	
108-90-7	Chlorobenzene	ND	2.1	0.16	ug/kg	
75-00-3	Chloroethane	ND	5.3	0.51	ug/kg	
67-66-3	Chloroform	ND	2.1	0.16	ug/kg	
74-87-3	Chloromethane	ND	5.3	0.28	ug/kg	
110-82-7	Cyclohexane	ND	2.1	0.33	ug/kg	
96-12-8	1,2-Dibromo-3-chloropropane	ND	2.1	0.57	ug/kg	
124-48-1	Dibromochloromethane	ND	2.1	0.22	ug/kg	
106-93-4	1,2-Dibromoethane	ND	1.1	0.14	ug/kg	
95-50-1	1,2-Dichlorobenzene	ND	1.1	0.13	ug/kg	
541-73-1	1,3-Dichlorobenzene	ND	1.1	0.17	ug/kg	
106-46-7	1,4-Dichlorobenzene	ND	1.1	0.24	ug/kg	
75-71-8	Dichlorodifluoromethane	ND	5.3	0.38	ug/kg	
75-34-3	1,1-Dichloroethane	ND	1.1	0.15	ug/kg	
107-06-2	1,2-Dichloroethane	ND	1.1	0.14	ug/kg	
75-35-4	1,1-Dichloroethene	ND	1.1	0.62	ug/kg	
156-59-2	cis-1,2-Dichloroethene	ND	1.1	0.82	ug/kg	
156-60-5	trans-1,2-Dichloroethene	ND	1.1	0.62	ug/kg	
78-87-5	1,2-Dichloropropane	ND	2.1	0.25	ug/kg	
10061-01-5	cis-1,3-Dichloropropene	ND	2.1	0.12	ug/kg	
10061-02-6	trans-1,3-Dichloropropene	ND	2.1	0.19	ug/kg	
100-41-4	Ethylbenzene	ND	1.1	0.17	ug/kg	
76-13-1	Freon 113	ND	5.3	0.47	ug/kg	
591-78-6	2-Hexanone	ND	5.3	1.4	ug/kg	

ND = Not detected      MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 2 of 2

35  
3

<b>Client Sample ID:</b>	IDW-SO-3-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-3	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	89.7
<b>Method:</b>	SW846 8260C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**VOA TCL List**

CAS No.	Compound	Result	RL	MDL	Units	Q
98-82-8	Isopropylbenzene	ND	2.1	0.11	ug/kg	
79-20-9	Methyl Acetate	ND	5.3	0.90	ug/kg	
108-87-2	Methylcyclohexane	ND	2.1	0.24	ug/kg	
1634-04-4	Methyl Tert Butyl Ether	ND	1.1	0.16	ug/kg	
108-10-1	4-Methyl-2-pentanone(MIBK)	ND	5.3	0.48	ug/kg	
75-09-2	Methylene chloride	ND	5.3	1.0	ug/kg	
100-42-5	Styrene	ND	2.1	0.19	ug/kg	
79-34-5	1,1,2,2-Tetrachloroethane	ND	2.1	0.18	ug/kg	
127-18-4	Tetrachloroethene	ND	2.1	0.32	ug/kg	
108-88-3	Toluene	ND	1.1	0.22	ug/kg	
87-61-6	1,2,3-Trichlorobenzene	ND	5.3	0.19	ug/kg	
120-82-1	1,2,4-Trichlorobenzene	ND	5.3	0.18	ug/kg	
71-55-6	1,1,1-Trichloroethane	ND	2.1	0.16	ug/kg	
79-00-5	1,1,2-Trichloroethane	ND	2.1	0.15	ug/kg	
79-01-6	Trichloroethene	ND	1.1	0.15	ug/kg	
75-69-4	Trichlorofluoromethane	ND	5.3	0.26	ug/kg	
75-01-4	Vinyl chloride	ND	2.1	0.21	ug/kg	
	m,p-Xylene	ND	1.1	0.37	ug/kg	
95-47-6	o-Xylene	ND	1.1	0.29	ug/kg	
1330-20-7	Xylene (total)	ND	1.1	0.29	ug/kg	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
1868-53-7	Dibromofluoromethane	104%		70-122%
17060-07-0	1,2-Dichloroethane-D4	104%		68-124%
2037-26-5	Toluene-D8	99%		77-125%
460-00-4	4-Bromofluorobenzene	103%		72-130%

CAS No.	Tentatively Identified Compounds	R.T.	Est. Conc.	Units	Q
	Total TIC, Volatile		0	ug/kg	
	Total Alkanes		0	ug/kg	

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 4

<b>Client Sample ID:</b>	IDW-SO-3-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-3	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	89.7
<b>Method:</b>	SW846 8270D SW846 3550C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1 <sup>a</sup>	3P46380.D	2	08/31/15	AD	08/28/15	OP86778	E3P2077
Run #2	3P46452.D	20	09/02/15	OYA	08/28/15	OP86778	E3P2081
Run #3	3P46453.D	200	09/02/15	OYA	08/28/15	OP86778	E3P2081

	<b>Initial Weight</b>	<b>Final Volume</b>
Run #1	32.3 g	1.0 ml
Run #2	32.3 g	1.0 ml
Run #3	32.3 g	1.0 ml

**ABN TCL List (SOM0 2.0)**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
95-57-8	2-Chlorophenol	ND	140	63	ug/kg	
59-50-7	4-Chloro-3-methyl phenol	ND	350	130	ug/kg	
120-83-2	2,4-Dichlorophenol	ND	350	130	ug/kg	
105-67-9	2,4-Dimethylphenol	ND	350	150	ug/kg	
51-28-5	2,4-Dinitrophenol	ND	350	290	ug/kg	
534-52-1	4,6-Dinitro-o-cresol	ND	350	56	ug/kg	
95-48-7	2-Methylphenol	ND	140	90	ug/kg	
	3&4-Methylphenol	157	140	77	ug/kg	
88-75-5	2-Nitrophenol	ND	350	63	ug/kg	
100-02-7	4-Nitrophenol	ND	690	210	ug/kg	
87-86-5	Pentachlorophenol	ND	350	170	ug/kg	
108-95-2	Phenol	99.7	140	45	ug/kg	J
58-90-2	2,3,4,6-Tetrachlorophenol	ND	350	160	ug/kg	
95-95-4	2,4,5-Trichlorophenol	ND	350	150	ug/kg	
88-06-2	2,4,6-Trichlorophenol	ND	350	110	ug/kg	
83-32-9	Acenaphthene	17800 <sup>b</sup>	690	140	ug/kg	
208-96-8	Acenaphthylene	1190	69	10	ug/kg	
98-86-2	Acetophenone	ND	350	22	ug/kg	
120-12-7	Anthracene	21400 <sup>b</sup>	690	150	ug/kg	
1912-24-9	Atrazine	ND	140	41	ug/kg	
56-55-3	Benzo(a)anthracene	57900 <sup>b</sup>	690	130	ug/kg	
50-32-8	Benzo(a)pyrene	62200 <sup>b</sup>	690	170	ug/kg	
205-99-2	Benzo(b)fluoranthene	68000 <sup>b</sup>	690	140	ug/kg	
191-24-2	Benzo(g,h,i)perylene	33900 <sup>b</sup>	690	230	ug/kg	
207-08-9	Benzo(k)fluoranthene	24900 <sup>b</sup>	690	220	ug/kg	
101-55-3	4-Bromophenyl phenyl ether	ND	140	28	ug/kg	
85-68-7	Butyl benzyl phthalate	ND	140	27	ug/kg	
92-52-4	1,1'-Biphenyl	554	140	14	ug/kg	
100-52-7	Benzaldehyde	ND	350	16	ug/kg	
91-58-7	2-Chloronaphthalene	ND	140	16	ug/kg	

ND = Not detected      MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 2 of 4

35  
3

<b>Client Sample ID:</b>	IDW-SO-3-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-3	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	89.7
<b>Method:</b>	SW846 8270D SW846 3550C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**ABN TCL List (SOM0 2.0)**

CAS No.	Compound	Result	RL	MDL	Units	Q
106-47-8	4-Chloroaniline	ND	350	22	ug/kg	
86-74-8	Carbazole	9290 <sup>b</sup>	1400	150	ug/kg	
105-60-2	Caprolactam	ND	140	43	ug/kg	
218-01-9	Chrysene	57900 <sup>b</sup>	690	170	ug/kg	
111-91-1	bis(2-Chloroethoxy)methane	ND	140	46	ug/kg	
111-44-4	bis(2-Chloroethyl)ether	ND	140	16	ug/kg	
108-60-1	bis(2-Chloroisopropyl)ether	ND	140	24	ug/kg	
7005-72-3	4-Chlorophenyl phenyl ether	ND	140	15	ug/kg	
121-14-2	2,4-Dinitrotoluene	ND	69	23	ug/kg	
606-20-2	2,6-Dinitrotoluene	ND	69	15	ug/kg	
91-94-1	3,3'-Dichlorobenzidine	ND	140	37	ug/kg	
123-91-1	1,4-Dioxane	ND	69	46	ug/kg	
53-70-3	Dibenzo(a,h)anthracene	10200 <sup>b</sup>	690	170	ug/kg	
132-64-9	Dibenzofuran	4700	140	11	ug/kg	
84-74-2	Di-n-butyl phthalate	ND	140	18	ug/kg	
117-84-0	Di-n-octyl phthalate	ND	140	17	ug/kg	
84-66-2	Diethyl phthalate	ND	140	17	ug/kg	
131-11-3	Dimethyl phthalate	ND	140	14	ug/kg	
117-81-7	bis(2-Ethylhexyl)phthalate	ND	140	22	ug/kg	
206-44-0	Fluoranthene	92400 <sup>c</sup>	6900	2400	ug/kg	
86-73-7	Fluorene	9540 <sup>b</sup>	690	520	ug/kg	
118-74-1	Hexachlorobenzene	ND	140	18	ug/kg	
87-68-3	Hexachlorobutadiene	ND	69	23	ug/kg	
77-47-4	Hexachlorocyclopentadiene	ND	690	26	ug/kg	
67-72-1	Hexachloroethane	ND	350	35	ug/kg	
193-39-5	Indeno(1,2,3-cd)pyrene	39400 <sup>b</sup>	690	220	ug/kg	
78-59-1	Isophorone	ND	140	12	ug/kg	
91-57-6	2-Methylnaphthalene	2470	140	16	ug/kg	
88-74-4	2-Nitroaniline	ND	350	32	ug/kg	
99-09-2	3-Nitroaniline	ND	350	23	ug/kg	
100-01-6	4-Nitroaniline	ND	350	19	ug/kg	
91-20-3	Naphthalene	5860	69	10	ug/kg	
98-95-3	Nitrobenzene	ND	140	28	ug/kg	
621-64-7	N-Nitroso-di-n-propylamine	ND	140	19	ug/kg	
86-30-6	N-Nitrosodiphenylamine	ND	350	17	ug/kg	
85-01-8	Phenanthrene	64300 <sup>c</sup>	6900	1500	ug/kg	
129-00-0	Pyrene	75200 <sup>c</sup>	6900	1600	ug/kg	
95-94-3	1,2,4,5-Tetrachlorobenzene	ND	350	12	ug/kg	

ND = Not detected      MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

<b>Client Sample ID:</b>	IDW-SO-3-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-3	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	89.7
<b>Method:</b>	SW846 8270D SW846 3550C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**ABN TCL List (SOM0 2.0)**

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Run# 3	Limits
367-12-4	2-Fluorophenol	62%	38%	0% <sup>d</sup>	22-121%
4165-62-2	Phenol-d5	65%	41%	0% <sup>d</sup>	27-119%
118-79-6	2,4,6-Tribromophenol	54%	36%	0% <sup>d</sup>	17-158%
4165-60-0	Nitrobenzene-d5	81%	54%	0% <sup>d</sup>	33-127%
321-60-8	2-Fluorobiphenyl	64%	64%	0% <sup>d</sup>	41-121%
1718-51-0	Terphenyl-d14	50%	60%	0% <sup>d</sup>	44-137%

CAS No.	Tentatively Identified Compounds	R.T.	Est. Conc.	Units	Q
90-12-0	Naphthalene, 1-methyl-unknown	6.39 7.94	570 2500	ug/kg	JN J
	unknown	7.97	1700	ug/kg	J
	unknown	8.06	1600	ug/kg	J
	Phenanthere methyl	10.13	400	ug/kg	J
	unknown	10.28	650	ug/kg	J
	Pyrene methyl	12.65	1000	ug/kg	J
	Pyrene methyl	12.80	680	ug/kg	J
	Pyrene methyl	12.86	370	ug/kg	J
	unknown	13.99	370	ug/kg	J
	unknown	14.08	570	ug/kg	J
	unknown	14.83	500	ug/kg	J
	unknown	15.06	450	ug/kg	J
	unknown	15.15	300	ug/kg	J
	Chrysene methyl	15.51	610	ug/kg	J
	unknown	15.69	350	ug/kg	J
	unknown	15.80	350	ug/kg	J
	unknown PAH substance	17.14	660	ug/kg	J
	unknown PAH substance	17.50	1600	ug/kg	J
	unknown PAH substance	17.75	600	ug/kg	J
	unknown	18.04	630	ug/kg	J
	unknown	18.53	340	ug/kg	J
	unknown PAH substance	19.47	520	ug/kg	J
	unknown PAH substance	19.86	440	ug/kg	J
	unknown PAH substance	19.91	520	ug/kg	J
	Total TIC, Semi-Volatile		18280	ug/kg	J
	Total Alkanes		0	ug/kg	

(a) Dilution required due to viscosity of the extract matrix

(b) Result is from Run# 2

(c) Result is from Run# 3

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 4 of 4

35  
3

<b>Client Sample ID:</b>	IDW-SO-3-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-3	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	89.7
<b>Method:</b>	SW846 8270D SW846 3550C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**ABN TCL List (SOM0 2.0)**

CAS No.	Compound	Result	RL	MDL	Units	Q
---------	----------	--------	----	-----	-------	---

(d) Outside control limits due to dilution.

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

35  
3

<b>Client Sample ID:</b>	IDW-SO-3-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-3	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	89.7
<b>Method:</b>	SW846 8081B SW846 3546		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	1G114754.D	1	09/02/15	YD	08/24/15	OP86662	G1G3770
Run #2							

	<b>Initial Weight</b>	<b>Final Volume</b>
Run #1	17.0 g	10.0 ml
Run #2		

**Pesticide TCL List**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
309-00-2	Aldrin	ND	0.66	0.58	ug/kg	
319-84-6	alpha-BHC	ND	0.66	0.44	ug/kg	
319-85-7	beta-BHC	ND	0.66	0.40	ug/kg	
319-86-8	delta-BHC	ND	0.66	0.26	ug/kg	
58-89-9	gamma-BHC (Lindane)	ND	0.66	0.30	ug/kg	
5103-71-9	alpha-Chlordane	ND	0.66	0.35	ug/kg	
5103-74-2	gamma-Chlordane	ND	0.66	0.50	ug/kg	
57-74-9	Chlordane (alpha and gamma)	ND	0.66	0.35	ug/kg	
60-57-1	Dieldrin	ND	0.66	0.51	ug/kg	
72-54-8	4,4'-DDD	ND	0.66	0.24	ug/kg	
72-55-9	4,4'-DDE	ND	0.66	0.22	ug/kg	
50-29-3	4,4'-DDT <sup>a</sup>	17.4	0.66	0.25	ug/kg	
72-20-8	Endrin	ND	0.66	0.23	ug/kg	
1031-07-8	Endosulfan sulfate	ND	0.66	0.37	ug/kg	
7421-93-4	Endrin aldehyde <sup>a</sup>	26.0	0.66	0.49	ug/kg	
959-98-8	Endosulfan-I	ND	0.66	0.22	ug/kg	
33213-65-9	Endosulfan-II	ND	0.66	0.62	ug/kg	
76-44-8	Heptachlor	ND	0.66	0.54	ug/kg	
1024-57-3	Heptachlor epoxide	ND	0.66	0.27	ug/kg	
72-43-5	Methoxychlor	ND	1.3	0.36	ug/kg	
53494-70-5	Endrin ketone	ND	0.66	0.34	ug/kg	
8001-35-2	Toxaphene	ND	16	11	ug/kg	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
877-09-8	Tetrachloro-m-xylene	42%		24-136%
877-09-8	Tetrachloro-m-xylene	46%		24-136%
2051-24-3	Decachlorobiphenyl	95%		10-153%
2051-24-3	Decachlorobiphenyl	1532% <sup>b</sup>		10-153%

(a) More than 40 % RPD for detected concentrations between the two GC columns.

(b) Outside control limits due to matrix interference.

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

35  
3

<b>Client Sample ID:</b>	IDW-SO-3-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-3	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	89.7
<b>Method:</b>	SW846 8082A SW846 3546		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	2G119165.D	1	08/28/15	DG	08/24/15	OP86661	G2G3447
Run #2							

	<b>Initial Weight</b>	<b>Final Volume</b>
Run #1	17.0 g	10.0 ml
Run #2		

**PCB List**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
12674-11-2	Aroclor 1016	ND	33	10	ug/kg	
11104-28-2	Aroclor 1221	ND	33	19	ug/kg	
11141-16-5	Aroclor 1232	ND	33	11	ug/kg	
53469-21-9	Aroclor 1242	ND	33	15	ug/kg	
12672-29-6	Aroclor 1248	ND	33	10	ug/kg	
11097-69-1	Aroclor 1254	ND	33	15	ug/kg	
11096-82-5	Aroclor 1260	ND	33	14	ug/kg	
11100-14-4	Aroclor 1268	ND	33	10	ug/kg	
37324-23-5	Aroclor 1262	ND	33	9.2	ug/kg	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
877-09-8	Tetrachloro-m-xylene	58%		20-152%
877-09-8	Tetrachloro-m-xylene	50%		20-152%
2051-24-3	Decachlorobiphenyl	1188% <sup>a</sup>		12-157%
2051-24-3	Decachlorobiphenyl	759% <sup>a</sup>		12-157%

(a) Outside control limits due to matrix interference.

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

3.6  
3

<b>Client Sample ID:</b>	IDW-SO-3-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-3A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	89.7
<b>Method:</b>	SW846 8260C SW846 1311		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	2V25462.D	5	08/25/15	HA	08/23/15	GP91434	V2V1022
Run #2							

<b>Purge Volume</b>	
Run #1	5.0 ml
Run #2	

**VOA TCLP Leachate****TCLP Leachate method SW846 1311**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>HW#</b>	<b>MCL</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
71-43-2	Benzene	ND	D018	0.50	0.0025	0.0012	mg/l	
78-93-3	2-Butanone (MEK)	ND	D035	200	0.10	0.028	mg/l	
56-23-5	Carbon tetrachloride	ND	D019	0.50	0.0050	0.0011	mg/l	
108-90-7	Chlorobenzene	ND	D021	100	0.0050	0.00093	mg/l	
67-66-3	Chloroform	ND	D022	6.0	0.0050	0.00094	mg/l	
106-46-7	1,4-Dichlorobenzene	ND	D027	7.5	0.0050	0.0014	mg/l	
107-06-2	1,2-Dichloroethane	ND	D028	0.50	0.0050	0.00090	mg/l	
75-35-4	1,1-Dichloroethene	ND	D029	0.70	0.0050	0.0026	mg/l	
127-18-4	Tetrachloroethene	ND	D039	0.70	0.0050	0.0020	mg/l	
79-01-6	Trichloroethene	ND	D040	0.50	0.0050	0.0011	mg/l	
75-01-4	Vinyl chloride	ND	D043	0.20	0.0050	0.00074	mg/l	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
1868-53-7	Dibromofluoromethane	94%		76-120%
17060-07-0	1,2-Dichloroethane-D4	92%		64-135%
2037-26-5	Toluene-D8	101%		76-117%
460-00-4	4-Bromofluorobenzene	101%		72-122%

ND = Not detected      MDL = Method Detection Limit  
 MCL = Maximum Contamination Level (40 CFR 261 6/96)  
 E = Indicates value exceeds calibration range

J = Indicates an estimated value  
 B = Indicates analyte found in associated method blank  
 N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

36  
3

<b>Client Sample ID:</b>	IDW-SO-3-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-3A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	89.7
<b>Method:</b>	SW846 8270D SW846 3510C		
<b>Project:</b>	CHMHLMB: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	5P20745.D	1	08/26/15	SD	08/25/15	OP86663	E5P1067
Run #2							

	<b>Initial Volume</b>	<b>Final Volume</b>
Run #1	100 ml	1.0 ml
Run #2		

**ABN TCLP Leachate****TCLP Leachate method SW846 1311**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>HW#</b>	<b>MCL</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
95-48-7	2-Methylphenol	ND	D023	200	0.020	0.0082	mg/l	
	3&4-Methylphenol	ND	D024	200	0.020	0.0067	mg/l	
87-86-5	Pentachlorophenol	ND	D037	100	0.10	0.014	mg/l	
95-95-4	2,4,5-Trichlorophenol	ND	D041	400	0.050	0.015	mg/l	
88-06-2	2,4,6-Trichlorophenol	ND	D042	2.0	0.050	0.014	mg/l	
106-46-7	1,4-Dichlorobenzene	ND	D027	7.5	0.020	0.0023	mg/l	
121-14-2	2,4-Dinitrotoluene	ND	D030	0.13	0.020	0.0026	mg/l	
118-74-1	Hexachlorobenzene	0.0064	D032	0.13	0.020	0.0042	mg/l	J
87-68-3	Hexachlorobutadiene	ND	D033	0.50	0.010	0.0036	mg/l	
67-72-1	Hexachloroethane	ND	D034	3.0	0.050	0.0022	mg/l	
98-95-3	Nitrobenzene	ND	D036	2.0	0.020	0.0046	mg/l	
110-86-1	Pyridine	ND	D038	5.0	0.020	0.0027	mg/l	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
367-12-4	2-Fluorophenol	56%		12-110%
4165-62-2	Phenol-d5	35%		10-110%
118-79-6	2,4,6-Tribromophenol	91%		42-154%
4165-60-0	Nitrobenzene-d5	88%		29-139%
321-60-8	2-Fluorobiphenyl	74%		33-129%
1718-51-0	Terphenyl-d14	96%		10-140%

ND = Not detected      MDL = Method Detection Limit  
 MCL = Maximum Contamination Level (40 CFR 261 6/96)  
 E = Indicates value exceeds calibration range

J = Indicates an estimated value  
 B = Indicates analyte found in associated method blank  
 N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

3.6  
3

<b>Client Sample ID:</b>	IDW-SO-3-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-3A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	89.7
<b>Method:</b>	SW846 8081B SW846 3510C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	6G26589.D	1	09/02/15	YD	08/25/15	OP86672	G6G780
Run #2							

	<b>Initial Volume</b>	<b>Final Volume</b>
Run #1	100 ml	10.0 ml
Run #2		

**Pesticide TCLP Leachate****TCLP Leachate method SW846 1311**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>HW#</b>	<b>MCL</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
58-89-9	gamma-BHC (Lindane)	ND	D013	0.40	0.00010	0.000052	mg/l	
12789-03-6	Chlordane	ND	D020	0.030	0.0050	0.00092	mg/l	
72-20-8	Endrin	ND	D012	0.020	0.00010	0.000045	mg/l	
76-44-8	Heptachlor	ND	D031	0.0080	0.00010	0.000049	mg/l	
1024-57-3	Heptachlor epoxide	ND	D031	0.0080	0.00010	0.000082	mg/l	
72-43-5	Methoxychlor	ND	D014	10	0.00020	0.000072	mg/l	
8001-35-2	Toxaphene	ND	D015	0.50	0.0025	0.0015	mg/l	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
877-09-8	Tetrachloro-m-xylene	78%		30-137%
877-09-8	Tetrachloro-m-xylene	78%		30-137%
2051-24-3	Decachlorobiphenyl	72%		10-137%
2051-24-3	Decachlorobiphenyl	144% <sup>a</sup>		10-137%

(a) Outside control limits due to matrix interference.

ND = Not detected      MDL = Method Detection Limit  
 MCL = Maximum Contamination Level (40 CFR 261 6/96)  
 E = Indicates value exceeds calibration range

J = Indicates an estimated value  
 B = Indicates analyte found in associated method blank  
 N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

3.6  
3

<b>Client Sample ID:</b>	IDW-SO-3-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-3A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	89.7
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**Metals Analysis, TCLP Leachate SW846 1311**

Analyte	Result	HW#	MCL	RL	Units	DF	Prep	Analyzed By	Method	Prep Method
Arsenic	< 0.50	D004	5.0	0.50	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Barium	< 1.0	D005	100	1.0	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Cadmium	< 0.025	D006	1.0	0.025	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Chromium	< 0.050	D007	5.0	0.050	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Lead	< 0.50	D008	5.0	0.50	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Mercury	< 0.00020	D009	0.20	0.00020	mg/l	1	08/24/15	08/24/15	MA	SW846 7470A <sup>1</sup>
Selenium	< 0.50	D010	1.0	0.50	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>
Silver	< 0.050	D011	5.0	0.050	mg/l	5	08/24/15	08/27/15	MS	SW846 6010C <sup>2</sup>

(1) Instrument QC Batch: MA37397

(2) Instrument QC Batch: MA37414

(3) Prep QC Batch: MP88566

(4) Prep QC Batch: MP88584

RL = Reporting Limit

MCL = Maximum Contamination Level (40 CFR 261 6/96)

**Report of Analysis**

Page 1 of 1

3.6  
3

<b>Client Sample ID:</b>	IDW-SO-3-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-3A	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	SO - Soil	<b>Percent Solids:</b>	89.7
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**General Chemistry**

Analyte	Result	RL	Units	DF	Analyzed	By	Method
Corrosivity as pH	7.11 NC		su	1	08/22/15 14:23	SA	SW846 CHAP7
Cyanide Reactivity	< 10	10	mg/kg	1	08/24/15 15:08	BM	SW846 CHAP7/9012 B
Ignitability (Flashpoint)	> 200		Deg. F	1	08/22/15	SA	SW846 CHAP7/ASTM D93
Sulfide Reactivity	< 100	100	mg/kg	1	08/24/15	MP	SW846 CHAP7/9034

RL = Reporting Limit

**Report of Analysis**

Page 1 of 3

37  
3

<b>Client Sample ID:</b>	IDW-AQ-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-4	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	AQ - Water	<b>Percent Solids:</b>	n/a
<b>Method:</b>	SW846 8260C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	3A144272.D	2	08/27/15	TK	n/a	n/a	V3A6236
Run #2							

<b>Purge Volume</b>	
Run #1	5.0 ml
Run #2	

**VOA TCL List**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
67-64-1	Acetone	88.6	20	6.6	ug/l	
71-43-2	Benzene	195	1.0	0.47	ug/l	
74-97-5	Bromochloromethane	ND	2.0	0.74	ug/l	
75-27-4	Bromodichloromethane	0.94	2.0	0.45	ug/l	
75-25-2	Bromoform	ND	2.0	0.47	ug/l	
74-83-9	Bromomethane	ND	4.0	0.85	ug/l	
78-93-3	2-Butanone (MEK)	14.4	20	11	ug/l	J
75-15-0	Carbon disulfide	0.68	4.0	0.51	ug/l	J
56-23-5	Carbon tetrachloride	ND	2.0	0.44	ug/l	
108-90-7	Chlorobenzene	ND	2.0	0.37	ug/l	
75-00-3	Chloroethane	ND	2.0	0.68	ug/l	
67-66-3	Chloroform	1.9	2.0	0.37	ug/l	J
74-87-3	Chloromethane	ND	2.0	0.81	ug/l	
110-82-7	Cyclohexane	ND	10	0.56	ug/l	
96-12-8	1,2-Dibromo-3-chloropropane	ND	4.0	2.0	ug/l	
124-48-1	Dibromochloromethane	0.39	2.0	0.31	ug/l	J
106-93-4	1,2-Dibromoethane	ND	2.0	0.46	ug/l	
95-50-1	1,2-Dichlorobenzene	2.2	2.0	0.37	ug/l	
541-73-1	1,3-Dichlorobenzene	ND	2.0	0.45	ug/l	
106-46-7	1,4-Dichlorobenzene	ND	2.0	0.55	ug/l	
75-71-8	Dichlorodifluoromethane	ND	4.0	1.8	ug/l	
75-34-3	1,1-Dichloroethane	ND	2.0	0.34	ug/l	
107-06-2	1,2-Dichloroethane	ND	2.0	0.36	ug/l	
75-35-4	1,1-Dichloroethene	ND	2.0	1.0	ug/l	
156-59-2	cis-1,2-Dichloroethene	ND	2.0	0.55	ug/l	
156-60-5	trans-1,2-Dichloroethene	ND	2.0	1.3	ug/l	
78-87-5	1,2-Dichloropropane	ND	2.0	0.79	ug/l	
10061-01-5	cis-1,3-Dichloropropene	ND	2.0	0.41	ug/l	
10061-02-6	trans-1,3-Dichloropropene	ND	2.0	0.37	ug/l	
100-41-4	Ethylbenzene	144	2.0	0.54	ug/l	
76-13-1	Freon 113	ND	10	1.0	ug/l	
591-78-6	2-Hexanone	ND	10	3.5	ug/l	

ND = Not detected      MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 2 of 3

37  
3

<b>Client Sample ID:</b>	IDW-AQ-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-4	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	AQ - Water	<b>Percent Solids:</b>	n/a
<b>Method:</b>	SW846 8260C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**VOA TCL List**

CAS No.	Compound	Result	RL	MDL	Units	Q
98-82-8	Isopropylbenzene	11.3	2.0	0.47	ug/l	
79-20-9	Methyl Acetate	ND	10	3.8	ug/l	
108-87-2	Methylcyclohexane	1.7	10	0.44	ug/l	J
1634-04-4	Methyl Tert Butyl Ether	ND	2.0	0.47	ug/l	
108-10-1	4-Methyl-2-pentanone(MIBK)	7.6	10	2.0	ug/l	J
75-09-2	Methylene chloride	ND	4.0	1.5	ug/l	
100-42-5	Styrene	86.4	2.0	0.54	ug/l	
79-34-5	1,1,2,2-Tetrachloroethane	ND	2.0	0.41	ug/l	
127-18-4	Tetrachloroethene	ND	2.0	0.80	ug/l	
108-88-3	Toluene	218	2.0	0.32	ug/l	
87-61-6	1,2,3-Trichlorobenzene	ND	2.0	0.45	ug/l	
120-82-1	1,2,4-Trichlorobenzene	ND	2.0	0.42	ug/l	
71-55-6	1,1,1-Trichloroethane	ND	2.0	0.50	ug/l	
79-00-5	1,1,2-Trichloroethane	ND	2.0	0.43	ug/l	
79-01-6	Trichloroethene	ND	2.0	0.45	ug/l	
75-69-4	Trichlorofluoromethane	ND	4.0	0.86	ug/l	
75-01-4	Vinyl chloride	ND	2.0	0.29	ug/l	
	m,p-Xylene	326	2.0	0.75	ug/l	
95-47-6	o-Xylene	208	2.0	0.33	ug/l	
1330-20-7	Xylene (total)	534	2.0	0.33	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
1868-53-7	Dibromofluoromethane	81%		76-120%
17060-07-0	1,2-Dichloroethane-D4	93%		73-122%
2037-26-5	Toluene-D8	111%		84-119%
460-00-4	4-Bromofluorobenzene	95%		78-117%

CAS No.	Tentatively Identified Compounds	R.T.	Est. Conc.	Units	Q
	C3 alkyl benzene	16.64	41	ug/l	J
95-63-6	Benzene, 1,2,4-trimethyl-	17.14	82	ug/l	JN
271-89-6	Benzofuran	17.53	95	ug/l	JN
496-11-7	Indane	17.90	590	ug/l	JN
95-13-6	Indene	18.16	270	ug/l	JN
	Benzofuran, methyl- isomer	18.76	49	ug/l	J
	Benzofuran, methyl- isomer	18.88	100	ug/l	J
	1H-Indene-dihydro-methyl- isomer	19.14	37	ug/l	J
	1H-Indene-dihydro-methyl- isomer	19.34	35	ug/l	J
	1H-Indene-methyl- isomer	19.42	68	ug/l	J

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 3 of 3

37  
3

<b>Client Sample ID:</b>	IDW-AQ-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-4	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	AQ - Water	<b>Percent Solids:</b>	n/a
<b>Method:</b>	SW846 8260C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**VOA TCL List**

CAS No.	Tentatively Identified Compounds	R.T.	Est. Conc.	Units	Q
91-20-3	1H-Indene-methyl- isomer	19.55	110	ug/l	J
	Naphthalene	20.15	2700	ug/l	JN
	Benzothiophene	20.30	180	ug/l	J
	Naphthalene, methyl- isomer	21.48	270	ug/l	J
	Naphthalene, methyl- isomer	21.76	130	ug/l	J
	Total TIC, Volatile		4757	ug/l	J
	Total Alkanes		0	ug/l	

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 3

37  
3

<b>Client Sample ID:</b>	IDW-AQ-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-4	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	AQ - Water	<b>Percent Solids:</b>	n/a
<b>Method:</b>	SW846 8270D SW846 3510C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	6P18979.D	1	08/27/15	AD	08/26/15	OP86664	E6P856
Run #2	6P19006.D	40	08/27/15	BP	08/26/15	OP86664	E6P857
Run #3 <sup>a</sup>	6P19030.D	1	08/28/15	SW	08/27/15	OP86765	E6P858

	<b>Initial Volume</b>	<b>Final Volume</b>
Run #1	800 ml	1.0 ml
Run #2	800 ml	1.0 ml
Run #3	850 ml	1.0 ml

**ABN TCL List without all PAH**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
95-57-8	2-Chlorophenol	ND	6.3	1.6	ug/l	
59-50-7	4-Chloro-3-methyl phenol	ND	6.3	1.6	ug/l	
120-83-2	2,4-Dichlorophenol	ND	2.5	2.0	ug/l	
105-67-9	2,4-Dimethylphenol	85.0	6.3	2.3	ug/l	
51-28-5	2,4-Dinitrophenol	ND	13	8.1	ug/l	
95-48-7	2-Methylphenol	4.4	2.5	1.6	ug/l	
	3&4-Methylphenol	ND	2.5	1.3	ug/l	
88-75-5	2-Nitrophenol	ND	6.3	2.3	ug/l	
100-02-7	4-Nitrophenol	ND	13	1.1	ug/l	
108-95-2	Phenol	ND	2.5	0.68	ug/l	
58-90-2	2,3,4,6-Tetrachlorophenol	ND	6.3	1.8	ug/l	
95-95-4	2,4,5-Trichlorophenol	ND	6.3	2.1	ug/l	
88-06-2	2,4,6-Trichlorophenol	ND	6.3	1.9	ug/l	
83-32-9	Acenaphthene	254 <sup>b</sup>	50	15	ug/l	
208-96-8	Acenaphthylene	21.2	1.3	0.25	ug/l	
98-86-2	Acetophenone	ND	2.5	0.46	ug/l	
120-12-7	Anthracene	29.4	1.3	0.24	ug/l	
1912-24-9	Atrazine	ND	2.5	0.53	ug/l	
100-52-7	Benzaldehyde	ND	6.3	0.84	ug/l	
191-24-2	Benzo(g,h,i)perylene	1.2	1.3	0.39	ug/l	J
101-55-3	4-Bromophenyl phenyl ether	ND	2.5	0.31	ug/l	
85-68-7	Butyl benzyl phthalate	ND	2.5	0.28	ug/l	
92-52-4	1,1'-Biphenyl	70.4	1.3	0.34	ug/l	
91-58-7	2-Chloronaphthalene	ND	2.5	0.43	ug/l	
106-47-8	4-Chloroaniline	ND	6.3	0.38	ug/l	
86-74-8	Carbazole	199 <sup>b</sup>	50	8.4	ug/l	
105-60-2	Caprolactam	ND	2.5	0.51	ug/l	
218-01-9	Chrysene	3.6	1.3	0.20	ug/l	
111-91-1	bis(2-Chloroethoxy)methane	ND	2.5	0.52	ug/l	
111-44-4	bis(2-Chloroethyl)ether	ND	2.5	0.54	ug/l	

ND = Not detected      MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 2 of 3

37  
3

<b>Client Sample ID:</b>	IDW-AQ-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-4	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	AQ - Water	<b>Percent Solids:</b>	n/a
<b>Method:</b>	SW846 8270D SW846 3510C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**ABN TCL List without all PAH**

CAS No.	Compound	Result	RL	MDL	Units	Q
108-60-1	bis(2-Chloroisopropyl)ether	ND	2.5	0.51	ug/l	
7005-72-3	4-Chlorophenyl phenyl ether	ND	2.5	0.48	ug/l	
121-14-2	2,4-Dinitrotoluene	ND	1.3	0.40	ug/l	
606-20-2	2,6-Dinitrotoluene	ND	1.3	0.32	ug/l	
91-94-1	3,3'-Dichlorobenzidine	ND	2.5	0.70	ug/l	
123-91-1	1,4-Dioxane	1.6	1.3	0.89	ug/l	
132-64-9	Dibenzofuran	185 <sup>b</sup>	250	11	ug/l	J
84-74-2	Di-n-butyl phthalate	ND	2.5	0.73	ug/l	
117-84-0	Di-n-octyl phthalate	ND	2.5	0.31	ug/l	
84-66-2	Diethyl phthalate	ND	2.5	0.29	ug/l	
131-11-3	Dimethyl phthalate	ND	2.5	0.33	ug/l	
117-81-7	bis(2-Ethylhexyl)phthalate	ND	2.5	0.69	ug/l	
206-44-0	Fluoranthene	29.0	1.3	0.20	ug/l	
86-73-7	Fluorene	160 <sup>b</sup>	50	14	ug/l	
87-68-3	Hexachlorobutadiene	ND	1.3	0.49	ug/l	
77-47-4	Hexachlorocyclopentadiene	ND	13	0.60	ug/l	
67-72-1	Hexachloroethane	ND	2.5	0.36	ug/l	
78-59-1	Isophorone	ND	2.5	0.42	ug/l	
91-57-6	2-Methylnaphthalene	742 <sup>b</sup>	50	15	ug/l	
88-74-4	2-Nitroaniline	ND	6.3	0.40	ug/l	
99-09-2	3-Nitroaniline	ND	6.3	0.33	ug/l	
100-01-6	4-Nitroaniline	ND	6.3	0.38	ug/l	
91-20-3	Naphthalene	4030 <sup>b</sup>	50	13	ug/l	
98-95-3	Nitrobenzene	ND	2.5	0.65	ug/l	
621-64-7	N-Nitroso-di-n-propylamine	ND	2.5	0.47	ug/l	
86-30-6	N-Nitrosodiphenylamine	ND	6.3	0.26	ug/l	
85-01-8	Phenanthrene	220 <sup>b</sup>	50	9.3	ug/l	
129-00-0	Pyrene	17.0	1.3	0.24	ug/l	
95-94-3	1,2,4,5-Tetrachlorobenzene	ND	2.5	0.56	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Run# 3	Limits
367-12-4	2-Fluorophenol	2% <sup>c</sup>	0% <sup>d</sup>	2% <sup>d</sup>	14-88%
4165-62-2	Phenol-d5	0% <sup>c</sup>	0% <sup>d</sup>	1% <sup>d</sup>	10-110%
118-79-6	2,4,6-Tribromophenol	0% <sup>c</sup>	0% <sup>d</sup>	0% <sup>d</sup>	39-149%
4165-60-0	Nitrobenzene-d5	121%	90%	139% <sup>d</sup>	32-128%
321-60-8	2-Fluorobiphenyl	83%	100%	96%	35-119%
1718-51-0	Terphenyl-d14	76%	91%	96%	10-126%

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 3 of 3

37  
3

<b>Client Sample ID:</b>	IDW-AQ-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-4	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	AQ - Water	<b>Percent Solids:</b>	n/a
<b>Method:</b>	SW846 8270D SW846 3510C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**ABN TCL List without all PAH**

CAS No.	Tentatively Identified Compounds	R.T.	Est. Conc.	Units	Q
62-53-3	Pyridine, -methyl-system artifact/aldol-condensation	2.93	34	ug/l	J
		3.16	42	ug/l	J
	Pyridine, -dimethyl-C3 alkyl benzene	3.86	110	ug/l	J
		4.10	31	ug/l	J
	Aniline	4.21	28	ug/l	JN
	Pyridine, -trimethyl-C3 alkyl benzene	4.28	85	ug/l	J
	unknown	4.32	75	ug/l	J
496-11-7	unknown	4.35	110	ug/l	J
	unknown	4.38	31	ug/l	J
	unknown	4.51	32	ug/l	J
	Indane	4.59	310	ug/l	JN
	Benzonitrile, -methyl-	4.76	56	ug/l	J
	unknown	4.95	25	ug/l	J
	Naphthalene dimethyl	7.00	36	ug/l	J
90-43-7	Naphthalene dimethyl	7.08	69	ug/l	J
	Naphthalene dimethyl	7.12	30	ug/l	J
	Quinoline, -dimethyl-	7.23	59	ug/l	J
	o-Hydroxybiphenyl	7.74	34	ug/l	JN
	unknown	8.11	31	ug/l	J
	unknown	9.86	47	ug/l	J
	unknown	10.21	53	ug/l	J
	unknown	10.82	30	ug/l	J
	unknown	12.04	28	ug/l	J
	unknown	12.51	74	ug/l	J
	Total TIC, Semi-Volatile		1418	ug/l	J
	Total Alkanes		0	ug/l	

- (a) Confirmation run for surrogate recoveries.  
 (b) Result is from Run# 2  
 (c) Outside control limits due to matrix interference. Confirmed by re-extraction.  
 (d) Outside control limits due to matrix interference.

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

37  
3

<b>Client Sample ID:</b>	IDW-AQ-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-4	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	AQ - Water	<b>Percent Solids:</b>	n/a
<b>Method:</b>	SW846 8270D BY SIM	SW846 3510C	
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	3M57207.D	1	08/27/15	LK	08/26/15	OP86664A	E3M2646
Run #2 <sup>a</sup>	3M57340.D	1	09/01/15	AD	08/27/15	OP86765A	E3M2653

	<b>Initial Volume</b>	<b>Final Volume</b>
Run #1	800 ml	1.0 ml
Run #2	850 ml	1.0 ml

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
534-52-1	4,6-Dinitro-o-cresol	ND	0.63	0.11	ug/l	
87-86-5	Pentachlorophenol	ND	0.31	0.14	ug/l	
56-55-3	Benzo(a)anthracene	1.09	0.063	0.023	ug/l	
50-32-8	Benzo(a)pyrene	2.53	0.063	0.037	ug/l	
205-99-2	Benzo(b)fluoranthene	3.64	0.13	0.026	ug/l	
207-08-9	Benzo(k)fluoranthene	0.809	0.13	0.024	ug/l	
53-70-3	Dibenzo(a,h)anthracene	0.394	0.13	0.044	ug/l	
118-74-1	Hexachlorobenzene	ND	0.019	0.018	ug/l	
193-39-5	Indeno(1,2,3-cd)pyrene	1.14	0.13	0.039	ug/l	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
367-12-4	2-Fluorophenol	0% <sup>c</sup>	1% <sup>b</sup>	10-110%
4165-62-2	Phenol-d5	0% <sup>c</sup>	1% <sup>b</sup>	10-110%
118-79-6	2,4,6-Tribromophenol	0% <sup>c</sup>	0% <sup>b</sup>	10-157%
4165-60-0	Nitrobenzene-d5	44%	57%	23-131%
321-60-8	2-Fluorobiphenyl	67%	78%	24-120%
1718-51-0	Terphenyl-d14	17%	32%	10-125%

- (a) Confirmation run for surrogate recoveries.  
 (b) Outside control limits due to matrix interference.  
 (c) Outside control limits due to matrix interference. Confirmed by re-extraction.

ND = Not detected      MDL = Method Detection Limit  
 RL = Reporting Limit  
 E = Indicates value exceeds calibration range

J = Indicates an estimated value  
 B = Indicates analyte found in associated method blank  
 N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 2

37  
3

<b>Client Sample ID:</b>	IDW-AQ-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-4	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	AQ - Water	<b>Percent Solids:</b>	n/a
<b>Method:</b>	SW846 8081B SW846 3510C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1 <sup>a</sup>	4G59940.D	1	09/03/15	YD	08/25/15	OP86699	G4G1565
Run #2							

	<b>Initial Volume</b>	<b>Final Volume</b>
Run #1	270 ml	2.0 ml
Run #2		

**Pesticide TCL List**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
309-00-2	Aldrin	ND	0.0074	0.0031	ug/l	
319-84-6	alpha-BHC	ND	0.0074	0.0048	ug/l	
319-85-7	beta-BHC	ND	0.0074	0.0064	ug/l	
319-86-8	delta-BHC	ND	0.0074	0.0048	ug/l	
58-89-9	gamma-BHC (Lindane) <sup>b</sup>	0.042	0.0074	0.0039	ug/l	
5103-71-9	alpha-Chlordane	ND	0.0074	0.0045	ug/l	
5103-74-2	gamma-Chlordane	ND	0.0074	0.0037	ug/l	
57-74-9	Chlordane (alpha and gamma)	ND	0.0074	0.0037	ug/l	
60-57-1	Dieldrin	ND	0.0074	0.0037	ug/l	
72-54-8	4,4'-DDD	ND	0.0074	0.0048	ug/l	
72-55-9	4,4'-DDE	ND	0.0074	0.0045	ug/l	
50-29-3	4,4'-DDT	ND	0.0074	0.0038	ug/l	
72-20-8	Endrin	ND	0.0074	0.0033	ug/l	
1031-07-8	Endosulfan sulfate	ND	0.0074	0.0054	ug/l	
7421-93-4	Endrin aldehyde	ND	0.0074	0.0054	ug/l	
53494-70-5	Endrin ketone	0.024	0.0074	0.0035	ug/l	
959-98-8	Endosulfan-I	ND	0.0074	0.0047	ug/l	
33213-65-9	Endosulfan-II	ND	0.0074	0.0049	ug/l	
76-44-8	Heptachlor	ND	0.0074	0.0036	ug/l	
1024-57-3	Heptachlor epoxide	ND	0.0074	0.0060	ug/l	
72-43-5	Methoxychlor	ND	0.015	0.0053	ug/l	
8001-35-2	Toxaphene	ND	0.19	0.11	ug/l	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
877-09-8	Tetrachloro-m-xylene	53%		26-132%
877-09-8	Tetrachloro-m-xylene	88%		26-132%
2051-24-3	Decachlorobiphenyl	58%		10-118%
2051-24-3	Decachlorobiphenyl	119% <sup>c</sup>		10-118%

(a) There is no additional sample for re-extraction.

(b) More than 40 % RPD for detected concentrations between the two GC columns.

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 2 of 2

37  
3

<b>Client Sample ID:</b>	IDW-AQ-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-4	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	AQ - Water	<b>Percent Solids:</b>	n/a
<b>Method:</b>	SW846 8081B SW846 3510C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**Pesticide TCL List**

CAS No.	Compound	Result	RL	MDL	Units	Q
---------	----------	--------	----	-----	-------	---

(c) Outside control limits due to matrix interference.

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

37  
3

<b>Client Sample ID:</b>	IDW-AQ-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-4	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	AQ - Water	<b>Percent Solids:</b>	n/a
<b>Method:</b>	SW846 8082A SW846 3510C		
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

	<b>File ID</b>	<b>DF</b>	<b>Analyzed</b>	<b>By</b>	<b>Prep Date</b>	<b>Prep Batch</b>	<b>Analytical Batch</b>
Run #1	XX176224.D	1	08/26/15	RK	08/25/15	OP86698	GXX5440
Run #2							

	<b>Initial Volume</b>	<b>Final Volume</b>
Run #1	300 ml	2.0 ml
Run #2		

**PCB List**

<b>CAS No.</b>	<b>Compound</b>	<b>Result</b>	<b>RL</b>	<b>MDL</b>	<b>Units</b>	<b>Q</b>
12674-11-2	Aroclor 1016	ND	0.33	0.13	ug/l	
11104-28-2	Aroclor 1221	ND	0.33	0.21	ug/l	
11141-16-5	Aroclor 1232	ND	0.33	0.17	ug/l	
53469-21-9	Aroclor 1242	ND	0.33	0.14	ug/l	
12672-29-6	Aroclor 1248	ND	0.33	0.17	ug/l	
11097-69-1	Aroclor 1254	ND	0.33	0.044	ug/l	
11096-82-5	Aroclor 1260	ND	0.33	0.10	ug/l	
11100-14-4	Aroclor 1268	ND	0.33	0.081	ug/l	
37324-23-5	Aroclor 1262	ND	0.33	0.14	ug/l	

<b>CAS No.</b>	<b>Surrogate Recoveries</b>	<b>Run# 1</b>	<b>Run# 2</b>	<b>Limits</b>
877-09-8	Tetrachloro-m-xylene	73%		10-161%
877-09-8	Tetrachloro-m-xylene	86%		10-161%
2051-24-3	Decachlorobiphenyl	84%		10-137%
2051-24-3	Decachlorobiphenyl	71%		10-137%

ND = Not detected MDL = Method Detection Limit

J = Indicates an estimated value

RL = Reporting Limit

B = Indicates analyte found in associated method blank

E = Indicates value exceeds calibration range

N = Indicates presumptive evidence of a compound

**Report of Analysis**

Page 1 of 1

37  
3

<b>Client Sample ID:</b>	IDW-AQ-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-4	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	AQ - Water	<b>Percent Solids:</b>	n/a
<b>Project:</b>	CHMHLMB: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**Total Metals Analysis**

Analyte	Result	RL	Units	DF	Prep	Analyzed By	Method	Prep Method
Aluminum <sup>a</sup>	< 1000	1000	ug/l	5	08/24/15	08/26/15 ND	SW846 6010C <sup>3</sup>	SW846 3010A <sup>4</sup>
Antimony <sup>a</sup>	< 30	30	ug/l	5	08/24/15	08/26/15 ND	SW846 6010C <sup>3</sup>	SW846 3010A <sup>4</sup>
Arsenic <sup>a</sup>	< 15	15	ug/l	5	08/24/15	08/26/15 ND	SW846 6010C <sup>3</sup>	SW846 3010A <sup>4</sup>
Barium	246	200	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>
Beryllium	< 1.0	1.0	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>
Cadmium	< 3.0	3.0	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>
Calcium	922000	25000	ug/l	5	08/24/15	08/26/15 ND	SW846 6010C <sup>3</sup>	SW846 3010A <sup>4</sup>
Chromium	205	10	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>
Cobalt	< 50	50	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>
Copper	33.6	10	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>
Iron	1240	100	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>
Lead <sup>a</sup>	24.4	15	ug/l	5	08/24/15	08/26/15 ND	SW846 6010C <sup>3</sup>	SW846 3010A <sup>4</sup>
Magnesium	< 5000	5000	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>
Manganese	16.1	15	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>
Mercury	< 0.20	0.20	ug/l	1	08/26/15	08/26/15 VM	SW846 7470A <sup>2</sup>	SW846 7470A <sup>5</sup>
Nickel	< 10	10	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>
Potassium	642000	50000	ug/l	5	08/24/15	08/26/15 ND	SW846 6010C <sup>3</sup>	SW846 3010A <sup>4</sup>
Selenium	18.8	10	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>
Silver	< 10	10	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>
Sodium	814000	50000	ug/l	5	08/24/15	08/26/15 ND	SW846 6010C <sup>3</sup>	SW846 3010A <sup>4</sup>
Thallium <sup>a</sup>	< 10	10	ug/l	5	08/24/15	08/26/15 ND	SW846 6010C <sup>3</sup>	SW846 3010A <sup>4</sup>
Vanadium	< 50	50	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>
Zinc	< 20	20	ug/l	1	08/24/15	08/25/15 BS	SW846 6010C <sup>1</sup>	SW846 3010A <sup>4</sup>

(1) Instrument QC Batch: MA37406

(2) Instrument QC Batch: MA37413

(3) Instrument QC Batch: MA37421

(4) Prep QC Batch: MP88557

(5) Prep QC Batch: MP88620

(a) Elevated detection limit due to dilution required for high interfering element.

RL = Reporting Limit

**Report of Analysis**

Page 1 of 1

37  
3

<b>Client Sample ID:</b>	IDW-AQ-081915	<b>Date Sampled:</b>	08/19/15
<b>Lab Sample ID:</b>	JC1982-4	<b>Date Received:</b>	08/20/15
<b>Matrix:</b>	AQ - Water	<b>Percent Solids:</b>	n/a
<b>Project:</b>	CHMHLMA: Quanta Resources Corporation Superfund Site, Edgewater, NJ		

**General Chemistry**

Analyte	Result	RL	Units	DF	Analyzed	By	Method
Corrosivity as pH	12.45 NC		su	1	08/22/15 13:03	SA	SW846 CHAP7
Cyanide Reactivity	< 10	10	mg/l	1	08/24/15 15:25	BM	SW846 CHAP7/9012B
Ignitability (Flashpoint)	> 200		Deg. F	1	08/22/15	SA	SW846 1010A/ASTM D93
Sulfide Reactivity	< 100	100	mg/l	1	08/24/15	MP	SW846 CHAP7/9034

RL = Reporting Limit



## Misc. Forms

---

### Custody Documents and Other Forms

---

Includes the following where applicable:

- Chain of Custody



SLL  
www

## **CHAIN OF CUSTODY**

2235 Route 130, Dayton, NJ 08810  
TEL. 732-329-0200 FAX: 732-329-3499/3480  
[www.accutest.com](http://www.accutest.com)

PAGE    OF

## JC1982: Chain of Custody

Page 1 of 2



## Accutest Laboratories Sample Receipt Summary

**Accutest Job Number:** JC1982      **Client:** \_\_\_\_\_      **Project:** \_\_\_\_\_  
**Date / Time Received:** 8/20/2015 3:03:00 PM      **Delivery Method:** \_\_\_\_\_      **Airbill #'s:** \_\_\_\_\_

Cooler Temps (Raw Measured) °C: Cooler 1: (2.7);

Cooler Temps (Corrected) °C: Cooler 1: (2.4);

**Cooler Security**      Y or N      Y or N

1. Custody Seals Present:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	3. COC Present:	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2. Custody Seals Intact:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	4. Smpl Dates/Time OK	<input checked="" type="checkbox"/>	<input type="checkbox"/>

**Cooler Temperature**      Y or N

1. Temp criteria achieved:	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2. Cooler temp verification:	IR Gun	
3. Cooler media:	Ice (Bag)	
4. No. Coolers:	1	

**Quality Control Preservation**      Y or N      N/A

1. Trip Blank present / cooler:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2. Trip Blank listed on COC:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3. Samples preserved properly:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
4. VOCs headspace free:	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

**Sample Integrity - Documentation**      Y or N

1. Sample labels present on bottles:	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2. Container labeling complete:	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3. Sample container label / COC agree:	<input checked="" type="checkbox"/>	<input type="checkbox"/>

**Sample Integrity - Condition**      Y or N

1. Sample recvd within HT:	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2. All containers accounted for:	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3. Condition of sample:	Intact	

**Sample Integrity - Instructions**      Y or N      N/A

1. Analysis requested is clear:	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2. Bottles received for unspecified tests	<input type="checkbox"/>	<input checked="" type="checkbox"/>
3. Sufficient volume recvd for analysis:	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4. Compositing instructions clear:	<input type="checkbox"/>	<input type="checkbox"/>
5. Filtering instructions clear:	<input type="checkbox"/>	<input type="checkbox"/>

Comments

Accutest Laboratories  
V:732.329.0200

2235 US Highway 130  
P: 732.329.3499

Dayton, New Jersey  
www.accutest.com

**JC1982: Chain of Custody**

**Page 2 of 2**